IMPACT ASSESSMENT, MITIGATION AND MONITORING 5.

The Transit Projects Regulation (Ontario Regulation 231/08) Section 9 (2) requires the proponent to prepare an environmental project report that contains the following information, among other requirements:

- "6. The proponent's assessment and evaluation of the impacts that the preferred method of carrying out the transit project and other methods might have on the environment, and the proponent's criteria for assessment and evaluation of those impacts.
- 7. A description of any measures proposed by the proponent for mitigating any negative impacts that the preferred method of carrying out the transit project might have on the environment.
- 8. If mitigation measures are proposed under paragraph 7, a description of the means the proponent proposes to use to monitor or verify their effectiveness."

The purpose of this chapter is to document the potential impacts of the Eglinton Crosstown LRT, to identify mitigation measures and to recommend monitoring activities.

Interactions Between the Undertaking and the Environment 5.1

The environmental factors that may be affected by project facilities/activities were identified using an interactions matrix. The interactions matrix is designed to scope the types and level of significance of environmental effects that may be encountered for this project and the level of detail that may be necessary to address those environmental effects. The interactions matrix considered site-specific environmental conditions and project-specific facilities and activities.

The environmental effects of the Undertaking can be classified under three categories:

- 1. Footprint Impacts These are existing environmental features located within the study area that will potentially be displaced or lost through the introduction of the LRT facility;
- 2. **Construction Impacts** These are potential short-term disruption effects resulting from construction of the LRT facility; and
- 3. Operation and Maintenance Impacts These are potential long-term disruption effects resulting from the operation and maintenance of the LRT facility.

The level of interaction between a facility/activity and an environmental factor can be classified as: "none," "weak," "moderate" and "strong." These terms were defined as follows:

- 1. **None** (blank) no probability of an interaction or the interaction has no significance to society. As a result, no additional discussion and documentation is required in support of this Transit Project Assessment.
- 2. Weak (W)- a low probability of an interaction or the interaction has low significance to society. A general discussion is provided in this section, but given the anticipated low probability and/or significance, no additional commitments or follow up actions are required.
- 3. Moderate (M) a moderate probability of an interaction or the interaction has moderate significance to society. A more detailed discussion accompanied with supporting supplemental analysis and possible mitigation measures and commitments.

4. Strong (S) - a high probability of an interaction or the interaction has a high level of significance to require detailed analysis to quantify the potential impact and the anticipated effect of mitigation measures. Future commitments for elements with strong interactions are addressed.

The interactions matrix helped to establish the scope of the environmental assessment and reveal which project facilities/activities have a significant interaction with environmental factors. The interactions matrix is presented in **Exhibit 174.** The subsequent sections will discuss for each of the environmental effects identified in Exhibit 174, the following topics:

- 1. Describe the potential impacts;
- 2. Identify mitigation measures and residual impacts;
- 3. Describe the monitoring program; and
- 4. Recommend contingency measures, as required.

Exhibit 174 presents a summary of Eglinton Crosstown LRT potential impacts, mitigation measures, monitoring, future work, and contingency plan.

5.2 Monitoring

A monitoring plan will be prepared in accordance with Subsection 9(2)(8) of Ontario Regulation 231/08. The objectives of the monitoring plan will be as follows:

- To augment existing information and databases, where required; 1.
- 2. To determine the accuracy of impact predictions and the effectiveness of environmental protection measures;
- 3. To ensure compliance with federal, provincial and local legislation and regulations; and,
- 4. To ensure that EA commitments, plans and programs are carried out as planned.

These objectives help to determine the types of monitoring to be used including baseline monitoring, implementation monitoring, effectiveness monitoring and compliance monitoring.

5.2.1.1 **Baseline Monitoring**

A considerable amount of baseline information has been collected for the Study Area. At the same time, the level of detail of information and the timeframe involved presents only a snapshot of conditions as they are today. For these reasons, an ongoing monitoring program is required to gain a fuller understanding of baseline conditions within the Study Area.

5.2.1.2 Implementation Monitoring

A plan for implementing prescribed mitigation measures and environmental commitments will be prepared during design. The plan will include a schedule, resources and priorities for implementation. The plan will also serve as a baseline for monitoring the completion of tasks. A review to determine the success of implementation will be conducted on a regular basis. An annual report will be prepared to document the degree of implementation of prescribed measures and set priorities for the following year.

Toronto Transit Commission/City of Toronto EGLINTON CROSSTOWN LIGHT RAIL TRANSIT TRANSIT PROJECT ASSESSMENT **Environmental Project Report**

society. These issues are usually regulated or closely monitored by government agencies and will

5.2.1.3 Effectiveness Monitoring

Effectiveness monitoring will be performed at regular intervals to determine if impact predictions were accurate and if environmental protection measures are effective. If the results of effectiveness monitoring reveal unanticipated effects, contingency measures will be implemented to correct the situation.

Environmental commitments and mitigation measures will usually form the basis of contract documents for construction.

5.2.1.4 Compliance Monitoring

Compliance monitoring will be conducted to ensure that construction activities do not contravene legislation and regulations and are in accordance with contract provisions.

Where standard monitoring procedures are known, they are identified in the following sections. A detailed monitoring plan will be prepared once the design for the Eglinton Crosstown LRT is advanced. Contingency measures, where appropriate, will be addressed as part of the detailed monitoring plan.

Ex							Exhibit 174: Interaction Matrix												
		N	atura	l Envi	ronmer	nt		Em	issio	ns		So	ocio	-Econ	omi	С	Cult	ture	
Environmental Factors Facilities/Activities			Groundwater	Surface Water	Communities/ Ecosystems	Population/Species	Electromagnetic Interference	Air Pollution	Noise	Vibration	Stray Current	Parks and Open Space	Utilities	Businesses Operations	Land Use	Property	Archaeology	Cultural Heritage	Traffic Operations
	LRT Runningway			S									S						
	New Bridge Over Highway 401			S															
	Bridge/Culvert Improvements			S	S	S													
	Intersection Improvements			S	S	S							S			S			
	Road Improvements			S	S	S							S						
	Stations		S			S						S	S		S	S		S	
Footprint Impacts	Stops			W									S						
	Traction Power Substation			W		S						S			S	S		S	
	Emergency Exit Buildings			W		S						S			S	S		S	
	Ventilation Shafts			W		S						S						S	
	Portals	S	S		S	S													
	Work Yards			S	S	S						S							
	Tunnel	S	S										S						
	Bus Terminals			S		S										S			
	Tunnelling/Work Yards	S	S	W					W	W		S	S						
	Cut and Cover Construction	S	S					S	S	S				S					S
	Surface Excavation	S	S	S				S	S	S									
	Clearing and Grubbing			S	S	S		S	S	S									
	Utility Relocation												S						W
Construction Impacts	Roadwork							S	S	S				М					S
	Building Demolition							W	W	W				W				S	
	Soil Removal and Disposal	S		W				W				S							S
	Dewatering		S	W		М							S						
	Reinforcement of Existing Buildings	W				М				S									
	Erosion and Sedimentation Control	S		S				W				S							
	Heavy Equipment Operations and					М		М	S	S		S							



					ronmer	nt		Em	issio	าร		Sc	ocio-	Econor	nic	Culture		Transportation				
Environmental Factors Facilities/Activities			Groundwater	Surface Water	Communities/ Ecosystems	Population/Species	Electromagnetic Interference	Air Pollution	Noise	Vibration	Stray Current	Parks and Open Space	Utilities	Businesses Operations	Property	Archaeology	Cultural Heritage	Traffic Operations	Transit Service	Cyclists	Pedestrians	Navigation
	Maintenance																					
	Traffic Management																	S	S	S	S	
Material Import/Stockpiling Trackwork								W				S						S				
									W	W				S				S				
	Concrete Forming			S		М																
	LRT Operations						М		М	W	М							S	S	М		
	Track and Structure Maintenance																	М	М			
	Stormwater Management			S	W	W																
Operations and	Bus Operations							Μ	М	М									Μ			
Maintenance Impacts	Station Maintenance																		Μ	W		
	Stop Maintenance																		Μ	W		
	Testing of Emergency Equipment								S													
	Snow Removal					W												W				
Level of Interaction: "-" = N	None "W" = weak "M" = Moderate	9	"S" =	Stror	ng									·		•						

5.3 Displacement of Existing Features by LRT Facilities

Development of the Eglinton Crosstown LRT will result in the permanent displacement or loss of the existing features found within the footprint of the new facility. The Eglinton Crosstown LRT will be developed for the most part within the centre median along the existing rights-of-way of Silver Dart Drive, Convair Drive, Commerce Drive and Eglinton Avenue. Where the existing roadway is too narrow to accommodate LRT facilities and potential widening is constrained by development, the LRT will travel underground. The central underground section extends from west of Keele Street to east of Brentcliffe Road. There is a second underground section at the intersection with Don Mills Road and the Don Mills LRT. In the underground sections, footprint impacts are associated with LRT surface facilities including station entrances, traction power substations, ventilation shafts and emergency exit buildings.

Where the existing roadway is currently three lanes wide in each direction, the centre two lanes will be converted to LRT runningway and two lanes of traffic will be maintained in each direction. The sections where road widening will not be required extends from Weston Road to Black Creek Drive and from east of Brentcliffe Road to Kennedy Road. Through these sections, footprint impacts are associated with minor intersection improvements and traction power substations.

Where the roadway is currently two lanes wide in each direction, the roadway will be widened by two lanes to accommodate the LRT runningway within the median and to maintain two lanes of traffic in each direction. The section where road widening is required extends from Pearson International Airport to Weston Road and from Black Creek Drive to west of Keele Street. Through these sections, footprint impacts are associated with new traffic lanes and intersection improvements.

Several bridge/culverts will also be widened to accommodate LRT facilities. Bridge/culvert widening is required at Mimico Creek, Black Creek, West Don River, East Don River and Wilson Brook. No bridge/culvert widening is required at Silver Creek, Humber River and Massey Creek. Footprint impacts are associated with bridge/culvert widening, although no encroachment into the wetted channel is anticipated at bridge/culvert sites. A new bridge will also be constructed over Highway 401 to accommodate the LRT runningway only.

No displacement of existing features will occur during the operations and maintenance phase.

5.3.1 Terrain and Soils

Potential Impacts

The Eglinton Crosstown LRT will have minimum permanent impacts on terrain as LRT facilities will be located primarily within the right-of-way and the vertical profile of Silver Dart Drive, Convair Drive, Commerce Drive and Eglinton Avenue will be maintained. Minimium impact on terrain will occur in underground sections.

A large volume of soil will be displaced by tunnelling and cut-and-cover activities to be carried out at the portal, tunnel and stations. Approximately 1.8 million m³ of soils are expected to be removed. Excavations may generate excess soil that cannot be reused within the project. Excess soil that is stained, odourous, contains debris or has been analysed and found to be contaminated will require management as a waste.

Mitigation

Excess soil will require waste classifications in accordance with regulatory requirements. Regulatory requirements in place at the time of construction and excess materials management guidelines and specifications (e.g. OPSS180) will be used when developing an excess materials management plan.

A Soil and Groundwater Management Strategy will be developed during the design phase.

Monitoring

If excavations or property acquisitions are planned in areas of known or high potential for environmental impacts, additional environmental investigations (e.g. Phase 1 Environmental Site Assessments and Phase 2 Environmental Soil & Groundwater Investigations) will be conducted in accordance with provincial regulatory requirements to assess the environmental site conditions, disposal requirements for soil as well as health and safety requirements. Contaminated soils will be managed in accordance with provincial legislation and regulations including the Ministry of the Environment's Guidelines for Use at Contaminated Sites in Ontario (MOE 1997). This may include management within the right-of-way depending on circumstances.

A monitoring program will be included in the Soil and Groundwater Management Strategy which will be developed during the design phase.

Contingency

A contingency plan will be developed during the design phase where appropriate.

5.3.2 Groundwater

Potential Impacts

It is anticipated that Eglinton Crosstown LRT facilities will not interrupt existing groundwater migration pathways and permanent groundwater dewatering systems will not be used.

Mitigation

Contaminated groundwater will be managed in accordance with provincial legislation and regulations including the Ministry of the Environment's Guidelines for Use at Contaminated Sites in Ontario (MOE 1997). A Soil and Groundwater Management Strategy will be developed during the design phase.

Monitoring

If excavations or property acquisitions are planned in areas of known or high potential for environmental impacts, additional environmental investigations (e.g. Phase 1 Environmental Site Assessments and Phase 2 Environmental Soil & Groundwater Investigations) will be conducted in accordance with provincial regulatory requirements to assess the environmental site conditions, disposal requirements for soil as well as health and safety requirements. Groundwater will be managed in accordance with provincial legislation and regulations including the Ministry of the Environment's Guidelines for Use at Contaminated Sites in Ontario (MOE 1997). This may include management within the right-of-way depending on circumstances.

A monitoring program will be included in the Soil and Groundwater Management Strategy which will be developed during the design phase.

Contingency

A contingency plan will be developed during the design phase where appropriate.

5.3.3 Surface Water

Potential Impacts

At two locations, Humber River and Black Creek, it was determined that the Eglinton Crosstown LRT will be affected by the regional storm event (1 in 500 years) but operations will not be affected by the 100 year storm event. The east and west portal are both located above the flood elevation for the regional storm; therefore, minimum risk of flooding within the portal or tunnel are predicted.

A small drainage channel that originates west of the West Don River Bridge on the north side of Eglinton Avenue and flows easterly into the West Don River will be displaced by the proposed LRT facilities.

Stormwater runoff within most of the Eglinton Avenue right-of-way is conveyed by storm sewers. However, roadway runoff at the west section of the project is conveyed by roadside ditches. Storm runoff from these areas is eventually conveyed to 8 watercourse crossings with the exception of drainage area 1. Storm runoff from the drainage area 1 (west project limit) is collected by storm sewers and conveyed to Renforth Creek /Etobicoke Creek located outside the project limits, and as such there is no creek crossing within this segment (Renforth Drive to Silver Dart) of the project.

Under proposed conditions, the existing storm sewers will continue to discharge to current cross-culverts and trunk sewer systems within the Eglinton Avenue right-of-way, as presently occurs. It is assumed that the proposed roadway drainage within Mimico Creek and Silver Creek watersheds will continue to be conveyed by roadside ditches. The general direction of roadway flow will not be altered and drainage pattern will be maintained. In the west section (west of Martin Grove Road), catchbasins / storm sewers may require relocation as a result of proposed Eglinton Avenue widening. The storm sewers located between Royal York and Weston Road may require hydraulic capacity assessment to ensure that the capacities of these receiving storm sewers are not compromised due to proposed increase in pavement area. At other locations where increase in pavement area is nominal, it is anticipated that the existing storm sewers capacities will not be impacted.

A pavement area analysis was performed to determine the increase in impervious surface as a result of the roadway improvements. It was determined that the proposed roadway improvements will result in a 15-percent increase in pavement area within the study corridor. As a result, the project will not significantly add impermeable areas in the east section of the project. Also, at underground sections there will be no significant increase in the pavement with the exception to portal locations where some roadway widening is anticipated. As such no water quality control measures are warranted on these segments of the LRT.

However, according to the Ministry of the Environment (MOE), any new construction/development must address existing situations and provide the necessary measures to achieve an 'enhanced' level of water quality treatment of stormwater converging into the watercourses that are located within the project area. Due to the limitation of space, it is recommended to provide oil/grit separator (OGS) units to improve the existing situation at all watercourses where water quality is impaired. Where feasible, the project should incorporate water quality control measures by means of permeable paving on future bike lanes/sidewalks and creating more green spaces within the right-of-way. In the west section, a number of stormwater quality control practices were reviewed and assessed for their applicability on this project. Due to the nature of this facility (i.e. linear transportation corridor), limited space within the roadway right-of-way, it was determined that two possible stormwater management measures were applicable for use, namely oil/grit separator systems and grassed swales. The possibility of using wet ponds located in adjacent lands outside the right-of-way (existing /future) should be explored to ensure that the stormwater objectives are effectively addressed. A more detailed evaluation of these measures is required during the design phase.

It is assumed that existing water quality control measures (i.e. roadside ditches within the project corridor) will be maintained. Wherever feasible, opportunities to enhance existing stormwater measures will be explored. Currently water quality controls at Mimico Creek and Silver Creek are achieved by roadside ditches. Where space constraints allow, these roadside ditches should be enhanced by providing a flat bottom width of 0.75 metres. Details including location, length and size of swales will be determined during the design phase.

The drainage system at east Don River Bridge consists of deck drains located at certain intervals on the bridge deck. Stormwater is collected into a single pipe and then discharged through outfall below the deck into the river. It is recommended to modify the current drainage system by directing outlet pipe from deck drain to soak pits. The soak pits can be placed at the bottom of piers. These soak pits will prevent erosion and filter runoff before discharging to the river system. The possibility of installing OGS before discharging to soak pits should be explored during the design phase.

It should be noted that no deck drains exist on other bridges including west Don River Bridge. Storm water drains to catch basins at the abutments and outlet to adjacent roadside ditches before reaching the river. Erosion protection is required at the catch basin outlets to protect the embankment and prevent potential sediments from reaching the river.

Mitigation

LRT operations will be suspended during the regional storm event to prevent potential risks to human health and safety and damage to LRT facilities and vehicles.

The small drainage channel west of the West Don River Bridge on the north side of Eglinton Avenue will need to be realigned or enclosed as it is currently confined by Eglinton Avenue and the adjacent embankment. The treatment for this drainage channel will be determined during the design process in consultation with the TRCA.

Eglinton Crosstown LRT facilities will be located within the TRCA Regulation Limit; therefore, a permit(s) under Ontario Regulation 166/06 – Regulation of Development, Interference with Wetlands and Alterations to Shorelines and Watercourses will be secured from TRCA during the design phase.

A stormwater management plan will be developed during the design phase in accordance with the City of Toronto, city of Mississauga, TRCA and the Ministry of the Environment requirements. Stormwater Control, Mitigation, Erosion and Sediment Control measures shall be enumerated as per Ministry of the Environment's Stormwater Management Design Manual 2003 and City of Toronto's Wet Weather Flow Management Guidelines 2007.

Water quality control for the Eglinton Avenue widening should meet the following stormwater management criteria:

- Provide water quality treatment to offset, as a minimum, the increase in roadway pavement area as a result of roadway widening;
- Any proposed control measures should be sized to provide Level 1 treatment and meet the design requirements of the Ministry of the Environment s Stormwater Management Planning and Design (MOE Manual, 2003); and,
- Provide erosion control, if feasible (Detention runoff for 24 hours from 25 mm storm).

Monitoring

The City of Toronto operates and maintains a network of rainfall gauges. The information is used to determine sewer sizes and the influence of storms of various sizes on the existing sewer system and on streams (floods).

The City collects and analyses water samples from sewers at sewer outfalls, in stream and at the lakefront for a variety of management reasons. Sample results from sewer outlets are used to determine trace and correct the discharge of prohibited pollutants to its sewer systems.

5.3.4 Communities/Ecosystems

An ecological community is composed of a group of organisms or a population of different species, both plant and animal, occupying a particular area. The species present often interact with one another, affecting each other's distribution, abundance, diversity and existence. Human interference can also greatly affect these four interdependent components of a community.

5.3.4.1 Terrestrial

Vegetation communities were classified according to the Ecological Land Classification for Southern Ontario: First Approximation and Its Application (Lee et al. 1998). A total of twenty-five different ecological land classification (ELC) vegetation community types have been identified by LGL along Eglinton Avenue. These communities include: mixed forest (FOM6-1); deciduous forest (FOD2-1, FOD3-1, FOD4, FOD5-1, FOD5-2, FOD5-3, FOD5-8, FOD6-1, FOD6-4, FOD7, FOD7-3 and FOD8); cultural plantation (CUP3); cultural meadow (CUM1-1); cultural thicket (CUT1); cultural savannah (CUS1); cultural woodland (CUW1); deciduous swamp (SWD2-2, SWD4 and SWD4-1); swamp thicket (SWT2-2); meadow marsh (MAM2 and MAM2-2); and, shallow marsh (MAS2-1). The above vegetation communities are considered widespread and common in Ontario and secure globally.

Potential Impacts

The Eglinton Crosstown LRT runningway includes dedicated light rail tracks travelling in both directions along the centreline of Eglinton Avenue, Commerce Boulevard, Convair Drive and Silver Dart Drive between the Pearson International Airport and Kennedy Road. Because the LRT will operate in a dedicated right-of-way in the centre of the road on Eglinton Avenue; the ELC communities will only be impacted along the edge of the vegetation community that is adjacent to the existing road alignment and fragmentation of any ELC community will not occur.

The LRT will be underground through the central section of the overall alignment, from Keele Street to Brentcliffe Road; consequently, vegetation communities along this section will not be affected.

A total of 1.357 hectares of vegetation will be removed along the Eglinton Crosstown LRT corridor. Deciduous forests account for 42.7% (0.579 hectares) of this total. The majority of forest cover to be

removed (0.554 hectares) occurs along the west section of the alignment between Martin Grove Road and Keele Street. The forest parcels that will be affected are generally linear in extent, relatively isolated, and are bordered on their interior side by residential or industrial/commercial development.

The forest communities associated with the Humber River, Black Creek, the West Don, and East Don Rivers are natural, contiguous vegetation communities defined by the valley systems of each of the watercourses. The existing bridge structures at each of the river crossings span the associated watercourse and have sufficient vertical clearance over the vegetation communities that are present under the bridge structure; as a result, impacts to the forest vegetation communities at each of these watercourses are not anticipated.

The remaining vegetation communities to be affected are culturally based and account for 59.6% (0.741 hectares) of the total area lost. The community type and quantity of area to be affected includes: cultural meadows, CUM1-1, 0.469 hectares; cultural woodlands, CUW1, 0.197 hectares: cultural thickets (CUT1) 0.075 hectares; and cultural savannah (CUS1) 0.034 hectares. Thirty-eight individual cultural vegetation communities will be affected; however the quantity of vegetation removal at each community is generally less than 500 square metres. The communities will only be impacted along the edge of the vegetation communities will not occur. All of the vegetation communities that will be affected are presently in a disturbed state as a result of past human disturbances.

Several wetland communities were identified within the Eglinton Crosstown LRT corridor including deciduous swamps, swamp thickets, meadow marshes and shallow marshes; however only two areas are at risk. A small meadow marsh (MAM2) is situated on the north side of Eglinton Avenue, west of Victoria Park Avenue and a linear shallow marsh is located on the south side of Eglinton Avenue immediately west of Renforth Drive. In both situations, the amount of area affected is less than 10 square metres.

The proposed realignment of Wynford Drive to remove the existing grade separation and create a new at grade intersection to the east will result in an encroachment into the East Don River valleylands. The vegetation community in this area is comprised of a high quality dry fresh sugar maple – beech deciduous forest (FOD5-2) that provides slope stabilization and a natural migration corridor along the East Don River. The proposed encroachment will extend over the top of bank in this location and will require a retaining wall or fill slope to support the Wynford Drive road platform. Given the significance of impact in this location, including an encroachment into areas regulated by Toronto and Region Conservation Authority (TRCA) under Ontario Regulation 166/06 and Toronto Ravine and Natural Feature Protection By-law, the realignment of Wynford Drive should be investigated further during design.

The total loss of 1.357 ha of vegetation as a result of this project is considered minor given the disturbed condition of the vegetation, the limited encroachment that will occur in each instance and the magnitude of the project. However, in the cities of Mississauga and Toronto, where vegetation cover is at a premium, every effort must be made to avoid vegetation loss where possible.

Mitigation

Further opportunities to reduce the physical extent of natural areas impacted by the LRT will be investigated during the design process. Notwithstanding, the cumulative total loss of vegetation does represent a significant loss of natural area cover and needs to be addressed. A suitable restoration/compensation plan to accurately reflect this loss will be developed with TRCA and Urban Forestry (RNFP) to address this concern.

The following environmental protection measures designed to reduce or minimize vegetation removals will be considered on a site-specific basis during the design phase:

- Reduce grading requirements to the minimum extent possible;
- Implement local protection measures including guide rails, retaining walls and ditches, where warranted to avoid vegetation removals;
- Identify and protect trees to be retained during construction using a temporary tree protection barrier in accordance with OPSS 565 and the City's Tree Protection Policies. Work zones will be isolated using construction fencing, barrier fencing and silt fencing to avoid accidental vegetation removal;
- Prepare arborist reports, tree protection plans, edge management plans and restoration plans during design to identify site-specific impacts, mitigation and compensation measures to offset vegetation losses and to achieve a net gain in vegetation area, attributes and functions; and,
- Prepare restoration and enhancement plans that will meet or exceed both TRCA and Urban Forestry standards that will offset vegetation losses and achieve a net gain in vegetation area, attributes and functions.

In addition, the City of Toronto Tree Protection Policy and Specifications for Construction Near Trees prohibits the following activities in protection zone areas which are outside the work zones during construction to avoid accidental removal of vegetation:

- No altering of grade by adding fill, excavating, trenching, scraping, dumping or disturbance of any kind within a protection zone area;
- No storage (pocket) of construction materials, equipment, soil, construction waste or debris within a protection zone area;
- No disposal of any liquids e.g. concrete sleuth, gas, oil, paint within a protection zone area;
- No movement of vehicles, equipment or pedestrians within a protection zone area; and
- No parking of vehicles or machinery within a protection zone area.

Protection of natural areas is in part provided by the Ravine & Natural Feature Protection By-law that is defined by and administered through City of Toronto's Urban Forestry. Proposed removal of trees and features within protected areas will be reviewed and subject to approval by City of Toronto's Urban Forestry.

5.3.4.2 Aquatic

Potential Impacts

There are eight watercourses located along the Eglinton Crosstown LRT. In general terms, any project that involves road widening and associated bridge/culvert improvements over a watercourse, drainage

modifications or generation of stormwater runoff has the potential to result in a harmful alteration, disruption or destruction (HADD) of fish habitat.

The Mimico Creek Bridge will be widened by 5.5 metres on each side to accommodate the LRT. This widening can be achieved with no encroachment into the wetted stream channel; therefore, alteration of fish habitat is not anticipated with the implementation of best management practices.

The Silver Creek Culvert is wide enough to accommodate the Eglinton Crosstown LRT; therefore, alteration of fish habitat is not anticipated with the implementation of best management practices.

The Humber River Bridge is wide enough to accommodate the Eglinton Crosstown LRT; therefore, alteration of fish habitat is not anticipated with the implementation of best management practices.

The Black Creek Bridge will be widened by 1.5 metres on each side to accommodate the LRT. This widening can be achieved with no encroachment into the wetted stream channel; therefore, alteration of fish habitat is not anticipated with the implementation of best management practices.

The West Don River Bridge will be widened by 1.0 metre on each side to accommodate the LRT. This widening can be achieved with no encroachment into the wetted stream channel; therefore, alteration of fish habitat is not anticipated with the implementation of best management practices.

The East Don River Bridge will be widened by 1.2 metres on each side to accommodate the LRT. This widening can be achieved with no encroachment into the wetted stream channel; therefore, alteration of fish habitat is not anticipated with the implementation of best management practices.

The Wilson Brook Culvert will be extended by 3.5 metres to the north to accommodate the LRT. This extension can be achieved with no encroachment into the wetted stream channel; therefore, alteration of fish habitat is not anticipated with the implementation of best management practices. Wilson Brook is enclosed downstream of Eglinton Avenue for a distance of approximately 750 metres so a 3.5 metres extension is considered negligible.

The Massey Creek Bridge is wide enough to accommodate the Eglinton Crosstown LRT; therefore, alteration of fish habitat is not anticipated with the implementation of best management practices.

Mitigation

To reduce the potential for alteration of fish habitat, the following best management practices will be implemented:

- Delineate work areas with construction fencing to minimize the area of disturbance;
- Restrict the use of heavy equipment in the watercourse and on watercourse banks;
- Prohibit the use of heavy equipment in the watercourse;
- Place silt fence along stream margins in areas of soil disturbance; .
- Monitor and maintain erosion and sedimentation control measures during construction to ensure their effectiveness;
- Apply seed and mulch, tackifier and/or erosion control blanket in areas of soil disturbance to provide adequate slope protection and long-term slope stabilization; and

Implement good housekeeping practices related to materials storage (pocket)/stockpiling, equipment fuelling/maintenance, etc. during construction.

These environmental protection measures will greatly reduce the potential for adverse effects to fish and fish habitat located along the Eglinton Avenue LRT. The TRCA has a Level III agreement with the Department of Fisheries and Oceans. TRCA staff will review the project in line with TRCA's Level III agreement with Fisheries and Oceans Canada as per Section 35 (1) of the Fisheries Act. TRCA's will assess all components of the project to determine whether there is a potential for the project to result in a Harmful Alteration, Disruption or Destruction of fish habitat (HADD). Where fisheries timing window restrictions apply, TRCA will provide TTC with the necessary information for construction staging purposes. Staff will work with TTC to ensure appropriate mitigation and restoration is achieved during construction.

5.3.5 **Populations/Species**

A population is a group of individuals of the same species located in a particular time and place. Species are of related plants or animals all sharing common attributes. Streetscape trees are included under this environmental factor.

Potential Impacts

The existing land use along the Eglinton Avenue corridor is primarily industrial, commercial, residential or educational/institutional. With the exception of the valley corridors along the Humber River, Black Creek, the West and East Don Rivers, terrestrial wildlife habitat is minimal and the habitat that is present is provided by cultural meadows, cultural thickets, cultural woodlots and isolated forested parcels. Most of the available wildlife habitat that is adjacent to Eglinton Avenue can best be characterized as being of poor quality, low structural diversity and low habitat diversity.

A number of streetscape trees and trees within private properties identified for acquisition may be affected by the placement of fire ventilation shafts, station entrances, emergency exit buildings, traction power substations, bus terminals and the widening of roads to accommodate the LRT.

It is inevitable that some habitat will be lost. A total of 1.357 hectares of habitat will be removed along the Eglinton Crosstown LRT corridor. Deciduous forests account for 42.7% (0.579 hectares) of the total while cultural woodlots, thickets and meadows account for 59.6% (0.741 hectares) of the total area affected. Because the LRT will operate in a dedicated right-of-way in the centre of the road on Eglinton Avenue, only edge habitat will be affected. Fragmentation of any wildlife habitat areas will not occur.

The overall limited capability of the wildlife habitat and the type of species supported by these isolated patches of vegetation reduces the level of significance attributable to the loss. Wildlife species present in these areas are represented primarily by small mammals and small, migratory and resident passerine birds; species that are tolerant of human disturbance. Minor habitat loss will not have any significant long term effects on the existing populations as individuals will adapt and become tolerant of the new conditions.

There are two plant species of concern: Honey locust (Gleditsia triacanthos) and Virginia bluebells (Mertensia virginica). Honey locust was found within the FOD3-1 vegetation community, in the northwest guadrant of the Islington Avenue/Eglinton Avenue intersection. Honey Locust is ranked as S2 (Imperilled) by the Ministry of Natural Resources. Virginia bluebells was found within a FOD4 vegetation community, south of Eglinton Avenue and Leslie Street. Virginia bluebells is ranked as S3 (Vulnerable) by the Ministry of Natural Resources. However, both honey locust and Virginia bluebells are considered to be non-native in the TRCA watershed (TRCA, April 2003) consequently their significance is reduced.

The study area does, however, contain forty-one plant species that are rare to uncommon in the City of Toronto and in the TRCA watershed, including: balsam fir (Abies balsamea), black maple (Acer nigrum), smooth juneberry (Amelanchier laevis), wild columbine (Aquilegia canadensis), Pennsylvania bitter-cress (Cardamine pensylvanica), fibrous rooted sedge (Carex communis), broad-leaved sedge (Carex platyphylla), stellate sedge (Carex rosea), blue cohosh (Caulophyllum thalictroides), Virginia spring beauty (Claytonia virginica), round-leaved hawthorn (Crataegus chrysocarpa), Cockspur thorn (Crataegus crusgalli), marginal wood fern (Dryopteris marginalis), running strawberry-bush (Euonymus obovata), woodland strawberry (Fragaria vesca ssp. americana), cleavers (Galium aparine), spotted crane's-bill (Geranium maculatum), witch-hazel (Hamamelis virginiana), cow-parsnip (Heracleum maximum), butternut (Juglans cinerea), common juniper (Juniperus communis), eastern red cedar (Juniperus virginiana), tamarack (Larix laricina), moonseed (Menispermum canadense), common evening-primrose (Oenothera biennis), ninebark (Physocarpus opulifolius), white spruce (Picea glauca), red pine (Pinus resinosa), old-field cinquefoil (Potentilla simplex), white rattlesnake-root (Prenanthes alba), white oak (Quercus alba), smooth rose (Rosa blanda), swamp rose (Rosa carolina), marsh rose (Rosa palustris), common elderberry (Sambucus nigra ssp. canadensis), early goldenrod (Solidago juncea), marsh fern (Thelypteris palustris var. pubescens), and white trillium (Trillium grandiflorum). Measures will be taken during detail to design to avoid these rare to uncommon plants to the extent possible. Where avoidance is not achievable, plants will be removed from the impact area and transplanted into nearby areas that will be protected from construction.

Three wildlife species recorded in the Eglinton Avenue study area are listed by Committee on the Status of Endangered Wildlife in Canada and regulated under the Canadian Species at Risk Act. The Chimney Swift (Chaetura pelagica) is recognized as a Threatened Species, whereas the milk snake (Lampropeltis triangulum) and map turtle (Graptemys geographica) are listed as Special Concern, Schedule 1. The habitats where these three species were observed are not located in areas that will be affected by this project and as a result, displacement of or disturbance to these species is not anticipated.

The Fish and Wildlife Conservation Act protects three bird species, twelve mammal species and four of the herpetofauna species recorded. Most of the bird species are also protected under the Migratory Birds Convention Act. Eight of the migratory bird species recorded in the study area are also recognized as priority species of conservation concern by Bird Studies Canada for the Toronto region.

All fish species historically recorded within or near the study area are considered to be either very common in Ontario (provincial rank of S5), common (provincial rank of S4) or non-native (provincial rank of SE). One aquatic species, redside dace (Clinostomus elongate) that is classified as Endangered by the Committee on the Status of Species at Risk in Ontario (COSSARO) and by the Committee on the Status of Endangered Wildlife in Canada (COSEWIC) has been observed in the Humber and Don River watersheds. However, none of the historic records for redside dace occur in the vicinity of Eglinton Avenue. Since no inwater work is required at this time, there will be no impact on fish species or populations.

Mitigation

The impacts on wildlife, wildlife habitat resulting from this project are generally considered to be of minor significance; however habitat loss will be required to construct the LRT along the preferred transit alignment. The following environmental protection measures designed to reduce or minimize vegetation removals/wildlife habitat will be considered on a site-specific basis during the design process:

- Reduce grading requirements to the minimum extent possible; •
- Implement local protection measures including guide rails, retaining walls and ditches, where • warranted to avoid vegetation removals;

- Work zones will be isolated using construction fencing, barrier fencing and silt fencing to avoid further encroachment to wildlife habitat;
- Prepare restoration, enhancement and streetscape plans to offset vegetation/habitat losses and to achieve a net gain in vegetation/habitat area, attributes and functions;
- Prepare edge management plans for areas where encroachment on vegetation communities/habitat will occur;
- Bird friendly lighting and design will be incorporated where the LRT crosses valley and stream corridors to reduce the potential for birds to impact buildings; and
- Perform good housekeeping practices related to materials storage (pocket)/stockpiling, equipment fuelling/maintenance, etc. will be implemented during construction.

In addition, the City of Toronto Tree Protection Policy and Specifications for Construction Near Trees prohibits the following activities in the protection zone areas which are outside the work zones during construction:

- No altering of grade by adding fill, excavating, trenching, scraping, dumping or disturbance of any kind within a protection zone area;
- No storage (pocket) of construction materials, equipment, soil, construction waste or debris within a protection zone area;
- No disposal of any liquids e.g. concrete sleuth, gas, oil, paint within a protection zone area;
- No movement of vehicles, equipment or pedestrians within a protection zone area; and
- No parking of vehicles or machinery within a protection zone area.

A total of forty-one plant species that are rare to uncommon were recorded in the study area. Individual occurrences of these species are generally beyond the zone of influence of this project and it is unlikely that they will be disturbed. During the design phase, precise locations for all species located in areas of potential disturbance will be determined and site-specific measures such as avoidance, design modifications, installation of construction fencing and transplanting where appropriate, will be identified to minimize displacement or disturbance effects.

During the design phase, design and construction of underground support columns and retaining wall structures will be considered to facilitate adequate continuous soil tranches within the road right-of-way. Also streetscape tree plantings in continuous soil trenches will be considered during the design phase.

Implementation of the mitigation measures outlined above will minimize or reduce the potential effects and as a result, the Eglinton Crosstown LRT will have no significant adverse effects on wildlife, wildlife habitat or vegetation species/populations.

5.3.6 Parks and Open Space

Potential Impacts

Construction of fire ventilation shafts, station entrances, emergency exit buildings and traction power substations along the Eglinton Crosstown LRT corridor will result in minor encroachment at five parks/parkettes including: St. Hilda's parkette; Ben Nobleman Park; Chaplin parkette; Eglinton Park; and, Howard Talbot Park. The LRT facilities proposed at each park/parkette are presented in **Exhibit 175**.

Exhibit 175: LRT	Facilities Propose
Park/Parkette	
St. Hilda's Parkette	Dufferin Station M
Ben Nobleman Park	Allen Station Vent
Chaplin Parkette	Chaplin Station D
Eglinton Park	Emergency Exit B
Howard Talbot Park	Traction Power Su Entrance, Bayviev

Eglinton Avenue will be widened by one lane in each direction to maintain two lanes of traffic in each direction and to accommodate LRT facilities. Between Martin Grove Road and Scarlett Road, Eglinton Avenue will be widened on the north side within the Richview Corridor. The existing recreational trail located on the south side of Eglinton Avenue between Martin Grove Road and Scarlett Avenue will be maintained in place.

Mitigation

The LRT facilities will be positioned and configured to minimize intrusion into the parks to the extent possible. The LRT facilities will be designed to blend into their surroundings using a context sensitive solution. TTC will consult with City of Toronto Parks, Forestry and Recreation Division during design to mitigate impacts on City of Toronto parks and parkettes located along Eglinton Avenue.

5.3.7 Utilities

Potential Impacts

There are a number of large diameter utilities and pipelines located within the Eglinton Avenue right-ofway. There are also numerous large underground utility chambers throughout, with the majority located at the major intersections. In addition, there is an extensive system of minor storm sewers and combination storm/sanitary sewers along Eglinton Avenue. Similarly, there are watermains located along Eglinton Avenue from 150 millimetre diameter up to 600 millimetre diameter.

Along the north and south sides of Eglinton Avenue, there are Hydro towers west of Martin Grove Road and west of the Highway 427 overpass. Toronto Hydro has poles located along the roads within the LRT corridor and has an extensive system of buried conduit throughout, with large underground chambers at numerous major intersections. Hydro One Networks Inc (Ontario Hydro) has a 115 kV transmission line crossing Eglinton Avenue just east of Yonge Street. Rogers and Telus utility plants are located in shared buried conduit and Enbridge Gas has 100 millimetres and 150 millimetres gas main throughout the LRT corridor. There are also gas mains crossing Eglinton Avenue at various intersections. Bell Canada has an extensive conduit system along Eglinton Avenue, with double conduit systems at a number of locations as well as crossing ducts at intersections.

Many of these utilities and pipelines will be impacted by the Eglinton Crosstown LRT.

Mitigation

Toronto Transit Commission/City of Toronto EGLINTON CROSSTOWN LIGHT RAIL TRANSIT TRANSIT PROJECT ASSESSMENT Environmental Project Report

ed Within Parks and Open Space LRT Facility

lain Entrance

Shaft

Double Vent Shaft

Building #3

ubstation #13, Bayview Station Secondary w Station Vent Shaft

Utilities and pipelines located within the underground section of the Eglinton Crosstown LRT will be avoided to the extent possible through tunneling. In areas of cut and cover construction, small utilities that are not in direct conflict with the LRT facility will be supported and protected during construction. For utilities that are in direct conflict with the LRT facility, or for large utilities that cannot be temporarily supported, relocation will occur. Services will be maintained to the extent possible during relocation and notice of planned service interruptions will be provided to service users prior to interruptions. The location of all plant, potential conflicts and the relocation strategy will be confirmed with service providers during design.

For all utilities that will be relocated, relocation plans and construction activities will be undertaken in accordance with the *Road Rights of Way Act* and with the City's Requirements for the Installation of Services within the City of Toronto Road Allowance or its equivalent in Mississauga.

5.3.8 Property

Potential Impacts

A total of 149 properties are required to accommodate road widening/realignment, LRT alignment, station entrances, emergency exit buildings, vent shafts, and traction power substations. Of the 149 property acquisitions, 45 are full acquisitions and 104 are partial acquisitions, while 88 acquisitions occur of private property and 61 acquisitions occur of public property. The 88 acquisitions of private property include 45 partial acquisitions and 43 full acquisitions. The list of property takings are summarized in **Exhibit 176**.

			Full (F) or Partial	Reason for	Public or Private
	Address	Street Name	(P)	Property Impact	Property
1		Silver Dart Rd	Р	Substation - TPSS 02	Public
2		Silver Dart Rd	Р	Road widening	Public
3		Convair Dr	Р	LRT alignment	Public
4		Convair Dr	Р	LRT alignment	Public
5		Hwy 401	Р	New bridge	Public
6	2882	Matheson Blvd E	Р	LRT alignment	Private
7	2845	Matheson Blvd E	Р	Road widening	Private
8	2901-2911	Matheson Blvd E	Р	Road widening	Private
9	5090	Commerce Blvd	Р	Road widening	Private
10	5080	Commerce Blvd	Р	Road widening	Private
11		Citation Place West edge of Citation Place ROW	Р	Road widening	Public
12	5015	Commerce Blvd	Р	Road widening	Private
13	2780-2800	Skymark Ave	Р	Road widening	Private
14	2885	Eglinton Ave	Р	Road widening	Public

Exhibit 176: List of Property Acquisitions

	Address	Street Name	Full (F) or Partial (P)	Reason for Property Impact	Public or Private Property
15		NW corner of Renforth Dr and Eglinton Ave	P	Road widening	Public
16		North of Eglinton Ave between Renforth Dr and Matheson Blvd	Р	Road widening	Public
17		South of Eglinton Ave between Renforth Dr and Matheson Blvd	Р	Road widening / TPSS 03	Public
18		South of Eglinton Ave between Eglinton Ave and Hardwick Crt	Р	Road widening	Public
19	128	Rangoon Rd	Р	Road widening	Private
20	130	Rangoon Rd	Р	Road widening	Private
21	132	Rangoon Rd	Р	Road widening	Private
22		Open space near Rangoon	Р	Road widening	Public
23		SW corner of Hwy 427 Southbound lane and Eglinton Ave	Р	Road widening	Public
24		SW corner of Martin Grove Rd / Eglinton Ave	Р	Diversion lane	Public
25		SW corner of Martin Grove Rd / Eglinton Ave	Р	Diversion lane	Public
26		NW corner of Martin Grove	Р	Road widening	Public
27		NE corner of Martin Grove	Р	Road widening	Public
28	55	Martin Grove North side of Eglinton, between Martin Grove Rd and Widdicombe Hill Blvd	Ρ	Road widening	Public
29		North side of Eglinton, between Widdicombe Hill Blvd and Kipling Ave	Р	Road widening	Public
30		North side of Eglinton, between Kipling Ave and Wincott Dr	Р	Road widening	Public

					_						,
A	Address	Street Name	Full (F) or Partial (P)	Reason for Property Impact	Public or Private Property		Address	Street Name	Full (F) or Partial (P)	Reason for Property Impact	Public or Private Property
		North side of Eglinton,				49	3582	Eglinton Ave	F	Road widening	Private
		between Wincott Dr and	-			50	3580	Eglinton Ave	F	Road widening	Private
31		Islington Ave	Р	Road widening	Public	51	3578	Eglinton Ave	F	Road widening	Private
		North side of Eglinton, between Islington Ave				52	3576	Eglinton Ave	F	Road widening	Private
32		and Russell Rd	Р	Road widening	Public	53	3574	Eglinton Ave	F	Road widening	Private
		North side of Eglinton,				54	3570	Eglinton Ave	F	Road widening	Private
33		between Islington Ave	Р	Road widening	Public	55	3568	Eglinton Ave	F	Road widening	Private
		North side of Edlinton	-	Road Widening	1 dblic	56	3566	Eglinton Ave	F	Road widening	Private
		between Islington Ave				57	3564	Eglinton Ave	F	Road widening	Private
34		and Russell Rd	Р	Road widening	Public	58	3562	Eglinton Ave	F	Road widening	Private
		North side of Eglinton,				59	3560	Eglinton Ave	F	Road widening	Private
35		and Russell Rd	Р	Road widening	Public	60	3558	Eglinton Ave	F	Road widening	Private
		North side of Ealinton.				61	3556	Eglinton Ave	F	Road widening	Private
		between Islington Ave				62	1	Bijou Walk	F	Road widening	Private
36		and Russell Rd	Р	Road widening	Public	63	3	Bijou Walk	F	Road widening	Private
		North side of Eglinton, between Islington Ave				64	5	Bijou Walk	F	Road widening	Private
37		and Russell Rd	Р	Road widening	Public	65	7	Bijou Walk	F	Road widening	Private
38	4400	Eglinton Ave	Р	Road widening	Public	66	9	Bijou Walk	F	Road widening	Private
		SE corner of Islington		Substation -		67	11	Bijou Walk	F	Road widening	Private
39		Ave and Eglinton Ave W	Р	TPSS 06	Public			NE corner of Pearen St		Descharidanian	Driverte
40		SE corner of Eglinton	D	Pood widoning	Public	68		and Eglinton Ave	P	Road widening	Private
40		SW corper of Eglipton	I	Road widening	1 dblic	69		and Weston Rd	Р	Road widening	Private
41		Ave and Royal York Rd	Р	Road widening	Public	70	3561	Eglinton Ave	Р	Road widening	Private
42	4200	Eglinton Ave	Р	Road widening	Public	71	3559	Eglinton Ave	Р	Road widening	Private
		NW corner of Richview				72	3549	Eglinton Ave	Р	Road widening	Private
43		Rd and Eglinton Ave	Р	Road widening	Public	73	3547	Eglinton Ave	Р	Road widening	Private
		Entrance to Plant World				74	3543	Eglinton Ave	Р	Road widening	Private
		Richview Rd and				75	3533	Eglinton Ave	F	Road widening	Private
44		EgInton Ave	Р	Road widening	Public	76	3531	Eglinton Ave	Р	Road widening	Private
45	125	La Rose Ave	Р	Road widening	Public	77	1148	Weston Rd	F	Road widening	Private
46	3588	Eglinton Ave	F	Road widening	Private	78	1	Hollis St	Р	Road widening	Public
47	3586	Eglinton Ave	F	Road widening	Private	79	1156-1160	Weston Rd	F	Road widening	Private
48	3584	Eglinton Ave	F	Road widening	Private	80	1162	Weston Rd	F	Road widening	Private

	Address	Street Name	Full (F) or Partial	Reason for Property Impact	Public or Private Property	
81	1168	Weston Rd	P	Road widening	Private	90
82	1151	Weston Rd	Р	Road widening	Private	9
83	2800	Eglinton Ave	Р	Widening due to portal	Public	10
84	2700	Eglinton Ave	Р	Widening due to portal	Public	10
85	2690	Eglinton Ave W	P	Secondary Entrance / Fire Vent	Public	10
				Main Entrance / Substation - TPSS 09		10
86	111	Yore Rd	F	Bus terminal	Private	10
87	2660	Eglinton Ave W	Р	Fire Vent	Public	
88	2615	Eglinton Ave W	Р	Secondary Entrance / Fire Vent	Private	10
89	2330	Eglinton Ave W	Р	2 Fire Vents Secondary Entrance Station box	Private	10
90		Pail Corridor	P	Main Entrance (partial) plus Tunnel between Main Entrance	Public	10 10 11
90			F	Main Entranco	FUDIIC	11
91		Rd & Eglinton Ave W	F	and Bus loop	Public	
92	1854	Eglinton Ave W	F	Fire Vent	Private	11
93	1804-1808	Eglinton Ave W	Р	Substation - TPSS 10 / 2 Fire Vents	Private	11
94	1815 - 1817	Eglinton Ave W	Р	Main Entrance (partial)	Private	11
95	1606	Eglinton Ave W	F	Fire Vent	Private	
96	1574	Eglinton Ave W	F	Secondary Entrance	Private	11
97	1609	Eglinton Ave W	Р	Secondary Entrance / Fire Vent	Public	11

	Adduces		Ful P
	Address		
98	15/3-15/5	Eglinton Ave W	
99	1557	NE corner of Park Hill	
100		Rd & Eglinton Ave W	
101		NW corner of Allen Rd W & Eglinton Ave W	
102	1435	Eglinton Ave W	
103	1435	Eglinton Avenue West	
104		SE corner Everden Ave & Eglinton Ave W	
105		SW corner Glen Cedar & Eglinton Ave W	
106	880	Eglinton Ave W	
107	842	Eglinton Ave W	
108	823-825	Eglinton Ave W	
109	821	Eglinton Ave W	
110	576	Eglinton Ave W	
111	574	Eglinton Ave W	
112	550	Eglinton Ave W	
113		SE corner of Chaplin Cres and Eglinton Ave W	
114	643	Eglinton Ave W	
115	1024 + 1024A	Avenue Rd.	
116	284	Eglinton Ave W	
117	1021	Avenue Rd.	

III (F) or Partial (P)	Reason for Property Impact	Public or Private Property
F	Main Entrance	Private
F	Fire Vent	Private
Р	Fire Vent	Public
Р	Emergency Exit	Public
Р	Automatic Entrance / Fire Vent	Public
	Automatic Entrance	
Ρ	Fire Vent	Public
F	Emergency exit building (# 2)	Public
F	Fire Vent	Private
F	Main Entrance / Substation - TPSS 11 / Fire Vent	Private
Р	Secondary Entrance	Private
F	Fire Vent	Private
Р	2 Fire Vents	Public
F	Main Entrance	Private
Ρ	Secondary Entrance / 2 Fire Vents	Private
P	Secondary Entrance	Public
Ρ	Secondary Entrance (partial)	Public
F	Main Entrance / Fire Vent	Private
F	Fire Vent	Private
Р	Secondary Entrance	Private

	Address	Street Name	Full (F) or Partial (P)	Reason for Property Impact	Public or Private Property
118	275	Eglinton Ave W	P	Fire Vent	Private
119	180	Eglinton Ave W	Р	Emergency exit building (# 3)	Public
120	1 to 73	Eglinton Ave W	Р	Substation - TPSS 12 / 2 Fire Vents / Emergency Exit	Public
121	30	Eglinton Ave E	F	2 Fire Vents	Private
122	123	Eglinton Ave E	Р	Emergency exit building (# 4) – parking	Public
123	223	Eglinton Ave E	Р	Fire Vent	Public
124	256	Eglinton Avenue East	F	Main Entrance	Private
125	280	Eglinton Ave E	F	Secondary entrance	Private
126	282	Eglinton Ave E	F	2 Fire Vents	Private
127	485	Eglinton Ave E	Р	Emergency exit building (# 5) – parking	Private
128	656	Eglinton Ave E	Р	Main Entrance / 2 Fire Vents	Private
129	660	Eglinton Ave E	Р	Secondary entrance / Fire Vent	Private
130	635	Eglinton Ave E	Р	Secondary entrance / Substation - TPSS 13 / Fire Vent	Public
131	276	Rumsey Road	Р	Emergency Exit building (#6) - parking	Private
132	250-256	Laird Dr	F	Main Entrance / 2 Fire Vents	Private
133	825 to 845	Eglinton Ave E	P	Secondary entrance / 2 Fire Vents	Private
134	939	Eglinton Ave E	P	Road widening	Private

	Address	Street Name	Full (F) or Partial (P)	Reason for Property Impact	Public or Private Property
125		SW corner of Eglinton Avenue and Don River	D	Launch shaft &	Public
135		Gonvois Dr	Г D	Pood widoning	Privata
100	1000		Г		Private
137	1200	Eglinton Ave E	Р	Road widening	Private
138		NE corner of Eglinton Ave and Don Mills Rd	Р	Bus terminal	Public
139	35	Wynford Heights Crt	Р	Wynford Dr re- alignment	Private
140	-	Wynford Heights Crt	Р	Wynford Dr re- alignment	Public
141	1880	Edinton Ave E	Р	Road widening & North side U- turn	Private
142	1891	Eglinton Ave E	P	South side LI-turn	Private
143	1896	Eglinton Ave E	P	Road widening	Private
140	1807	Eglinton Avo E	P	Road widening Road widening	Privato
144	1097		Г		Private
145	1900	Eglinton Ave E	Р	Road widening	Private
146	1960	Eglinton Ave E	Р	Substation - TPSS 18	Private
147	2206	Eglinton Ave E	Р	RT alignment	Private
148	2201	Eglinton Avenue East	Р	Right turn lane	Private
149	2222	Eglinton Ave E	Р	Right turn lane	Public

Mitigation

Property acquisition required for this project will be undertaken by the City of Toronto on behalf of the TTC. In acquiring property, the City of Toronto balances community need and the rights of the property owner. The objective is to ensure that individual rights are respected and protected and to provide fair compensation within the framework of the Expropriations Act for any property acquired or affected by civic projects. The acquisition process emphasizes negotiation and the achievement of a mutually satisfactory agreement between the City and the owner. If necessary, in order to protect the ability to proceed with the Eglinton Crosstown LRT project, expropriation may be required to acquire the necessary property. In general, property acquisition uses the following steps:

- The City of Toronto contacts the property owner to indicate its interest in the property and to • identify issues and concerns;
- The City conducts legal surveys, appraisals, environmental site assessments and other ٠ property-related assessments;

- An offering price is discussed. If a tentative agreement is reached, an Offer to Sell is signed by the owner. The Offer is then sent to City of Toronto Council for approval and acceptance;
- If discussions do not result in an agreement, the City initiates the expropriations procedures. The expropriation process may be initiated while negotiations are occurring;
- If expropriation is pursued, the owner has a right to an independent inquiry called a Hearing of Necessity, which determines whether the property requirements are fair, sound and reasonably necessary:
- The City approves the settlement/expropriation, and acquires the property; and
- If expropriated, the owner has the right to have compensation payable referred to arbitration at the Ontario Municipal Board.

The objective of the *Expropriations Act* is to put tenants and property owners in the same position that they were in prior to the beginning of the civic project directly affecting their properties. Compensation is determined having regard for the *Expropriations Act* by experienced, gualified appraisers and other experts. Compensation is generally based on three factors:

- Market Value Market value is defined as "the amount that the land will be expected to realize if sold on the open market by a willing seller to a willing buyer." The date of expropriation is usually determined as the date to determine market value.
- Damages Attributable to Disturbance These refer to the economic loss suffered by an owner as a result of having to vacate expropriated property. This can include moving costs, temporary accommodation, redundant furninshings, or loss of business revenues and profitability. Compensation for damages of this type is determined after expropriation.
- Damages for Injurious Affection Injurious affection is sometimes referred to as "consequential damages." It has very precise and limited applications according to the law and can include items such as reduced market value and increased business operating expenses. Injurious affection is usually determined after expropriation.

The total property acquisition process and resulting compensation is intended to leave the affected owner "whole" and thereby mitigating the negative impact.

Partial takings have been identified for a further 49 properties. These include underground easements and surface facilities such as station entrances. TTC and the City of Toronto will conduct a Property Protection Study during the design of the Eglinton Crosstown LRT, which will determine detailed property requirements, including temporary construction easements. The acquisition of these properties will follow the same principles described above.

Where properties to be displaced form a continuous development of retail/business streetscape, the displacement TTC facility will ensure the continuation of the existing street wall (with respect to height setback and general architectural characteristics).

Any brownfield sites will be managed in accordance with the Ontario Regulation 153/04 and Ontario Regulation 511/09 once it comes into force. A Designated Subtances Surveys for any buildings or structures which require demolition will be undertaken during the design phase.

5.3.9 Archaeology

Potential Impacts

A Stage 1 and 2 archaeological assessment was conducted in accordance with the Ministry of Culture's Archaeological Assessment Technical Guidelines (MCzCR 1993).

The Stage 1 archaeological assessment involved an evaluation of archaeological potential based on a review of geographic, land use and historical information and a field inspection of the Eglinton Crosstown LRT corridor. The Stage 1 Archaeological Assessment indicated high potential for the recovery of archaeological material along the Eglinton Crosstown LRT corridor. This was based on the confirmed presence of nine listed² and designated heritage properties along the corridor. Additionally, a total of five registered archaeological sites had been encountered within a one-kilometre radius of the Eglinton Crosstown LRT corridor, and four registered archaeological sites within a two-kilometre radius of the Airport Link study area, indicating that significant archaeological resources could be encountered within their limits.

The subject lands are bisected by Mimico Creek, the Humber River, Black Creek, the West Don River, the East Don River, and Massey Creek, further supporting the potential for locating Aboriginal artifactual remains within undisturbed portions of the study area limits. A review of the subject lands within the Tremaine's Map of the County of York, Canada West, 1860 and The 1878 Illustrated Historical Atlas of York County and the township of West Gwillimbury & Town of Bradford in the County of Simcoe indicated that approximately 90 properties and between 15 to 23 homesteads and structures are illustrated within or directly adjacent to its limits. The subject lands encompasses the sites of several historic railroads, one historic post office, two historic school houses, one urban concentration, a church and many orchards. Two historic cemeteries, Richview Memorial Cemetery (also known as, Union Chapel Cemetery plus Willow Grove and McFarlane Cemeteries) established in 1853 and Prospect Cemetery established 1890, are situated alongside the Eglinton Crosstown LRT study corridor. As such, the research supported high potential for locating Euro-Canadian artifactual remains within undisturbed portions of the subject lands. In light of all of this information, it was recommended that a Stage 2 archaeological assessment be undertaken in all undisturbed locations.

Consequently, a Stage 2 archaeological assessment was conducted and consisted of a test-pit survey as well as the identification of disturbed locations within the footprint of the Eglinton Crosstown LRT. Encountered disturbances included paved roadways and highway intersections, paved sidewalks and bicycle paths, paved and gravel shoulders, paved driveways, grading from previous and recent development activities, wet drainage ditches, sloping terrain from embankment constructions, and underground utilities. Physiographic factors affecting archaeological potential consisted of sloping terrain. Due to the low archaeological potential classification of these areas, systematic survey was not warranted nor was it undertaken. Furthermore, two portions of the proposed alignment along Commerce Drive and Convair Drive, specifically from north of STA 53+180 to 53+340, and STA 53+520 to 53+600, fell within private ownership and permission to enter was not granted. As such, these lands will require assessment prior to any intrusive activity.

² "Listed" is a term used for properties for which the Toronto City Council has adopted a recommendation to be included on the Inventory. The recommendations are based on criteria that relate to architecture, history, and neighbourhood context. Their inclusion on the Inventory is a clear statement that the City would like to see the heritage attributes of these properties preserved. If designated, these structures must be preserved (www.toronto.ca)

The remaining undisturbed portions of the subject lands that could be tested were comprised of grass and fallow margins. Test-pit survey was undertaken at five metre intervals, based on the established high potential for the recovery of archaeological resources. Despite careful scrutiny, no archaeological resources were encountered during the Stage 2 field assessment and, thus, with the exception of the unassessed segments, the remainder of the Eglinton Crosstown LRT is considered clear of further archaeological concern.

Mitigation

No mitigation measures are proposed since no archaeological resources are known to occur within the footprint of Eglinton Crosstown LRT facilities. The Stage 1 and 2 Archaeological Assessment reports were filed with the Ministry of Culture in compliance with Section 65 (1) of the *Ontario Heritage Act*. The Ministry reviews reports to ensure that the licensee has met the terms and conditions of the licence and archaeological resources have been identified and documented according to the standards and guidelines set by the ministry, ensuring the conservation, protection and preservation of the heritage of Ontario. Confirmation that the Ministry of Culture has entered these reports into the provincial register of reports and that the Ministry of Culture has no further archaeological concerns with this project was received on December 21, 2009.

A Stage 2 archaeological assessment will be conducted on properties where permission to enter were not obtained during the Transit Project Assessment.

Monitoring and Contingency

The following monitoring and contingency measures are recommended by the Ministry of Culture:

- 1. Should previously unknown or unassessed deeply buried archaeological resources be uncovered during development, they may be a new archaeological site and therefore subject to Section 48 (1) of the *Ontario Heritage Act*. The proponent or person discovering the archaeological resources must cease alteration of the site immediately and engage a licensed archaeologist to carry out archaeological fieldwork, in compliance with Section 48 (1) of the *Ontario Heritage Act*. The office of the Heritage Operations Unit, Ministry of Culture (416-314-7146) should be contacted immediately.
- 2. Any person discovering human remains must immediately notify the office of the Heritage Operations Unit, Ministry of Culture (416-314-7146), the police or coroner, and the Registrar of Cemeteries, Cemeteries Regulation Unit, Ministry of Government Services (416-326-8404).

Consultation with stakeholders, including First Nations, will be initiated in the event that archaeological resources or human remains are discovered in accordance with Ministry of Culture practices.

5.3.10 Cultural Heritage

Potential Impacts

Generally changes due to transit infrastructure projects have the potential to adversely affect cultural heritage landscapes and built heritage resources by displacement and/or disruption during and after construction. Built heritage and/or cultural heritage landscapes may experience displacement or direct impacts, i.e., removal, if they are located within the rights-of-way of the undertaking. There may also be potential for disruption or indirect impacts to cultural heritage resources by the introduction of physical, visual, audible or atmospheric elements that are not in keeping with their character and, or setting. Both direct and indirect effects will occur as a result of the Eglinton Crosstown LRT.

The potential impacts of the Eglinton Crosstown LRT on cultural heritage resources are presented in **Exhibit 180**. The Eglinton Crosstown LRT will not encroach on either of the two cemeteries located within the project limits, the Richview Cemetery or the Prospect Cemetery. Station entrances will displace 1950's commercial buildings at Oakwood Station and the 20th Century commercial buildings at Mount Pleasant Station. Placement of station entrances at Keele Station, Mount Pleasant Station and Bayview Station will indirectly affect the cultural heritage landscape around the York Memorial School, 300 Eglinton Avenue East (a Uno Prii designed building) and Sunnybrook Plaza, the first strip mall built in the City of Toronto.

Mitigation

Transit improvements should be managed in such a way that its impact is sympathetic with the value of the resources. When the nature of the undertaking is such that adverse impacts are unavoidable it may be necessary to implement management or mitigation strategies that alleviate the deleterious effects to cultural heritage resource. Mitigation is the process of lessening or negating anticipated adverse impacts to cultural heritage resources, It may include such actions as avoidance, monitoring, protection, relocation, documentation, salvage, remedial landscaping, etc., and may be a temporary or permanent action.

The measures identified to mitigate potential impacts of the Eglinton Crosstown LRT on cultural heritage resources are presented in **Exhibit 177.** Documentation through the use of historical mapping and photography of the affected buildings will be conducted prior to removal in accordance with the requirements of the City of Toronto Heritage Preservation Services requirements. LRT Station entrances will be designed using context sensitive solutions in consultation with the City of Toronto, Heritage Preservation Services.

Exhibit 177: Cultural Heritage Impacts and Mitigation Measuresand Potential ImpactMitigation Recommendation

Location and Potential Impact	
Weston Road	
1) Displacement:	1) rec
Row of residences, N. Side of Eglinton Ave. West 3556-3588	CO SC
2) Disruption:	2) bis
1151 Weston Road, Bank of Nova Scotia site context.	an He co
Keele Street	
Disruption:	Pr im
Road widening on the west side of the Keele Street and placement of an emergency exit in front of York Memorial Collegiate, a municipally designated property under the <i>Ontario Heritage Act</i> .	He thi Se
Dufferin Street	

Toronto Transit Commission/City of Toronto EGLINTON CROSSTOWN LIGHT RAIL TRANSIT TRANSIT PROJECT ASSESSMENT Environmental Project Report

City of Toronto Heritage Preservation Services will equire a Heritage Impact Statement (HIA) for the ollection of residences to be removed after creening.

Document the change with photographs and storical mapping prior to intersection modifications and prepare a brief area history. Consult with eritage Preservation Services regarding report ontent prior to commencement.

repare a sympathetic design that recognizes the aportance of the viewscape in front of the building. A eritage Impact Statement (HIA) will be required for is site by City of Toronto Heritage Preservation ervices.

Location and Potential Impact	Mitigation Recommendation
Displacement: Loss of a 1947 commercial buildings for fire vent placement: 1850-1854 Eglinton Avenue West	Document the change in the streetscape with photographs and historical mapping and prepare a brief area history prior to removal of the buildings. Consult with Heritage Preservation Services regarding report content prior to commencement.
Oakwood Avenue	
Displacement: Loss of 1950's commercial buildings for station/exit placement. Addresses displaced include: 1557; 1573-75; 1574-76; and, 1606 Eglinton Avenue West.	Document the change in the streetscape with photographs and historical mapping and prepare a brief area history prior to removal of the buildings. Consult with Heritage Preservation Services regarding report content prior to commencement.
Mount Pleasant Road	
 Displacement: The 20th century commercial building at 794 Mount Pleasant Road will be removed. Disruption: 	1) City of Toronto Heritage Preservation Services will require a Heritage Impact Statement (HIA). Adaptive reuse of the building will be considered as a station entrance will be studied further during design. Photo document of the building and site prior to removal, if this is the preferred option.
The station development will result in a change in the context adjacent the Uno Prii designed apartment building, 300 Eglinton Avenue East is listed on the City of Toronto Inventory of Heritage Properties.	2) City of Toronto Heritage Preservation Services will require a Heritage Impact Statement (HIA) for the site.
Bayview Avenue	
Disruption: Change in context due to new secondary entrance at Sunnybrook Plaza, 600 Eglinton Avenue East. Site listed on City of Toronto Modernist Inventory.	City of Toronto Heritage Preservation Services will require a Heritage Impact Statement (HIA) for the site after screening.

5.3.11 Navigable Waters

Potential Impacts

The Humber River, West Don River and East Don River have been identified as navigable waters by Transport Canada, Navigable Waters Protection Agency. The Navigable Waters Protection Act (NWPA) regulates any works proposed in, upon, over, under, through or across any navigable waterway in Canada. Modifications to the Humber River Bridge, including adding an LRT facility, and the West Don River Bridge and East Don River Bridge, including adding an LRT facility and associated bridge widening and possible reinforcement, may require an approval under the NWPA.

Mitigation

TTC will prepare and submit an application for approval under the Navigable Waters Protection Act during detail design. The application will include mitigation measures designed to maintain navigation clearances at these bridges and maintain navigation on these waterways during construction. Measures to mitigate potential impacts on navigable waters may include the following:

- Bridge modifications shall not encroach on the existing horizontal or vertical navigation • clearances.
- The navigation channel shall be maintained at all times during construction. Boat traffic shall be • allowed uninterrupted passage through the work site at all time, and assisted as necessary. The navigation channel shall not be altered in any way during construction.
- Sufficient signage shall be erected upstream and downstream of the work area to alert boat • traffic of construction activities.
- A temporary containment system shall be installed under the bridges to prevent any materials • from falling off the bridge into the navigation channel.
- No person shall permit any tools, equipment, vehicles, temporary structures or parts thereof ٠ used or maintained for the purpose of building or placing a work in navigable water to remain in such water after the completion of the project.

NWPA approval will be obtained by TTC prior to construction at navigable waters.

5.4 **Construction Impacts**

The runningway will be tunnelled through the underground sections. As a result, impacts are predicted to be negligible. Stations and special track work areas will be constructed by cut-and-cover method. Station entrances, emergency exit buildings, ventilation shafts, and traction power substations will be constructed following standard at surface construction methods with excavation activities for connection to the underground sections. Bridge modifications are not anticipated to involve in-water construction work.

5.4.1 Terrain and Soils

Potential Impacts

This project will result in the displacement of approximately 1.8 million m³ of surplus excavated material generated by tunnelling and cut-and-cover construction at the portals, tunnel and stations. This material will be hauled by truck for disposal off-site. A total of 160 trucks per day will be required to remove this material, the equivalent of one truck every four minutes. On busy urban streets such as Eglinton Avenue and the major north-south arterials that already carry a large proportion of truck traffic, the addition of one truck every four minutes is considered a neglibible increase in truck traffic. Truck haul routes will be identified during detail design as part of traffic management plans. Trucks hauling materials associated with the Eglinton Crosstown LRT will be restricted from entering residential areas through contract provisions.

There is potential for encountering buildings with deep foundations within the underground section of the Eglinton Crosstown LRT. Therefore, where necessary, underpinning will be implemented to minimize the potential for building settlement/structural stress due to tunnelling, piling and dewatering.

Mitigation

A review of historical records identified several areas to have known soil or groundwater impacts from previous and current operations. Phase 1 Environmental Site Assessments and Phase 2 Environmental Soil & Groundwater Investigations will be conducted in areas where excavation, road widening and property acquisitions will take place and have known or high potential for environmental impacts. This is to meet provincial regulatory requirements to assess the environmental site conditions, disposal requirements for soil/groundwater as well as health and safety requirements.

An excess materials management plan will be implemented in accordance to regulatory requirements during construction. Management of contaminated material encountered will follow MOE Standards, Ontario Regulation 153/04 and Ontario Provincial Standards Specification 180 – General Specification for the Management and Disposal of Excess Material.

Monitoring

This baseline monitoring will be undertaken in accordance with the Ontario Environmental Protection Act and will be documented in the Geotechnical Baseline Report, which will provide the necessary information for the handling and disposing of excess soil. The disposal of contaminated materials will be directed to an MOE approved soil treatment site or waste disposal site. The monitoring of these facilities is the jurisdiction of the Ministry of the Environment of Ontario.

Prior to construction, TTC will require the contractor to submit the name, location and type of license of the designated soil disposal sites (as issued by MOE).

Prior to the commencement of construction operations, separate nstrumentation readings will be taken to provide a pre-condition survey for all buildings to assess current conditions.

Monitoring during construction will include ground settlement measurements, inclinometers and surface monitoring points for structures. Monitoring is undertaken on a weekly basis during active excavation. This moinotiring schedule is reduced to every three months for up to a year following backfilling.

The monitoring program will include revie wand alert levels. If instrument readings exceed "review" levels, TTC and its contractor will jointly assess the necessity of altering the method, rate or sequence of construction. At "alert" levels, TTC can order construction operations to cease until the necessary mitigation measures are undertaken.

Following construction, TTC and its contractors will arrange for a joint post-construction inspection of buildings/structures and utilities with the respective Owners. The results of these surveys will be compared with the pre-construction surveys.

TTC will monitor horizontal and vertical movements and tilt of adjacent structures and utilities on a daily basis during active excavation or backfilling. In the event that instrument readings reach "alert" levels, (as to be defined on a structure-specific bais in the construction contract documents), TTC site supervisory staff oil order construction operations to cease and take necessary actions to mitigate unacceptable

movements, including, but not limited to alternative construction methods or construction equipment and/or additional support/protection measures.

Contingency

In the event that a property owner submits a claim for property damage, TTC will conduct further investigations and, if appropriate, will negotiate a settlement.

5.4.2 Groundwater

Potential Impacts

The groundwater table is likely to be above the base of the proposed depth of alignment at many areas within the underground section of the Eglinton Crosstown LRT. Therefore, seepage cut-off and depressurization of aquifers will be required to control groundwater, stabilize the base of excavations and tunneling. It can be expected that groundwater will need to be controlled by methods such as pumping from sumps, educators or well points or in some cases by deep well dewatering systems. For the majority of the underground section of the LRT, the base of excavation/tunneling is likely to be in glaciolacustrine (silt, clay and sand) deposists of the Thorncliffe Formation; therefore, care must be taken to prevent the removal of fine soil particles during pumping.

Mitigation

There is potential to encounter contaminated groundwater. Further hydrogeologic assessments will be conducted at locations requiring dewatering to estimate discharge rates, predict impacts and evaluate treatment/discharge options. These studies are also needed to support the Ministry of the Environment's Permit to Take Water (PTTW) applications.

There is potential for buildings to have foundations built below the local water table, and a potential exists for these foundations to be affected by dewatering. Further investigation to determine the radius of influence of any required dewatering will be necessary to fully consider the impacts to nearby structures and infrastructure. Further mitigation plans will be developed during the design phase.

Monitoring

Most cut-and-cover operations for the construction of stations will require dewatering to reduce groundwater pressure and lower groundwater levels to allow for construction on stable undisturbed and substantially dry subgrade. To avoid adverse effects sush as settlement of buildings two tupes of monitoring are employed:

- 1. Amount of Total Suspended Solids in the Dewatering Effluent Unless required to be more stringent by the geotechnical engineer during design, is limited to 5 parts per million Total
- 2. Ground Water Monitoring Wells (piezometers) The measurement of groundwater levels are taken a minimum of 2 sets of readings prior to the start of dewatering will be taken. The monitoring of water levels will be conducted on a daily basis while dewatering systems remaining in operation. levels, TTC and its contractor will joinly assess the necessity of altering the method, rate or

Toronto Transit Commission/City of Toronto EGLINTON CROSSTOWN LIGHT RAIL TRANSIT TRANSIT PROJECT ASSESSMENT **Environmental Project Report**

Suspended Solids. This monitoring is undertaken 12 hours after the commencement of pumping.

from piezometers generally situated within areas of excavation. As part of the baseline monitoring, The monitoring program will include review and alert levels. If instrument readings exceed "review"

sequence of construction. At "alert" groundwater levels, TTC can order construction operations to cease until the necessary mitigation measures are undertaken.

Recognizing the urban environment within which this project occurs, the disposal of groundwater will be to an existing storm or sanitary sewer and will be arranged by the contractor. The conditions and resulting monitoring and reporting requirements will be th subject of a water disposal permit with the City of Toronto and monitoring will include sampling and analysis carried out in accordance with the procedures, modified or validated by the City, as set out in the City document entitled "Quality System, Analytical Methods Manual" as it may be amended from time to time. [Amended 2002-10-31 by By-law No. 855-2002]

5.4.3 Surface Water

Impacts

In-stream works are not proposed at any of the crossings therefore changes to the fluvial integrity of the channel are not anticipated. Measures will be put in place during all phases of construction to minimize disturbance to watercourses from inputs of soil, concrete dust/washwaterand other materials. Measures will be included in the design process to ensure that storm water impacts will be minimal and that water features are protected as part of the proposed construction.

In areas where construction sites or roadways are located in proximity to watercourses, the use of minor grading to direct surface runoff away from the aguatic habitats is recommended. This generally consists of the slope leading to a very shallow swale created by a low ridge of topsoil. The vegetative swale is configured to direct surface runoff along the swale back away from the edge.

If uncontrolled, the construction activities associated with Eglinton Avenue widening could result in increased rates of erosion and sedimentation within and adjacent to the site area and tributaries to three major watersheds which include Mimico Creek, Humber River and the Don River. The potential environmental impacts from increased erosion and sedimentation include: degradation of water quality: destruction of fisheries habitat; and, increased flooding potential. Erosion and sedimentation processes are typically accelerated due to construction activities.

Mitigation

In order to prevent and minimize the release of sediment to watercourses, various sediment and erosion control measures will be implemented during LRT construction, such as:

- Environmental protection measures will be installed in areas adjacent to watercourses. Erosion and sediment control measures will be prepared in accordance with the TRCA Guidelines "Erosion and Sediment Control for Urban Construction Sites";
- During the design process, a sediment and erosion control plan will be developed utilizing Best Management Practices;
- Any required structure work will be isolated from the open watercourse and conducted "in the ٠ dry";
- Any required dewatering operations for structure work should be outlet onto a grassed area at least 30m from the watercourse, a settling pond, and/or wetland filter bag. A Permit to Take Water application will be submitted to the Ministry of the Environment to undertake any dewatering that is over 50,000 L/day;

- Any effluents derived from concrete cutting/grinding/forming will be collected and managed in accordance to provincial standard specifications;
- Following the completion of final site grading and topsoil application, a roadside seed mixture • (Ontario Provincial Standard Specification, OPSS 572) and perennial rye grass nurse crop seed should be applied to all exposed soils. For exposed soils located adjacent to watercourses, immediately following seed application a straw erosion control blanket (installed as per OPSS 572.05.07, 572.05.08 and 572.07.04.04) should also be installed along the embankment slopes;
- All necessary steps should be taken to prevent dust nuisance resulting from Contractors' work. • Dust suppression will be undertaken as per OPSS 501 and 506;
- In order to mitigate the potential impacts associated with excess material storage (pocket), no stockpiles shall be located closer than 30m from water features, in accordance with OPSS 180. Waste and excess materials will be dealt with in accordance with OPSS 180, General Specification for the Management and Disposal of Excess Material. Waste generated on-site, which requires off-site removal should be in accordance with Ontario Regulation 347 under the Environmental Protection Act which provides for the transportation and processing of hazardous and non-hazardous waste;
- To prevent surface water contamination during construction, care will be taken to avoid • accidental spillage or discharge of chemical contaminants (i.e. gasoline, oils and lubricants). Refuelling should take place no closer than 30 metres from water features. Furthermore, proper containment, clean up and reporting, in accordance with provincial requirements, should be completed in the event of a spill;
- All exposed slopes shall be treated with topsoil and seeding, mulching or sodding; .
- A significant step towards controlling erosion during construction is to minimize the amount of disturbed ground cover particularly near watercourses;
- Exposed areas should not be left uncovered longer than necessary and ground cover should be re-established as quickly as possible; and
- Sediment control measures will be installed prior to construction, monitored during the • construction and replaced as necessary.

Monitoring

Prior to construction, the contractor is required to submit comprehensive environmental controls and methods plan to address, among other elements, effluent (water) control. The effectiveness of this plan is monitored during a demonstration of the process that is undertaken before the Work can commence on site. A representative of TTC will undertake monitoring of plan compliance.

As a component of erosion and sedimentation control, environmental inspections of the construction site will be conducted. Environmental inspections will be conducted to assess the performance of erosion and sedimentation control measures and identify any required maintenance. The frequent inspections will also permit the identification of localized erosion and sedimentation control issues that require site specific attention. A detailed erosion and sedimentation control plan will be prepared during later design phases.

Contingency

During the course of construction, there is a risk of spills or discharges of pollutants or contaminants by the Contractor. The following contingency plan will be put in place:

- 1. Names and telephone numbers of persons in local municipalities and MOE to be notified forthwith of a spill;
- 2. Names and telephone numbers of representatives of fire, police and health departments of local municipalities who are responsible to respond to mergency situations;
- 3. Names and telephone numbers of companies experienced in control and clean up of hazardous materials that will be called in an emergency involving a spill;
- 4. Contingency plan shall include provisions for hazardous or unknown materials (e.g. puncturing a drain during excavation);
- 5. Containement and control of spill and cluean up procedures are to be initiated immediately to mitigate environmental damage, while awaiting additional assistance; and
- 6. Ensure materials and products are on site with which temporary repairs can be made to broken pipelines or other services so emissions of pollutants can be controlled and stopped.

5.4.4 Communities/Ecosystems

Potential Impacts

The potential environmental effects on communities and ecosystems are described in detail in Section 4.2.4. Surface construction of the Eglinton Crosstown LRT has the potential to result in short term disturbance to vegetation that currently exists along the Eglinton corridor. Activities such as relocation of street lighting and utilities, temporary or permanent road widening, boulevard modifications, maintaining access to side streets and entrances, and temporary staging areas for construction equipment or construction materials can temporarily increase the overall project footprint size, and result in generally, short term disturbances.

Mitigation

The disturbance to vegetation along Eglinton Avenue as a result of this transit project is considered negligible since the majority of vegetation located adjacent to the right-of-way has been previously disturbed by urban development.

To minimize disturbance at a particular site:

- Work zones will be isolated using construction fencing and silt fencing to minimize the area of disturbance;
- Reinstate growing conditions on top of LRT facilities in areas of cut-and-cover construction; and
- Good housekeeping practices related to materials storage (pocket)/stockpiling, equipment fuelling/maintenance, etc. will be implemented during construction.

The work zones associated with the west and east portals will affect a considerably large area of approximately 5000 square metres, at each site.

The proposed location for the west portal work site is on the south side of Eglinton Avenue, 200 metres east of Black Creek Drive. The area is locally known as Keelesdale Park and the present land use consists of baseball diamonds, an indoor hockey arena and a grass soccer pitch. The soccer pitch is located adjacent to but separated from Eglinton Avenue by a cultural woodlot (CUW1), is bordered by a small deciduous forest parcel (FOD2-1) to the east, and a parking lot to the south. The work zone will be established on the soccer pitch, resulting in a temporary disturbance to this grassed area. Upon completion

of the project, the soccer pitch will be re-established to its present condition. To minimize or avoid increased disturbances to this site, the cultural woodlot should be left intact or restored following construction.

The proposed location for the east portal is on the south side of Eglinton Avenue, 400 metres east of Brentcliffe Road. Vegetation at the site is predominantly cultural meadow and this will be removed to establish the work zone area. Upon completion of the project, a cultural vegetation community can easily be re-established.

Resulting impacts at both of these sites are considered to be temporary and short term.

Monitoring

In the event that works must be undertaken within vegetation communities / ecosystems, TTC will monitor the health of the trees and overall state of the existing vegetation communities during construction. Once all construction activities are complete, this monitoring program will continue into the following growing season.

Contingency

If it is determined that tree health or vegetation community restoration is failing or has failed, then trees or shrubs will be replaced with the identical species and girth, and a modified restoration plan will be determined.

5.4.5 Populations/Species

Potential Impacts

During construction, the urban wildlife species present in the Eglinton Crosstown LRT corridor will be temporarily displaced but will re-establish to the available habitat once operation of the Eglinton Crosstown LRT is established. These short term impacts are not considered to be significant. There is potential impact to streetscape trees and possibly trees within private properties during construction but considered minor. Disturbance to trees and shrubs can have a direct effect on the vegetation itself but can also affect nesting birds.

Mitigation

The *Migratory Birds Convention Act* (MBCA) prohibits the killing, capturing, injuring, taking or disturbing of migratory birds (including eggs) or the damaging, destroying, removing or disturbing of nests. To meet the requirements of the MBCA, no vegetation removals should occur during the nesting season. With several exceptions, this includes the period from April 1 to July 31. This timing restriction will also protect the birds listed under the *Fish and Wildlife Conservation Act*.

TTC will comply with the requirements of the *Migratory Birds Convention Act* and nesting season, and as a result, the Eglinton Crosstown LRT will have no significant adverse effects on avian wildlife species/populations.

The potential impact to streetscape trees and possibly trees within private properties is of minor concern because trees at risk can be protected with barrier fencing, transplanted or removed and replaced during the final construction stage.

Monitoring

If vegetation clearing is required during the nesting season, TTC will retain a qualified avian biologist to conduct a nesting survey.

Contingency

If active nests are found, TTC will prepare a site-specific mitigation plan in consultation with the Canadian Wildlife Service.

In the event that works must be undertaken within areas of communities / ecosystems, TTC will monitor the health of the affected community during construction. Once all construction activities are complete, this monitoring program will continue into the following growing season.

5.4.6 Air Quality

Potential Impacts

During construction, there is potential for air quality impacts to occur. These impacts will be of short duration, limited to the period where significant excavation and construction activities occur on surface sections of the LRT or where cut and cover construction is required on the underground section of the LRT. The two major sources of emissions from construction are dust emissions and exhaust emissions from construction equipment. All construction locations will be temporary and will have a localized impact.

Mitigation

Best management practices will be implemented to prevent the potential release of dust and other airborne pollutants off site, such as:

- Periodic watering of unpaved construction areas:
- Periodic watering of stockpiles;
- Limiting speed of vehicular travel;
- Use of water sprays during the loading, unloading of materials; and
- Sweeping and/or water flushing of the entrances to the construction zones.

These types of controls aid in minimizing impacts to the environment during the construction phase. Night time construction activities should also be considered in order to reduce the higher emissions from vehicles that are slowed down by the reduced existing road capacity during the day. It is recommended that only water be used as a dust suppressant.

The reductions in greenhouse gases associated with the use of the LRT will far outweigh any short term increase in greenhouse gas emissions that are associated with construction activities.

Monitoring

During a demonstration and throughout the work, air monitoring of crystalline silica, total dusts and other contaminants (as applicable) should be conducted as a check on the effectiveness on dust control measures. In particular, Air quality monitoring should be conducted prior to, during or following construction as follows:

- 1) When construction and/or demolition activities are likely to cause dust emission, air monitoring must air. During construction and/or demolition operations where dust is being created, air quality minotiring must b econducted to establish the level of particulate matter in the air. Following construction and/or demolition operations where dust was created, confirmatory tests must be conducted to quantify the level of particularte matter in the air.
- Construction Borne Particulate Matter within Existing Buildigns In instances where works are 2) necessary to connect new works to existigting buildings and stations and activities, such as sawcutting are required. Monitoring of airborne contaminants such as crystalline silica will be required to show that these contaminants are below their respective time weighted average exposure values as indicated in Regulation 833.

5.4.7 Noise and Vibration

Potential Impacts

The impact of construction noise and vibration on nearby sensitive receptors has been investigated. Where feasible, noise and vibration control measures will be implemented to limit the potential disturbance of construction equipment and activities to nearby receptors. As the project has not reached the design level, specifics of equipment to be used in the construction process have not been determined. The focus of the construction noise and vibration impact assessment was to develop a generic guide to be further refined and expanded when more information becomes available during the design phase. As the project is guite extensive, consideration is given not only to structural and health-related effects of construction noise and vibration, but also to community annovance.

Residential receptors were the focus of the impact assessment as they are the predominant sensitive receptor in the corridor. Impacts at nearby residential receptors are representative of potential impacts at other sensitive receptors such as hospitals and nursing homes. It is recommended that in the long term construction areas, high-traffic commercial applications such as restaurants be treated as noise- and vibration-sensitive receptors. Industrial and commercial sites were also considered with respect to structural vibration and noise impacts, although their sensitivity is normally much less than residential and institutional receptors.

Mitigation

Provincial and municipal guidelines provide basic restrictions and recommendations with regard to construction noise and vibration. These criteria will be followed in all areas, regardless of duration of construction. In particular, municipal by-laws from the City of Toronto stipulate limitations on the vibration from construction activity and the times of construction. These have been taken from the MOE Model Noise Bylaw. The applicable guidelines can be found in the following documents:

- MOE's Model Municipal Noise Control Bylaw
- Toronto Municipal Code, Chapter 591, Noise, dated 2007-12-13 .
- City of Toronto Bylaw No. 1400-2007, Noise, Respecting Construction Noise, in force on January 1, 2008
- City of Toronto By-Law No. 514-2008, amending the Toronto Municipal Code Chapter 363, • Building Construction and Demolition, with Respect to Regulation of Vibration from **Construction Activity**

Toronto Transit Commission/City of Toronto EGLINTON CROSSTOWN LIGHT RAIL TRANSIT TRANSIT PROJECT ASSESSMENT **Environmental Project Report**

be conducted prior to beginning activities to establish a baseline value for the quantity of SPM in the

- NPC-115 'Construction Equipment'
- NPC-205 'Sound Level Limits for Stationary Sources in Class 1&2 (Urban) Areas'
- NPC-118 'Motorized Conveyances'

Provincial guidelines with regard to construction sound levels place specific restrictions on source sound levels. The guidelines are written to restrict maximum allowable sound levels for equipment used in certain construction activities. The applicable guidelines can be found in NPC-115. NPC-205 excludes noise sources related to construction activities.

Municipal bylaws place restrictions on the hours of operation for all construction activity: in particular, construction is limited from 7:00 AM to 7:00 PM on weekdays, and are more stringent on weekends and holidays. If construction activities occur outside the hours of operations, special exemptions will need to be obtained from the City of Toronto and residents in the area will be notified several weeks in advance of the construction activities.

It is assumed that the surface LRT construction will be carried out in a manner similar to the current streetcar construction methods. Much of the noise resulting from this construction activity will be that typical of a highway or road widening. The overall duration of the construction activity will be significant: however, the impact to a specific area will be comparatively short during the course of construction as construction will progress from one area to the next.

Monitoring

Noise levels for nearby sensitive uses (such as residential or institutional) will have specific monitoring locations and maximum noise elvesl. These levels and construction activities that may benerate exceedences will be definted prior to construction. The monitoring program will include review and alert levels. If instruments readings exceed "review" levels, TTC and its contractor will jointly assess the necessity of altering the method, rate or sequence of construction. At "alert" levels, TTC can order construction operations to cease until the necessary mitigation measures are undertaken.

Vibration resulting from construction will be monitored using seismographs. Vibrations will be monitored at locations at various distances from work operations and at critical structural or utility locations. As part of the baseline monitoring, a minimum of 3 consistent sets of readings will be taken prior to the start of work. TTC will then continuously monitor ambient vibration levels during construction. The monitoring program will include review and alert levels. If instrument readings exceed "review" levels, TTC and its contractor will jointly jointly assess the necessity of altering the method, rate or sequence of construction. At "alert" levels, TTC can order construction operations to cease until the necessary mitigation measures are undertaken.

Similarly, vibration during the tunnelling process will require monitoring.

Contingency

In the event that instrument readings reach "alert" levels, (as to be defined on a structure-specific basis in the construction contract documents), TTC site supervisory staff will order construction operations to cease and take necessary actions to mitigate unacceptable movements, including, but not limited to alternative construction metods or construction equipment.

5.4.8 Business Operations

Potential Impacts

Eglinton Avenue, Commerce Boulevard, Convair Drive and Silver Dart Drive provide the essential visibility and accessibility needed by businesses and other economic activities. The proposed Eglinton Crosstown LRT will enhance this accessibility with improved transit service, bringing more patrons to and along the corridor. By stimulating transit oriented development along the corridor, the Eglinton Crosstown LRT will attract more business activity, resulting in positive economic benefits.

Experience from other large LRT projects in the City has suggested that an important business issue is the possible reduced vehicle access to the area and potential loss of on-street parking. The design of the project has been developed to minimize these impacts. The City/TTC are committed to accelerating construction as much as possible to reduce the construction period in order to minimize construction related impacts to residents and businesses. Auto and transit traffic will be maintained throughout the construction period with a minimum of a single lane of travel in each direction. Pedestrian access may be detoured at times but will also be maintained throughout construction. Every attempt will be made to replace any short-term parking loss for individual homes and businesses.

Access to businesses will be modified during construction activities. As part of this study the construction footprint of the station box was analyzed. As a result, a minimum 1 metre clearance from the building face to construction could be provided for access to businesses during construction.

Mitigation

The City/TTC will form a "Construction Liaison Group" in active construction zones during construction to provide quick access to construction related information, specifically schedule and timing information for local business owners and residents. The Construction Liaison Groups will be made up of City/TTC and Contractors staff who will meet regularly on site. Business owners and residents directly impacted by the current/future construction activity will be invited and encouraged to attend these meetings where the day to day issues affecting their home/business will be discussed and resolved. Issues such as business deliveries, local parking, and garbage pick-up will often be topics of concern. Further, construction schedule and activity timing is also a prime topic. Besides the Construction Liaison Group, the City and TTC will undertake prior to each phase of construction, a comprehensive public awareness campaign. Keeping the area up to date and well informed in advance of construction can dramatically reduce the inevitable disruption brought about by this project.

Monitoring

A public consultation plan, including information on how the public can raise issues/concerns, will be developed during the design phase.

Contingency

Any complaints received will be investigated and resolved in an effective and efficient manner.

5.4.9 Parks and Open Space

Potential Impacts

The proposed location for the west temporary work site is on the south side of Eglinton Avenue, 200 m east of Black Creek Drive. The area is locally known as Keelesdale Park and the present land use consists of baseball diamonds, an indoor hockey arena and a grass soccer pitch. The soccer pitch is located adjacent to but separated from Eglinton Avenue by a cultural woodlot (CUW1), and is bordered by a small deciduous forest parcel (FOD2-1) to the east and a parking lot to the south. The majority of the work zone will be established on the soccer pitch, but will also require removal of approximately 0.105 ha. of cultural woodlot to accommodate the northern boundary of the work zone and the 'open shaft' access to the portal. The FOD2-1 vegetation community will not be affected. The soccer pitch will also be used as the tunnel boring machine launch site and as temporary material stockpiling and heavy equipment operations site resulting in temporary impacts to its recreational use.

Mitigation

To ensure that the forested area remains undisturbed, the entire FOD2-1 vegetation community will be separated and isolated with a barrier to prevent encroachment by any construction related activity.Upon completion of the project, the soccer pitch will be re-instated to its present condition. The cultural woodlot (CUW-1) will also be restored to its pre-construction state as it will be replanted with suitable native species.

5.4.10 Traffic Operations

Potential Impacts

Road improvements and cut-and-cover construction used for station construction and special track work areas will result in disruption to traffic operations along Silver Dart Drive, Convair Drive, Commerce Drive and Eglinton Avenue.

At least three traffic lanes will be open to traffic and on-street parking will not be permitted during construction.

Mitigation

During the design process, TTC will work with the City of Toronto and the City of Mississauga to develop an acceptable approach for traffic maintenance during construction. This material will be provided to the contractor as a guide. In the event that the contractor decides to deviate from this plan, the contractor will be required to prepare and submit a detailed and comprehensive Traffic Management Plan, for review by TTC and the Toronto and Mississauga transportation departments.

5.4.11 Property

Potential Impacts

Temporary property easements will be required during the construction phase to establish work zones, material laydown areas, equipment maintenance/storage (pocket) and to obtain access for construction activities.

Mitigation

The City of Toronto will negotiate temporary construction easements with property owners on a case-bycase basis following the procedures described in **Section 5.3.8.** Following construction, the City will reinstate lands to pre-construction conditions.

5.5 Operations and Maintenance Impacts

The operations and maintenance of the Eglinton Crosstown LRT will result in impacts that will be experienced over the life of the project. These impacts are associated with emissions during facility operations including air pollution, noise, vibration, electromagnetic interference and stray current. The Eglinton Crosstown LRT will also have long term effects on traffic and transit operations.

5.5.1 Air Quality

Potential Impacts

The operation of the Eglinton Crosstown LRT will result in significant reductions in emissions of oxides of nitrogen, volative organic compounds and carbon monoxide along Eglinton Avenue compared to current conditions. The replacement of existing diesel powered buses tha serve the LRT corridor and transfer of terminus points for some bus routes that are currently served from either the Eglinton Station or Eglinton West Station will result in a reduction in local air emissions.

There will be a need for more electricity to operate the Eglinton Crosstown LRT. However, even with the increased contaminant releases associated with electricity production, it is estimated that there will be a reduction of common air contaminants released in southern Ontario as a result of implementing the LRT. These reductions will grow if private vehicle users become LRT riders.

The new off-street bus terminals/bus loops located at the Keele Station, Don Mills Station and Caledonia Station will be point sources for exhaust emissions. Based on the number of buses to use these terminals/bus loops at any one time, the duration that the buses will be idling on site and the age o fthe bus fleet, it was determined that carbon monoxide (CO), total suspended particulate (TSP) and nitrogen oxide (NO_x) emission will be well below Canada Wide Standards and Ontario Ambient Air Quality Objectives at these locations.

5.5.2 Noise

Potential Impacts

Overall, the noise impact of the LRT is a slight increase in sound levels on the surface and a zero change or reduction in sound levels on the underground sections. The increases, at the most are 3dB on the surface routes and 4dB at the portals, are below the criterion limit of 5dB permissible increase in sound. Hence, no noise control is warranted as a result of the surface LRT operations.

Near the eastern tunnel portals, near Brentcliffe and on the east side of the Don Mills portal, the increase in sound approaches 5dB. Although slightly below the criterion limit, some noise absorption within the tunnel should be considered during the detail design phase to ensure that sound levels do not exceed 5dB. This comment partially reflects the reverberant character of the sound emanating from the tunnel out of the portals.

The Keele Street bus terminal, the Don Mills Road bus terminal and the Caledonia bus loop do not exceed the guideline limits with their current designs. No noise control is required for these facilities.

Traction power substations 10, 11 and 17 are significantly above the ambient sound levels at the nearest receptors.

Several fire ventilation shafts may generate noise in excess of the ambient sound levels in the area and guidelines.

Mitigation

At traction power substations 10, 11 and 17, consideration should be given to moving these power stations further away from the receptors. Otherwise, noise control measures should be incorporated into the design of the power substations. As this analysis is based on approximate data, the requirement for mitigation should be reviewed once more detailed data become available.

At several fire ventilation shafts, silencing beyond the standard generic package needs to be developed and implemented in order to meet the guidelines at the limited number of locations. In addition, the removal of property to facilitate the placement of fire ventilation shafts results in very local impacts that trigger the warrants for acoustic barriers or other forms of shielding for the roadway noise. These barriers should be constructed to a height similar to that of the buildings that are being removed.

5.5.3 Vibration

Potential Impacts

The perceptible vibration levels expected to be caused by the LRT are slightly above the vibration criterion limit of 0.1 mm/s rms at a setback of 20 metre from the tracks. This meets the MOE/TTC requirements. At closer setbacks, further vibration isolation will be required. The induced noise from vibration is predicted to cause some impact based on the US Federal Transit Administration guideline limit of 35dBA. Vibration impacts along tangent track in the underground section are not expected provided the isolation system is as effective as that employed along the Sheppard Subway Line.

Mitigation

Vibration isolation improvements would be needed for the tangent tracks, on the surface, located in residential neighbourhoods to reduce interior sound levels resulting from LRV vibration to 35dBA. Significant modifications to the vibration isolation system would be required for the special track areas noted as local vibration levels are expected to be significantly above the criterion limit, both in terms of noise and perceptible vibration in the areas where surface operations are within 20 m of residences.

5.5.4 Electromagnetic Interference (EMI)

Potential Impacts

All electrical devices generate electromagnetic interference (EMI). The LRT will operate using 600 VDC; therefore, it is a source of EMI. The most common sources of EMI include:

- Computing devices including microprocessor based patient diagnostic, monitoring and • therapeutic equipment;
- Radio transmitters including radio paging transmitters and portable/mobile transmitter/receivers ۰ such as the familiar walkie-talkie units used by maintenance and security personnel;
- Television receivers and projection devices;
- Cellular telephones; and •
- Electrical distribution systems within buildings.

Based on recent tests undertakin by the Bay Area Rapid Transit System (BART), examples of EMF intensities from human activities include the following:

- Overhead power transmission line 32 to 57 mG (range of exposure to utility workers); •
- Household appliances 8 to 165 mG (at a distance of 27 cm); .
- Computer video display 2 to 4 mG (at a distance of 35 cm); and
- Electric powered rail vehicle 400 mG (at 110 cm from the vehicle floor) to 1,500 mG (at floor level).

For comparison, in the natural environment apart from human activity, the earth's static magnetic field varies from 300 mG (30μ T) at the equator to over 600 mG (μ T) at the magnetic poles.

Mitigation

TTC currently operates under and nearby a variety of sensitive uses, including hospitals and university laboratories. TTC has had no EMI related issues materialize along any part of its electric system. Based on measurements taken on the BART system, the results of the modelling showed that static magnetic field levels above 50 µT do not extend beyond 10.0 m from the centre of the two BART tracks at track level. Therefore EMI can be mitigated through the setback of the overhead catenary wire.

5.5.5 Stray Current

Potential Impacts

Stray current corrosion, which is a form of electrolytic corrosion, occurs on buried metallic structures and differs from other forms of corrosion damage in that the current, which causes the corrosion, has a source

external to the affected structure. Stray current is caused by a portion of the negative return current which leaks into the ground and returns to the traction power substation through parallel paths provided by the ground and by any other metallic structures. For a non-metallic structure, such as plastic or concrete pipe and plastic coated cables, stray current is a non-issue. Stray current activities and step and touch voltage hazards will be considered during the design of traction power substations.

Mitigation

In order to minimize uncontrolled stray currents a number of measures shall be used in connection with measures applied to the traction power return system:

- Low linear rail electrical resistance;
- High rail-to-earth resistance, including insulated trackwork mounted fittings and appurtenances;
- Good rail bonding, both longitudinally and track cross-bonding;
- Parallel connected negative reinforcing feeder cables, insulated and cross-bonded to the return rails;
- Good water drainage:
- Structural steel-work and reinforcing isolation/separation; and
- Utility structures to be electrically insulated, bonded, coated and cathodically protected as required.

The LRT traction power distribution system shall be ungrounded and shall have no direct connection to the earth.

The running rails shall be insulated from earth with the use of insulating pads and hardware, and by the isolation of all rail associated metal ware from earth. Where applicable, the negative running rails shall be connected to the AC ground system through a floating negative automatic ground switch (FNAGS). The FNAGS operates (and alarms) only on an abnormally high return rail to ground voltage.

Monitoring

A monitoring program will be put in place where the LRT crosses a high-pressure steel pipeline. The monitoring program will include:

- Prior to construction, a baseline survey for stray current corrosion control is undertaken and reported to the pipelines:
- During construction, stray current test equipment is installed in the immediate vicinity of the pipelines;
- Upon completion of the work, stray currents will be monitored as often as is prudently required; and
- All data will be shared between the pipelines and TTC.

Traffic Operations 5.5.6

Along these sections, there will be some impact on the capacity for automobile movements although the total people carrying capacity of the corridor will be increased by introducing LRT service.

At existing non-signalized intersections, there will be a right-in/right-out arrangement to ensure safe LRT operation by not permitting crossing of the alignment by motor vehicles. A preliminary planning study has carefully considered each location to ensure that either an existing or new signalized intersection is nearby to provide a nearby U-turn opportunity.

At specific major signalized intersections, left-turns will not be provided to improve transit operations. Instead, motorists will be provided with left-turn and U-turn opportunities at locations beyond the intersections. The LRT section from the Pearson International Aiport to Martin Grove Road will not have left turn prohibitions at intersections.

In the section from Keele Street to Brentcliffe Road, the LRT will be underground. Lane configurations on Eglinton Avenue in this section will be unaffected.

The removal of one through lane in each direction along the east section of the Eglinton Crosstown LRT may displace some vehicular traffic. Current drivers could use other roads or could be converted to transit users.

Bicycle lanes will be provided or maintained along the LRT alignment to provide an alternative travelling mode for non-drivers.

Emergency service providers will continue to operate at current service levels with the LRT in place. The track area of the LRT will be paved with concrete. Emergency vehicles can utilize this right-of-way to avoid traffic congestion. As a step towards accommodating emergency vehicles' entry/exits, modifications to the LRT right-of-way will include adjusting pole locations or lowering the raised right-of-way at the driveways of fire, police and ambulance stations.

Monitoring

Traffic volumes on public roads and transit schedules are part of the City of Toronto's and TTC normal operating procedures. This will allow for either agency to identify future issues and develop corrective actions. Furthermore, as development proceeds around each station/stop, the City of Toronto and the City of Vaughan will ensure the continued functioning of the road network, through the use of supporting traffic impact studies.

5.5.7 Transit Operations

A formal analysis of bus routing changes, including public consultation, will be undertaken between 12 and 18 months prior to the opening of the Eglinton Crosstown LRT. For planning purposes, TTC staff have developed a preliminary bus plan to help guide discussion about LRT facilities and potential bus connections. The preliminary bus plan is presented in **Exhibit 159** and identifies the following changes to the existing bus network related to the Eglinton Crosstown LRT:

- No parallel bus routes will be provided along Eglinton Avenue; •
- North-south arterial bus routes will continue to operate;
- The Don Mills and Eglinton Station will include a new seven-bay bus terminal to service the . 25N. 25S. 54 and 100 bus routes:
- The Keele and Eglinton Station will include a new four-bay bus terminal to service the 32C and 32D bus routes; and

de a new bus loop to service the 47 based on achieving the right balance d stops/stations provide excellent lo	N and 47S bus routes. e between convenient local access cal access, but speed of service is	Route	Description	Start/End Station	F Ov Ll
aced too closely together. Stops/sta ubways, intersect Eglinton Avenue in se services and the LRT. The proxin s and future developments was also	ations will be located where current order to provide convenient nity of existing neighbourhoods, considered when stop/station	34	Eglinton East	Eglinton	Ke
ng and resulting speed of service in bway. On the surface sections, ave	the underground section is rage stop spacing is	47	Lansdowne	Lansdowne	Ca
service increase of approximately 5	51	Leslie	Eglinton	L	
op/Station Spacing and Resulting Stop/Station Spacing	Route Speed Route Speed	54	Lawrence East	Eglinton	L
670 m	28-31 km/h	56	Leaside	Eglinton	
660 m	32 km/h 22-25 km/h	61	Avenue Road North	Eglinton	Ave
tes that serve portions of the Eglinto	n Crosstown LRT route and their	100	Flemingdon	Eglinton	Do

The Caledonia Station will inclue •

Stop/station locations were selected and speed of service. Closely spaced compromised if stops/stations are spa TTC services, including buses and su passenger connections between thos commercial areas, major destinations locations. The average distance betw presented in Exhibit 178. The spacir comparable to the Bloor-Danforth Sul approximately twice that of the existin exclusive lanes, results in a speed of

Exhibit 178: Sto

Section	Stop/Station Spacing	Route Speed
West Surface Section	670 m	28-31 km/h
Underground Section	850 m	32 km/h
East Surface Section	660 m	22-25 km/h

Exhibit 179 lists the existing bus rout potential re-alignments.

Exhibit 179:	Potential Mo	odifications to	o Bus	Routes o	on Ealinton	Avenue
				NOULOS C	n Eginton /	Avenue.

Route	Description	Start/End Station	Route Overlaps LRT to:	Distance on Eglinton (km)	Potential Re-Alignment
Existing	Routes to be Altered				1
5	Avenue Road	Eglinton	Oriole Pkwy	0.6	Combine with 61- run through Avenue Rd Stn
32	Eglinton West	Eglinton	Renforth	16.13	Discontinue
32A	Eglinton West	Eglinton	Renforth	16.13	Discontinue
32B	Eglinton West	Eglinton	Renforth	16.13	Discontinue
32C	Eglinton West	Eglinton	Keele	6.4	Terminate at Trethewey (Keele & Eglinton Stn)
32D	Eglinton West	Eglinton W	Keele	3.3	Terminate at Trethewey

Route	Description	Start/End Station	Route Overlaps LRT to:	Distance on Eglinton (km)	Potential Re-Alignment
					(Keele & Eglinton Stn)
34	Eglinton East	Eglinton	Kennedy	11.5	Discontinue
47	Lansdowne	Lansdowne	Caledonia	0.3	Re-routed to serve Caledonia Station
51	Leslie	Eglinton	Leslie	4.1	Combine with 56 along Eglinton to Laird
54	Lawrence East	Eglinton	Leslie	4.1	Terminate at Don Mills & Eglinton Station
56	Leaside	Eglinton	Laird	2.8	Combine with 51 along Eglinton to Leslie
61	Avenue Road North	Eglinton	Avenue Rd	0.6	Combine with 5 - run through Avenue Rd Stn
100	Flemingdon	Eglinton	Don Mills	5.1	Terminate at Don Mills & Eglinton from east via Wynford to Donlands Stn
103	Mt. Pleasant North	Eglinton	Mt. Pleasant	0.6	Loop at Eglinton Station with 74 Mt. Pleasant to St. Clair
New Rol	utes to be Added				
51/56	Leslie/Leaside	Donlands	Laird to Leslie	1.25	New route for Leslie bus along Eglinton to Laird

Beneficial Effects 5.6

In general the benefits of a well developed transit system for the health and vitality of big cities are well documented. Transit helps cities be more liveable and vibrant by:

- Ensuring that transit is an more attractive travel option by improving travel times, comfort, and ٠ reliability of service;
- Increasing the people movement capacity in all corridors, generally without the widening of ٠ roadways and in an environmentally sound manner, so that they can take advantage of the employment, educational, recreational, and many other opportunities cities offer;

- Providing alternative travel choices for non-drivers, including transit and enhanced environments for cycling and walking;
- Providing opportunities to include urban design and streetscaping features in the construction of the LRT line;
- Improving air quality and, in doing so, improving people's health and their ability to enjoy outdoor spaces and activities;
- Reducing the wear-and-tear on city roads and the need to spend tax dollars on repairing and expanding road infrastructure; and
- Ensuring the long-term economic stability and environmental sustainability by reducing climatechanging emissions and reliance on fossil fuels.

A recent study named "Greenhouse Gases and Air Pollutants in the City of Toronto-Toward a Harmonized Strategy for Reducing Emissions, 2007" on the sources of greenhouse gases and air pollutants in the City of Toronto indicates that close to 40 per cent of greenhouse gas emissions originate from the transportation sector. The vast majority of these emissions are from cars and trucks. Encouraging residents to choose alternatives to the automobile for as many trips as possible must be a vital part of any action plan to reduce harmful emissions and address climate change. The emission reductions resulting from the implementation of the Eglinton Crosstown LRT will result in a net benefit to those who reside in close proximity to Eglinton Avenue. Furthermore, greenhouse gas emissions are estimated to be reduced and that benefit can be extended should the LRT encourage motorists to use the public transit system.

Light-rail transit technology, as proposed in this study, offers significant benefits with respect to the environment and city-building. These include:

- Provision of premium quality service quiet, smooth, comfortable, fast, and reliable which attracts people to ride transit;
- Highly energy-efficient technology: light rail vehicles produce 92 per cent less CO₂ than autos and 83 per cent less CO₂ than diesel buses, and produce zero local-area or "tailpipe" emissions;
- Ample capacity for projected ridership in all proposed corridors, with the capability to expand to meet increasing demands;
- Demonstration of long-term and substantial commitment to quality transportation, to instil the confidence which landowners and investors need to invest in development and city-building, and the confidence which residents need to choose a transit-oriented lifestyle;
- Creation of a strong and highly-recognizable presence which signifies the availability of highquality transit; and
- Association with Toronto's streetcar heritage and the positive connotations which streetcars bring to the City and its transit system

Potential benefits of the Eglinton Crosstown LRT are that it will promote the Official Plan vision for a more liveable Toronto as future growth within Toronto wll be steered to areas which are well served by transit, the existing road network and which have a number of properties with redevelopment potential.

Having a safe, fast and reliable transit service like the Eglinton Crosstown LRT, that is a viable alternative to vehicular travel, will attract new business in the area based on the provision of increased people movement capacity.

The mixed use areas within Avenues will perform a "Main Street" function and become meeting places for local neighbours and the wider community. By promoting alternative forms of travel, these areas become vibrant communities centred on the people and uses instead of automobiles. By directing growth to areas such as Avenues, the Official Plan provides greater certainty for land owners, businesses and residents about what type of growth can be anticipated, and where growth will occur.

	Exhibit 180: Summary of Eglinton Crosstown LRT Potential Impacts, Mitigation Measures, Monitoring, Future Work and Co					
Factor	Environmental Issue / Concern	Effect / Impact (During Construction; During Operations)	Mitigation Measures			
Terrain and Soils	Changes in terrain and generation of excess soil	LRT facilities will be located primarily within the right-of-way and the vertical profile of Silver Dart Drive, Convair Drive, Commerce Drive and Eglinton Avenue will be maintained. Minimum impact on terrain will occur in underground sections. Approximately 1.8 million m ³ of soils are expected to be removed.	Regulatory requirements in place at the time of construction and excess materials management guidelines and specifications (e.g. OPSS180) will be used when developing an excess materials management plan. Contaminated soils will be managed in accordance with provincial legislation and regulations including the Ministry of the Environment's Guidelines for Use at Contaminated Sites in Ontario (MOE 1997).	A Soil develo Any bit the Or 511/09 Subta require phase If exca areas Phase condu A cont phase		
Groundwater	Impacts to groundwater during construction and from implementation of the LRT.	Potential for tunnelling activities encountering groundwater. The groundwater table is likely to be above the base of the proposed depth of alignment at many areas within the underground section of the Eglinton Crosstown LRT. Potential for encountering contaminated groundwater during dewatering. There is potential for buildings to have foundations built below the local water table, and a potential exists for these foundations to be affected by dewatering.	 Groundwater will need to be controlled by methods such as pumping from sumps, educators or well points or in some cases by deep well dewatering systems. For the majority of the underground section of the LRT, the base of excavation/tunneling is likely to be in glaciolacustrine (silt, clay and sand) deposits of the Thorncliffe Formation; therefore, care must be taken to prevent the removal of fine soil particles during pumping. It is anticipated that Eglinton Crosstown LRT facilities will not interrupt existing groundwater migration pathways and permanent groundwater dewatering systems will not be used. 	Furthe locatic rates, option Ministr (PTTV Conta accord includi Use a A Soil develo A con phase		
Surface Water, Drainage and Stormwater	Impacts to LRT operations during regional and 100 storm events. Impacts to drainage and stormwater systems from the LRT. Fuel spills, due to accidents	At two locations, Humber River and Black Creek, it was determined that the Eglinton Crosstown LRT will be affected by the regional storm event (1 in 500 years) but operations will not be affected by the 100 year storm event. The east and west portal are both located above the flood elevation for the regional storm; therefore,	Stomwater control, mitigation, erosion and sediment control measures will be enumerated as per MOE's Stormwater Design Manual 2003 and the City of Toronto's Wet Weather Flow Management Guidelines 2007. LRT operations will be suspended during the regional storm event to prevent potential risks to human health and safety and damage to LRT facilities and vehicle.	Storm Toron require The C rainfal sewer on the		

ontingencies

Monitoring / Future Work / Contingency

I and Groundwater Management Strategy will be oped during the design phase.

rownfield sites will be managed in accordance with ntario Regulation 153/04 and Ontario Regulation 9 once it comes into force. A Designated ances Surveys for any buildings or structures which re demolition will be undertaken during design e.

avations or property acquisitions are planned in of known or high potential for contaminated soils, e 1 and 2 Environmental Site Assessments will be ucted during design phase.

tingency plan will be developed during design where appropriate.

er hydrogeology studies will be conducted at ons requiring dewatering to estimate discharge predict impacts and evaluate treatment/discharge ns. These studies are also needed to support the try of the Environment's Permit to Take Water *N*) applications.

aminated groundwater will be managed in dance with provincial legislation and regulations ling the Ministry of the Environment's Guidelines for at Contaminated Sites in Ontario (MOE 1997).

and Groundwater Management Strategy will be oped during the design phase.

tingency plan will be developed during design where appropriate.

water management, in accordance with City of to, City of Mississauga, TRCA and MOE ement will be developed during the design phase.

City of Toronto operates and maintains a network of Il guages. The information is used to determine r sizes and the influence of storms of various sizes e existing sewer system and on streams (floods).

Factor	Environmental Issue / Concern	Effect / Impact (During Construction; During Operations)	Mitigation Measures	
	during construction refueling and accidents during operation, entering the watercourses. Impacts to quality and quantity of surface water.	 minimum risk of flooding within the portal or tunnel are predicted. West of Martin Grove Road, catchbasins/storm sewers may require relocation as a result of proposed Eglinton Avenue widening. The storm sewers located between Royal York and Weston Road may require hydraulic capacity assessment to ensure that the capacities of these receiving storm sewers are not compromised due to proposed increase in pavement area. At other locations where increase in pavement area is nominal, it is anticipated that the existing storm sewers capacities will not be impacted. The LRT will not significantly add impervious surfaces, as such no water quality control measures are warranted. Potential for decline of quality of surface water during construction due to erosion and sedimentation. Potential for surface water contamination. 		The Ci sewers for a va from se trace a to its s A pern secure
Fisheries	Alteration of fish habitat during construction.	Potential alteration of fish habitat as a result of bridge widening and culvert extensions. No work in the wetted stream channel is proposed.	Implement best management practices for work on watercourse banks. Implement erosion and sedimentation control measures. Implement stormwater management practices	The TI Depart review agreer Sectio all con is a po Alterat (HADE apply, inform work v restora

Monitoring / Future Work / Contingency

City collects and analyses water samples from rs at sewer outfalls, in stream and at the lakefront variety of management reasons. Sample results sewers and at sewer outlets are used to determine, and correct the discharge of prohibited pollutants sewer systems.

nit under Ontairo Regulation 166/06 will be ed from TRCA during the design phase.

RCA has a Level III agreement with the rtment of Fisheries and Oceans. TRCA staff will v the project in line with TRCA's Level III ment with Fisheries and Oceans Canada as per on 35 (1) of the *Fisheries Act.* TRCA's will assess mponents of the project to determine whether there otential for the project to result in a Harmful tion, Disruption or Destruction of fish habitat D). Where fisheries timing window restrictions , TRCA will provide TTC with the necessary nation for construction staging purposes. Staff will with TTC to ensure appropriate mitigation and ation is achieved during construction

e environmental inspection during work at

Factor	Environmental Issue / Concern	Effect / Impact (During Construction; During Operations)	Mitigation Measures	Monitoring / Future Work / Contingency
Vegetation	Mortality of fish species during construction.	Potential mortality to fish species as a result of bridge widening and culvert extensions. No work in the wetted stream channel is proposed. A total of 1.357 hectares of vegetation will be removed along the Eglinton Crosstown LRT corridor. Deciduous forests account for 42.7% (0.579 hectares) of this total. The majority of forest cover to be removed (0.554 hectares) occurs along the west section of the alignment between Martin Grove Road and Keele Street. The remaining vegetation communities at risk are culturally based and account for 59.6% (0.741 hectares) of the total area affected.	Implement best management practices for work on watercourse banks. Implement erosion and sedimentation control measures. Implement stormwater management practices. The following environmental protection measures designed to reduce or minimize vegetation removals will be considered on a site-specific basis during the design phase.	 bridge/culvert sites. On-site environmental inspection during work at bridge/culvert sites. Obtain permits and approvals for tree protection and removal/injury from TRCA, city of Mississauga and City of Toronto (including permits required under the Ravine and Natural Feature Protection By-law and by-laws that protect private trees, street trees and park trees), as applicable. Preparation of arborist reports, tree protection plans, edge management plans and restoration plans will be developed during the design phase to identify site-specific impacts, mitigation and compensation measures to offset vegetation losses and to achieve a net gain in vegetation area, attributes and functions. Prepare restoration and enhancement plans that will meet or exceed both TRCA and Urban Forestry standards that will offset vegetation losses and functions.A monitoring plan will be developed during the design phase to measure the effectiveness of proposed mitigation measures. A contingency plan will be developed during the design phase.
	Disturbance to vegetation through edge effects during construction.	Creating new forest edges may result in sunscald, wind throw, and invasion by exotic species. Ditching, grading and other drainage modifications may alter local soil moisture regimes.	 The City of Toronto Tree Protection Policy and Specifications for Construction Near Trees requirements will be met. To minimize disturbance at a particular site, work zones will be isolated using construction fencing and silt fencing to minimize the area of disturbance; reinstate growing conditions on top of LRT facilities in areas of 	A monitoring plan will be developed during the design phase to measure the effectiveness of proposed mitigation measures. A contingency plan will be developed during the design phase.

Factor	Environmental Issue / Concern	Effect / Impact (During Construction; During Operations)	Mitigation Measures	
			 cut-and-cover construction; and, good housekeeping practices related to materials storage (pocket)/stockpiling, equipment fuelling/maintenance, etc. will be implemented during construction. 	
	Rare, threatened or endangered flora.	Forty-one plant species that are rare to uncommon in the City of Toronto and in the TRCA watershed	Determine precise GPS locations of potentially affected plant species during design phase.	A mor phase mitiga A cont phase
Wildlife	Destruction/ Disturbance of wildlife habitat during construction.	Construction of the LRT and associated facilities will result in the removal of vegetation and the wildlife habitat that it supports.	 The <i>Migratory Birds Convention Act</i> prohibits the killing, capturing, injuring, taking or disturbing of migratory birds (including eggs) or the damaging, destroying, removing or disturbing of nests. To meet the requirements of the Act, no vegetation removals should occur during the nesting season. With several exceptions, this includes the period from April 1 to July 31. This timing restriction will also protect the birds listed under the <i>Fish and Wildlife Conservation Act.</i> TTC will comply with the requirements of the <i>Migratory Birds Convention Act</i> and nesting season, and as a result, the LRT will have no significant adverse effects on avian wildlife species/populations. Mitigation measures for the disturbance to vegetation will be implemented to mitigate any impacts to wildlife habitat. 	If vege seaso condu will pre with th In the of com health Once monito growin A mor phase mitiga A cont
	Impacts on wildlife mortality during construction	Removal of wildlife habitat may result in wildlife mortality.	Perform vegetation removals outside of wildlife breeding seasons (typically April 1 to July 31).	Bird F where reduce
	Disturbance to rare, threatened or endangered wildlife.	No rare, threatened or endangered wildlife identified within study area.	None required.	None

Monitoring / Future Work / Contingency

nitoring plan will be developed during the design to measure the effectiveness of proposed ation measures.

tingency plan will be developed during the design

etation clearing is required during the nesting on, TTC will retain a qualified avian biologist to uct a nesting survey. If active nests are found, TTC repare a site-specific mitigation plan in consultation he Canadian Wildlife Service.

event that works must be undertaken within areas nmunities / ecosystems, TTC will monitor the n of the affected community during construction. all construction activities are complete, this oring program will continue into the following ng season.

nitoring plan will be developed during the design to measure the effectiveness of proposed ation measures.

tingency plan will be developed during the design

Friendly lighting and design will be incorporated the LRT crosses valley and stream corridors to the potential for birds to impact buildings.

required.

Factor	Environmental Issue / Concern	Effect / Impact	Mitigation Measures	Monitoring / Future Work / Contingency
		(During Construction; During Operations)		
Electromagnetic Interference (EMI)	Potential generation of electromagnetic interference	All electrical devices generate electromagnetic interference (EMI). The LRT will operate using 600 VDC; therefore, it is a source of EMI.	EMI can be mitigated through the setback of the overhead catenary wire.	
Air Quality	Impacts on air quality during construction. Impacts on air quality due to implementation of LRT.	 Air quality impacts will be of short duration, limited to the period where significant excavation and construction activities occur on surface sections of the LRT or where cut and cover construction is required on the underground section of the LRT. The two major sources of emissions from construction are dust emissions and exhaust emissions from construction equipment. All construction locations will be temporary and will have a localized impact. Overall emissions are expected to decrease with LRT implementation. 	Best management practices will be implemented to prevent the potential release of dust and other airborne pollutants off site. Air quality is anticipated to be improved after the LRT implementation. Gases pollutants and particulate based pollutants are anticipated to be decreased during LRT operations.	Monitor and investigate complaints on air quality is
Noise and Vibration	Noise level increase during construction and operation of the LRT. Vibration impacts generated from the operation of the LRT	 Noise level increases during construction will be of short duration, limited to the period where significant excavation and construction activities occur on surface sections of the LRT or where cut and cover construction is required on the underground section of the LRT. Overall, the noise impact of the LRT is a slight increase in sound levels on the surface and a zero change or reduction in sound levels on the underground sections. The increases, at the most are 3dB on the surface routes and 4dB at the portals, are below the criterion limit of 5dB permissible increase in sound. Hence, no noise control is warranted as a result of the surface LRT operations. 	Comply with construction noise by-laws (Toronto Municipal Code) to provide means of limiting excessively noisy operations and equipment. Specify hours of operation during construction. Noise by-law exemptions will be obtained prior to construction if required. Although slightly below the criterion limit, some noise absorption within the eastern tunnel should be considered during the detail design phase to ensure that sound levels do not exceed 5dB. Consideration should be given to moving the three power stations further away from the receptors. Otherwise, noise control measures should be incorporated into the design of the power substations. Silencing fire ventilation shafts beyond the standard generic package needs to be developed and implemented in order to meet the guidelines at the limited number of locations.	Monitor and investigate complaints on noise and vibration issues Provincial and municipal guidelines provide basic restrictions and recommendations with regard to construction noise and vibration. These criteria wi followed in all areas, regardless of duration of construction. In particular, municipal by-laws from City of Toronto stipulate limitations on the vibratior construction activity and the times of construction. Mitigation measures will be developed during the ophase.
		Near the eastern tunnel portals, near	The acoustic barriers should be constructed to a height similar to	

Monitoring / Future Work / Contingency or and investigate complaints on air quality issues. or and investigate complaints on noise and ion issues ncial and municipal guidelines provide basic ctions and recommendations with regard to ruction noise and vibration. These criteria will be ved in all areas, regardless of duration of truction. In particular, municipal by-laws from the f Toronto stipulate limitations on the vibration from

ation measures will be developed during the design Э.

_		Effect / Impact		
Factor	Environmental Issue / Concern	(During Construction; During Operations)	Mitigation Measures	
		Brentcliffe and on the east side of the Don Mills portal, the increase in sound approaches 5dB. The Keele Street bus terminal, the Don Mills Road bus terminal and the Caledonia bus loop do not exceed the guideline limits with their current designs. No noise control is required for these facilities. Traction power substations 10, 11, and 17 are significantly above the ambient sound levels at the nearest receptors. Several fire ventilation shafts may generate noise in excess of the ambient sound levels in the area and guidelines. The removal of property to facilitate the placement of fire ventilation shafts results in very local impacts that trigger the warrants for acoustic barriers or other forms of shielding for the roadway noise. The perceptible vibration levels expected to be caused by the LRT are slightly above the vibration criterion limit of 0.1 mm/s rms at a setback of 20 metre from the tracks. This meets the MOE/TTC requirements. At closer setbacks, further vibration isolation will be required. Vibration impacts along tangent track in the underground section are not expected provided the isolation system is effective.	that of the buildings that are being removed. Vibration isolation improvements would be needed for the tangent tracks, on the surface, located in residential neighbourhoods to reduce interior sound levels resulting from LRV vibration to 35dBA. Significant modifications to the vibration isolation system would be required for the special track areas noted as local vibration levels are expected to be significantly above the criterion limit, both in terms of noise and perceptible vibration in the areas where surface operations are within 20 m of residences. Mitigation measures will be developed during the design phase.	
Property	Loss of property for the construction of the LRT	Total of 149 properties - 45 full acquisitions and 104 partial acquisitions are required, while 88 of the acquisitions are private properties	Compensation for residential and commercial impacts will be provided for temporary and permanent property requirements. For permanent property acquisitions, compensation will be provided	The prostage. Partial

Monitoring / Future Work / Contingency

e property owners will be contacted during the design

tial property acquisitions have been identified for a

Factor	Environmental Issue / Concern	Effect / Impact (During Construction; During Operations)	Mitigation Measures	
		and 61 are public properties.	 at fair market value, which is determined at the time of purchase with a property appraisal report forming the basis for negotiations. Other ancillary costs are negotiated on a case-by-case basis. Compensation will provided for the temporary property requirements. Upon completion of construction, temporary property will be returned to the owner and restored to its original condition. Where properties to be displaced form a continuous development of retail/business streetscape, the displacement TTC facility will ensure the continuation of the existing street wall (with respect to height setback and general architectural characteristics). 	further easem Proper Eglintc proper easem follow
Stray Current	Potential impacts from stray current	Stray current corrosion occurring on buried metallic structures	Stray current activities and step and touch voltage hazards will be considered during the design of traction power substations. In order to minimize uncontrolled stray currents a number of measures shall be used in connection with measures applied to the traction power return system.	A mon crosse progra • Pri cui to t • Du ins • Up mc • All TT
Parks and Open Space	Impacts to parks and city trees	Between Martin Grove Road and Scarlett Road, Eglinton Avenue will be widened on the north side within the Richview Corridor. Temporary impacts to the use of the soccer pitch at Keelesdale Park as the west temporary work site will be used for tunnel boring machine launch site, temporary material stockpiling and heavy equipment operations site. The west temporary work site will also require removal of approximately 0.105 ha. of cultural woodlot to	Vegetation located east of the soccer pitch will be separated and isolated with a barrier to prevent encroachment by any construction related activity. Upon completion of the project, the soccer pitch will be re-instated to its present condition. The cultural woodlot will also be restored to its pre-construction state as it will be replanted with suitable native species. The LRT facilities will be positioned and configured to minimize intrusion into the parks to the extent possible. The LRT facilities will be designed to blend into their surroundings using a context sensitive solution.	TTC w Recrea City of Eglinto

Monitoring / Future Work / Contingency

r 49 properties. These include underground nents and surface facilities such as station nces. TTC and the City of Toronto will conduct a erty Protection Study during the design of the on Crosstown LRT, which will determine detailed rty requirements, including temporary construction nents. The acquisition of these properties will the same principles described above.

nitoring program will be put in place where the LRT es a high-pressure steel pipeline. The monitoring am will include:

ior to construction, a baseline survey for stray rrent corrosion control is undertaken and reported the pipelines;

uring construction, stray current test equipment is stalled in the immediate vicinity of the pipelines;

oon completion of the work, stray currents will be onitored as often as is prudently required; and,

data will be shared between the pipelines and C.

vill consult with City of Toronto Parks, Forestry and ation division during design to mitigate impacts on f Toronto parks and parkettes located along on Avenue.

Factor	Environmental Issue / Concern	Effect / Impact (During Construction; During Operations)	Mitigation Measures	
		accommodate the northern boundary of the work zone and the 'open shaft' access to the portal. Construction of fire ventilation shafts, station entrances, emergency exit buildings and traction power substations along the Eglinton Crosstown LRT corridor will result in minor encroachment at five parks/parkettes (St. Hilda's parkette; Ben Nobleman Park; Chaplin parkette; Eglinton Park; and, Howard Talbot Park)		
Utilities	Potential conflicts with existing utility plants	The presence of an extensive system of storm and sanitary sewers, large diameter utility plants, pipelines and utility poles may be impacted by the implementation of the LRT.	Utilities and pipelines located within the underground section of the Eglinton Crosstown LRT will be avoided to the extent possible through tunneling. In areas of cut and cover construction, small utilities that are not in direct conflict with the LRT facility will be supported and protected during construction. For utilities that are in direct conflict with the LRT facility, or for large utilities that cannot be temporarily supported, relocation will occur. Services will be maintained to the extent possible during relocation and notice of planned service interruptions will be provided to service users prior to interruptions. The location of all plant, potential conflicts and the relocation strategy will be confirmed with service providers during detail design.	For all constru- with the Requir City of Mississ
Businesses Operations, Pedestrians and Cyclists	Access to businesses will be modified during construction activities.	Reduced vehicle access to the area and potential loss of on-street parking during construction	A minimum 1 metre clearance from the building face to construction could be provided for access to businesses during construction. The City/TTC are committed to accelerating construction as much as possible to reduce the construction period in order to minimize construction related impacts to residents and businesses. Auto and transit traffic will be maintained throughout the construction period with a minimum of a single lane of travel in each direction. Pedestrian access may be detoured at times but will also be maintained throughout construction. Every attempt will be made to replace any short-term parking loss for individual homes and businesses. The City/TTC will form a "Construction Liaison Group" in active	A publi the pub during Any co resolve

Monitoring / Future Work / Contingency
utilities that will be relocated, relocation plans and uction activities will be undertaken in accordance e <i>Road Rights of Way Act</i> and with the City's rements for the Installation of Services within the Toronto Road Allowance or its equivalent in sauga.
ic consultation plan, including information on how blic can raise issues/concerns, will be developed the design phase.
omplaints received will be investigated and ed in an effective and efficient manner.

Factor	Environmental Issue / Concern	Effect / Impact (During Construction; During Operations)	Mitigation Measures	
			construction sites during construction to provide quick access to construction related information, specifically schedule and timing information for local business owners and residents. The Construction Liaison Group will be made up of City/TTC and Contractors staff who will meet regularly on site. Business owners and residents directly impacted by the current/future construction activity will be invited and encouraged to attend these meetings where the day to day issues affecting their home/business will be discussed and resolved. Issues such as business deliveries, local parking, and garbage pick-up will often be topics of concern. Further, construction schedule and activity timing is also a prime topic. Besides the Construction Liaison Committee, the City and TTC will undertake prior to each phase of construction, a comprehensive public awareness campaign. Keeping the area up to date and well informed in advance of construction can dramatically reduce the inevitable disruption brought about by this project	
Archaeology L	Loss of archaeological	Stage 1 and Stage 2 archaeological assessment was conducted for the LRT corridor except for two segments of the proposed LRT corridor, north and south of Highway 401 between Matheson Boulevard and Convair Drive.	Despite careful scrutiny, no archaeological resources were encountered during the Stage 2 Archaeological Assessment field investigation and, thus, with the exception of the unassessed segments, the remainder of the subject lands, encompassing the Eglinton Crosstown LRT have been considered clear of further archaeological concern. The Ministry of Culture have reviewed the Stage 1 and Stage 2 Archaeological Assessment reports and agreed to its findings.	A Sta for th prop betw desig The recol 3. SI bu de ar <i>H</i> th th th ar co <i>H</i> U u co 4. Ar
				4.

Environmental Project Re Monitoring / Future Work / Contingency

age 2 archaeological assessment will be conducted ne two unassessed segments segments of the osed LRT corridor, north and south of Highway 401 reen Matheson Boulevard and Convair Drive during gn phase.

following monitoring and contingency measures are mmended by the Ministry of Culture:

should previously unknown or unassessed deeply uried archaeological resources be uncovered during evelopment, they may be a new archaeological site nd therefore subject to Section 48 (1) of the *Ontario deritage Act*. The proponent or person discovering ne archaeological resources must cease alteration of ne site immediately and engage a licensed rchaeologist to carry out archaeological fieldwork, in ompliance with Section 48 (1) of the *Ontario deritage Act*. The office of the Heritage Operations Init, *Ministry of Culture* (416-314-7146) should be ontacted immediately.

Any person discovering human remains must nmediately notify the office of the Heritage Operations Unit, *Ministry of Culture* (416-314-7146), ne police or coroner, and the Registrar of Cemeteries, Cemeteries Regulation Unit, *Ministry of Government Services* (416-326-8404).
Factor	Environmental Issue / Concern	Effect / Impact (During Construction; During Operations)	Mitigation Measures	
Built Heritage and Cultural Landscapes	Generally changes due to transit infrastructure projects have the potential to adversely affect cultural heritage landscapes and built heritage resources by displacement and/or disruption during and after construction.	Buildings near the intersection with Eglinton Avenue and Weston Road, Keele Street, Dufferin Street, Oakwood Avenue, Mount Pleasant Road and Bayview Avenue may be affected. Built heritage and/or cultural heritage landscapes may experience displacement (removal) or disruptions (by the introduction of physical, visual, audible or atmospheric elements that are not in keeping with their character and, or setting).	A Heritage Impact Statement (HIA) for the collection of buildings to be removed will be conducted during design phase. Documentation through the use of historical mapping and photography of the affected buildings will be conducted prior to removal in accordance with the requirements of the City of Toronto Heritage Preservation Services requirements. LRT Station entrances will be designed using context sensitive solutions in consultation with the City of Toronto, Heritage Preservation Services.	TTC w and/or sites to Servic Herita phase
Traffic Operations	Reduce level of services on vehicular traffic	Road improvements and cut-and- cover construction used for station construction and special track work areas will result in disruption to traffic operations along Silver Dart Drive, Convair Drive, Commerce Drive and Eglinton Avenue. At least three traffic lanes will be open to traffic and on-street parking will not be permitted during construction.	During the design process, TTC will work with the City of Toronto and the City of Mississauga to develop an acceptable approach for traffic maintenance during construction.	The co detaile for rev transp City T
Transit Services	Change to TTC bus routes and stops	A high-order transit service will replace some of the existing TTC routes. Stops/stations will be located where current TTC services, including buses and subways, intersect Eglinton Avenue in order to provide convenient passenger connections between those	 For planning purposes, TTC staff have developed a preliminary bus plan to help guide discussion about LRT facilities and potential bus connections. The preliminary bus plan identifies the following changes to the existing bus network related to the Eglinton Crosstown LRT: no parallel bus routes will be provided along Eglinton Avenue; north-south arterial bus routes will continue to operate; the Don Mills and Eglinton Station will include a new seven-bay 	TTC w service A form public 18 mo Cross

Monitoring / Future Work / Contingency
rill prepare Cultural Heritage Evaluation Reports undertake Heritage Impact Assessments at select o address City of Toronto Heritage Preservation es and City of Mississauga Local Municipal ge Committee requirements during the design
ontractor will be required to prepare and submit a ed and comprehensive Traffic Management Plan, iew by TTC and the Toronto and Mississauga ortation departments.
ansportation Services will monitor.
ill require to continue to monitor the future transit e demands.
al analysis of bus routing changes, including consultation, will be undertaken between 12 and nths prior to the opening of the Eglinton rown LRT.

Factor	Environmental Issue / Concern	Effect / Impact (During Construction; During Operations)	Mitigation Measures	
		services and the LRT.	 bus terminal to service the 25N, 25S, 54 and 100 bus routes; the Keele and Eglinton Station will include a new four-bay bus terminal to service the 32C and 32D bus routes; and, the Caledonia Station will include a new bus loop to service the 47N and 47S bus routes. 	
Navigation	Potential impacts to navigation activities at watercourses	The Humber River, West Don River and East Don River are considered navigable. Therefore, modifications to the Humber River Bridge, including adding an LRT facility, and the West Don River Bridge and East Don River Bridge, including adding an LRT facility and associated bridge widening and possible reinforcement, may require an approval under the Navigable Waters Protection Act.	Measures to mitigate potential impacts on navigable waters will meet the <i>Navigable Waters Protection Act</i> requirements.	The N obtain waters

Navigable Waters Protection Act approval will be ned by TTC prior to construction at navigable rs.

CONSULTATION PROCESS 6.

Introduction 6.1

Overview of Consultation Process 6.1.1

An extensive consultation process was undertaken to assist in the planning and impact assessment process for the Eglinton Crosstown LRT project. The consultation process was designed to address the requirements of Ontario Regulation 231/08. Consultation was conducted during the Preliminary Planning Phase prior to the formal declaration of the Transit Project Assessment process on November 13, 2009 through the issuance of the Notice of Commencement.

Consultation was conducted with the government review agencies, technical agencies and local municipalities, the general public, business improvement areas and ratepayers associations, property owners, Aboriginal communities,

This chapter outlines the consultation carried out during the Preliminary Planning phase and during the formal Transit Project Assessment process. A detailed summary of how the issues noted in Schedule 2 of Ontario Regulation 231/08 were addressed is included in Section 6.4

Staff from key technical agencies and municipalities and the TTC participated in a Technical Advisory Committee which met each month throughout the Preliminary Planning and Transit Project Assessment. Other technical agencies and municipal were engaged through issue-specific meetings, working groups and a stakeholder agency workshop. As well, key study recommendations were endorsed by the Toronto Transit Commission and the City of Mississauga Council and approved by Toronto City Council. Detailed information about technical agency and municipal consultation is presented in Section 6.2.1 and Section 6.3.1.

During the Preliminary Planning phase, a letter was sent to the Ministry of the Environment (MOE), Environmental Assessment Approvals Branch (EAAB) Director requesting input for First Nation Consultation. The details of First Nations Consultation are included in Section 6.2.3.

The general public and property owners were able to choose their level of involvement from one or more of the following options:

- Public open houses,
- Project website, and/or
- Contacting the project team directly (24/7 hot line; fax; e-mail; and regular mail).

At the public open houses, information about the project was presented on display panels arranged in sequence in a public meeting place. Project staff was available at the open houses to answer directly any questions or concerns raised by a member of the public.

As discussed in Section 6.2.4 and Section 6.3.4 four formal rounds of public consultation were undertaken. Appendix M includes reports which summarize public comments submitted for each of round of consultation as well as a log of all public comments received during the study.

6.1.2 Notification Protocol

To notify the general public, business improvement associations, ratepayers associations and property owners within the study area of the consultation dates, newspaper advertisements were placed in the Toronto Star and community-base newspapers. Similar notices were issued by Canada Post mail walk to 72.200 households and business in the study area and were also placed on the project website and posted at key TTC subway stations.

Letters were sent to members of the general public, affected land owners and interest groups by regular mail and/ or by email. As the study progressed, the mailing lists were update to include new individuals taking an interest in the LRT project. In addition, all property owners within 30 metres of the project were advised on the Notice of Commencement.

The Notice of Commencement of the Transit Project Assessment was done in accordance with the requirements of Section 7 (4) of the regulation. Specifically:

- Letters were sent to all property owners within 30 metres of the project: ٠
- Email notices were sent to the MOE Regional Director and EAAB Director in addition to the • government ministries, agencies and local municipalities noted later in this chapter;
- All members of the public that participated in previous consultation events received notification; •
- Newspaper ads were placed in the Toronto Star, Metro News, City Centre Mirror, North York • Mirror, East York Mirror, Scarborough Mirror, and Etobicoke Guardian; and
- A notice was posted on the project website. •

Study Organization and Study Stages 6.1.3

As shown in **Exhibit 181**, the study included two distinct phases: the Preliminary Planning phase and the subsequent Transit Project Assessment process.

The focus of rthe Preliminary Planning phase was to discuss planning issues with stakeholders and identify a project. This phase occurred between March 2008 and November 12, 2009. The consultation undertaken as part of Preliminary Planning is outlined in Section 6.2.

The focus of the Transit Project Assessment process, which commenced on November 13, 2009, was to consult on the project, the alternatives considered, the potential impacts and proposed mitigation measures. The consultation undertaken during the Transit Project Assessment is outlined in Section 6.3.



Preliminary Planning 6.2

Technical Agencies and Municipal Staff 6.2.1

Notification and consultation was carried out to encourage the involvement of government, technical agencies and municipal staff during the Preliminary Planning Phase. The following technical review agencies and municipal departments were engaged during Preliminary Planning and the subsequent Transit Project Assessment process.

The following technical review agencies were invited to be involved in the Preliminary Planning Study as well as the formal Transit Project Assessment process.

Federal Government Review Agencies

Canadian Environmental Assessment Agency Canadian Transportation Agency Indian and Northern Affairs Canada Environment Canada **Department of Fisheries and Oceans** Transport Canada

Provincial Government Review Agencies

Ministry of Aboriginal Affairs Ministry of Agriculture, Food and Rural Affairs Ministry of Citizenship and Immigration Ministry of Culture

Ministry of Energy and Infrastructure Ministry of the Environment Ministry of Municipal Affairs and Housing Ministry of Natural Resources Ministry of Transportation **Ontario Realty Corporation**

Technical Agencies

Bell Canada Enbridge Gas Distribution Enbridge Pipelines Hydro One Networks Incorporated **Rogers** Cable Sarnia Products Pipeline Company, Inc. Sun-Canadian Pipeline Company, Inc. Toronto Hydro Trans-Northern Pipeline Canadian National Railway Canadian Pacific Railway Greater Toronto Airports Authority (GTAA) Toronto and Region Conservation Authority (TRCA) VIA Rail GO Transit

Municipal Staff

City of Mississauga City of Toronto - City Planning City of Toronto – Emergency Medical Services City of Toronto – Transportation Services City of Toronto - Parks Forestry and Recreation City of Toronto – Public Health Conseil Scolaire de district Catholique Centre-Sud **Toronto District School Board Toronto Catholic District School Board Toronto Fire Services Toronto Parking Authority Toronto Police Services** Toronto Water

A Technical Advisory Committee (TAC) was established early in the Preliminary Planning phase to facilitate communication between the study team and key stakeholders, including TTC departments, the City of Toronto (co-proponents), GO Transit and Mississauga Transit. The TAC provided advice to the study team and was consulted on key recommendations during Preliminary Planning.

- City of Toronto City Planning Transportation Planning (East, North and West District)
- City of Toronto City Planning Urban Design •
- City of Toronto Transportation Services

- TTC Service Planning
- GO Transit
- Mississauga Transit

In addition to monthly TAC meetings, focussed meetings were held with government and technical review agencies and City of Toronto and City of Mississauga departments in order to communication key study recommendations and to resolve issues. Exhibit 182 lists meetings held with government review and technical agencies and Exhibit 183 lists meetings held with municipal staff during Preliminary Planning.

Key issues raised and the study team's responses and/ or follow-up actions are summarized in Section6.4.

Date	Agency	Purpose
September 4, 2008	GO Transit	Coordinate future plans with GO Transit
October. 30, 2008	MTO	Coordination with Mississauga BRT
December. 1, 2008	TRCA	Initial meeting with TRCA to review western section of Eglinton Crosstown LRT Project
December 16, 2008	TRCA	Initial meeting with TRCA to review eastern section of Eglinton Crosstown LRT Project
January 8, 2009	TRCA	Initial site visit to review the Humber River, Mimico Creek and Black Creek watersheds
January 12, 2009	TRCA	Site visit to review the Don River watersheds
January 22, 2009	MOE	Present Eglinton Crosstown LRT to MOE
February. 2, 2009	GO Transit	Discuss potential opportunities to interface GO Transit services with the Eglinton Crosstown LRT
March 11, 2009	MTO	Coordination with Mississauga BRT
April. 14, 2009	GTAA	Coordinate the alignment of the Eglinton Crosstown LRT with the Airports Authority
April. 17, 2009	GTAA	Coordinate the alignment of the Eglinton Crosstown LRT with the Airports Authority
April. 28, 2009	GTAA	Coordinate the alignment of the Eglinton Crosstown LRT with the Airports Authority
May 5, 2009	TRCA	Meeting to discuss floodplain and property issues at Jane Street
July 16, 2009	GTAA	Coordinate the alignment of the Eglinton Crosstown LRT with the Airports Authority
July 29, 2008	GTAA	Coordinate the alignment of the Eglinton Crosstown LRT with the Airports Authority
July 29, 2009	MOE	Consultation/Coordination with the Project Officer from MOE
August 24, 2009	MTO	Coordination with Mississauga BRT

Discusion Technical Association Marstin

Date	Agency	
August 27, 2009	MOE	Present overview of Eg scopes of work for Air, investigations
September 2, 2008	GTAA	Coordinate the alignme Authority
September. 15, 2009	TRCA	Site visit to review surfa Black Creek and West
September 29, 2009	TRCA	Site visit to review surfa Don River, East Don R
December. 18, 2009	GTAA	Coordinate the alignme Authority

In accordance with TRCA's requirements, a copy of all letters issued by TRCA during Preliminary Planning and the Transit Project Assessment are included in Appendix M.

Exhibit 183: Preliminary Plannin Date **City/ Department** April 17, 2008 City of Mississauga Coord June 10, 2008 City of Toronto - Toronto Propo Water June 18, 2008 City of Mississauga Coord City of Toronto - City September 16, 2008 Don Planning Kick-October 21, 2008 City of Toronto - City Obtai Planning Distri November 5, 2008 City of Toronto - City Don Planning Initial City of Toronto - City December 8, 2008 Work Planning & Transportation Services City of Toronto - City December. 12, 2008 Work Planning & Transportation Services January 20, 2009 City of Toronto - City Traffi Planning & **Transportation Services** January 22, 2009 City of Toronto - Toronto Propo Water January 28, 2009 City of Toronto - City

Toronto Transit Commission/City of Toronto EGLINTON CROSSTOWN LIGHT RAIL TRANSIT TRANSIT PROJECT ASSESSMENT Environmental Project Report

Purpose

linton Crosstown LRT to MOE staff and to review Noise and Vibration, and Water Resources

ent of the Eglinton Crosstown LRT with the Airports

ace water issues at Mimico Creek, Jane Street, **Tunnel Launch Site**

face water issues at East Tunnel Launch Site, West River, Wilson Brooke and Massey Creek

ent of the Eglinton Crosstown LRT with the Airports

g - Municipal Staff Meetings
Purpose
dination with Mississauga BRT
osed water main at Mt. Pleasant Road
dination with Mississauga BRT
Mills LRT/Eglinton Crosstown LRT Special Study off
in information on development plans in the North ct
Mills LRT/Eglinton Crosstown LRT Screening of Alternatives
shop on Traffic Issues – West Surface Section
shop on Traffic Issues – East Surface Section
c Issues – Wynford and Victoria Park
osed water main at Mt. Pleasant Road

Traffic Issues – Martin Grove, Kipling and Jane

Date	City/ Department	Purpose
	Planning & Transportation Services	
February. 2, 2009	City of Toronto - City Planning & Transportation Services	Traffic Issues – Wynford and Victoria Park
February 6, 2009	City of Toronto - Toronto Water	Proposed water main at Mt. Pleasant Road
March 11, 2009	City of Mississauga	Coordination with Mississauga BRT
March 27, 2009	City of Toronto - Transportation Services	Traffic Analysis – U-turn versus standard intersection configuration
March 30, 2009	City of Mississauga	Coordination with Mississauga BRT
Apr. 7, 2009	City of Toronto - City Planning & Transportation Services	Black Creek traffic and Maintenance and Storage (pocket) access analysis
April 8, 2009	City of Toronto - City Planning	Station Entrances
April 21, 2009	City of Toronto - City Planning & Transportation Services	Interface with Jane LRT
April 30, 2009	City of Toronto - City Planning	Station Entrances
May 1, 2009	City of Toronto - Transportation Services	Intersection Concepts – West Surface Section
May 1, 2009	City of Toronto - Transportation Services	Intersection Concepts – East Surface Section
May 1, 2009	City of Toronto - City Planning	Don Mills LRT/Eglinton Crosstown LRT Special Study Final Results
May 7, 2009	City of Toronto - Parks, Forestry & Recreation	Meeting to discuss floodplain and property issues at Jane Street
May 22, 2009	City of Toronto - Police, Fire, EMS	Consultation with issues related to property owned by these services
June 6, 2009	City Planning & Transportation Services	Black Creek traffic and Maintenance and Storage (pocket) access analysis
July 13, 2009	City of Mississauga	Coordination with Mississauga BRT
August 14, 2009	City of Toronto - Transportation Services	Updated traffic analysis
September 3, 2009	City of Toronto - City Planning	Station Entrances
September 9, 2009	City of Toronto - City	Black Creek traffic and Maintenance and Storage

Date	City/ Department	
	Planning & Transportation Services	(pock
September 10, 2009	City of Toronto - Transportation Services	Traffi
October 2, 2009	City of Mississauga	Coord
October 14, 2009	City of Mississauga	Coord
October 20, 2009	City of Mississauga	Coord
October 28, 2009	City of Toronto - Parks, Forestry & Recreation	Meeti where buildi
November. 13, 2009	City of Toronto - Parks, Forestry & Recreation	Discu

6.2.2 Municipalities

In addition to the involvement of municipal staff on technical elements of the study, municipal political representatives in the City of Toronto and the City of Mississauga were provided with project overview presentations at key milestones during Preliminary Planning. The dates of key meetings held are noted in **Exhibit 184.**

Exhibit 184: Preliminary Planning – Municipal Meetings

Date	Purpose
August 7, 2009	City of Toronto Councillor Briefing – First Round of Public Open Houses
June 3 and 4, 2009	City Councillor Briefing – Second Round of Public Open Houses
August 31, 2009	City Councillor Briefing – Third Round of Public Open Houses

6.2.3 Aboriginal Consultation

Ontario Regulation 231/08 requires transit project proponents to request from the Ministry of the Environment's Environmental Assessment and Approvals Branch "for a list of bodies that, in the opinion of the Director, would be able to assist in identifying aboriginal communities that may be interested in the transit project" (Section 7(4)(a). On November 11, 2008, the TTC wrote to the Environmental Assessment and Approvals Branch to request agency contacts that could assist in identifying potentially interested aboriginal communities for the Transit City projects including the Eglinton Crosstown LRT.

The MOE Environmental Assessment and Approvals Branch (Zeljko Romic) wrote the TTC on December 3, 2008 with detailed information regarding agencies to assist in identifying potentially interested communities. The agencies included: Ontario Ministry of Aboriginal Affairs, and Indian and Northern Affairs Canada (INAC): (Specific Claims, Litigation Management and Resolution Branch (LMRB) and Comprehensive Claims).

Toronto Transit Commission/City of Toronto EGLINTON CROSSTOWN LIGHT RAIL TRANSIT TRANSIT PROJECT ASSESSMENT Environmental Project Report

Purpose

ket) access analysis

ic analysis update

dination with Mississauga BRT

dination with Mississauga BRT

dination with Mississauga BRT

ing to discuss property issues on City parklands e station entrances, fire vent shafts, emergency exit ings or traction power substations would be located.

uss the West Launch Shaft site at Keelesdale Park

During the first round of public consultation in the preliminary planning phase, notices were sent to:

- INAC Specific Claims, LMRB and Comprehensive Claims (July 31, 2008),
- Ministry of Aboriginal Affairs (July 31, 2008), and
- Mississaugas of the New Credit First Nation (July 31, 2008).

No comments were received from these organizations during the first round of open houses.

During the second round of consultation in the preliminary planning phase, notices were sent as follows:

- INAC Specific Claims, INAC LMRB, and INAC Comprehensive Claims (June 3, 2009),
- Ontario Ministry of Aboriginal Affairs (June 3, 2009), and
- Mississaugas of the New Credit First Nation (June 3, 2009).
- No comments were received from these organizations during the second round of open houses.

On September 2, 2009, an additional open house was held to specifically discuss the section of the LRT from Martin Grove Road to Pearson International Airport. Notices for this additional open house during preliminary planning were sent to the Mississaugas of the New First Nation (August 21, 2009). No comments were received from the Mississaugas as part of this Open House.

General Public and Property Owners 6.2.4

Involvement of the general public, community associations, ratepayers groups and property owners was an integral component of the study.

The following community associations and ratepayers groups received notification of public consultation events during both Preliminary Planning and the Transit Project Assessment process:

- Avenue Road Eglinton Community Association
- Bayview Blythwood Ratepayers Association
- Canadian Hispanic Congress
- Centennial Community Ratepayers Association
- Clairlea Regent Heights Neighbourhood Association
- Community of Rathburn-Grove Ratepayers
- **Confederation of Resident & Ratepayers Associations**
- Corvette Residents' Association
- Eglinton Way BIA
- Green Hills Residents' Association
- Islington Ratepayers & Residents Association
- Kennedy Road BIA
- Leaside Business Park
- Leaside Property Owners Association

MARCH 2010

- Markland Homes Association •
- Martin Grove Ratepayers' Association
- Maryvale Community Association •
- Midland Park Community Association
- Mount Dennis Community Association
- North Leaside Resident Association
- **Renaissance Tenants Association**
- Santamonica Birchmount Neighbourhood Association
- Silverthorne Ratepayers Association
- St. Andrew-St. Patrick Tenants Association
- The Princess Anne Manor Ratepayers Association
- Upper Village BIA .
- West Deane Homeowners Association
- West Gate Residents Association .
- Wexford BIA .
- Wynford/Concorde Residents Association
- York-Eglinton BIA

Key public consultation dates during preliminary planning were:

- First round of public open houses August 14 to September 22 2009 (6 locations),
- Ward 12 Open House December 9, 2008,
- Second round of public open houses June 15 to July 29, 2009 (6 Locations), •
- TTC Advisory Committee on Accessible Transit July 27, 2009,
- Don Mills Residents Incorporated July 27, 2009, and
- Third round public open house September 2, 2009.

Three rounds of public open house were held at key points during the Preliminary Planning phase. At each open house display panels were presented for public review and representatives TTC, City of Toronto, City of Mississauga (third open house only), and the consultants were available to discuss the study on a oneon-one basis with members of the public.

First Round of Public Open Houses (August 14 to September 22, 2008

The first round consisted of six open houses held between August 14, 2008 and September 22, 2008. The purpose of the first round was to share information about the Eglinton Crosstown LRT project with the community and to gather feedback on preliminary project plans. Each open house presented information on:

The planning context (rationale) for the LRT on Eglinton Avenue; ٠

- Background information about the Eglinton Avenue Corridor (such as consistency with City and • Provincial Plans, existing conditions and a description of LRT technology);
- Proposed surface and underground sections;
- Proposed stop and station locations; and
- Potential construction methods.

The level of public participation for the first round of open houses is summarized in Exhibit 185.

Exhibit 185: First Round of Public Open Houses – Summary of Participation				
	Location	Number of Participants signed-in	Number of Comments Forms Received	
August 14, 2008	Forest Hill Memorial Arena	119	35	
	340 Chaplin Crescent			
August 19, 2008	Leaside Arena	172	45	
	1073 Millwood Road			
August 25, 2008	Humber Valley United Church	209	52	
	76 Anglesey Boulevard			
August 27, 2008	Don Montgomery Community Centre	48	8	
	2467 Eglinton Avenue East			
September 4, 2008	Richview Baptist Church	70	11	
	1548 Kipling Avenue			
September 22, 2008(*)	Centennial Recreation Centre	73	18	
	2694 Eglinton Avenue West			
	Total	691	169	

(*) Joint Open House with the Jane LRT

Ward 12 Open House (December 9, 2008)

In addition, at the request of Councillor Frank DiGiorgio, an informal open house was held on December 9, 2008. The open house included the same presentation materials as the first round of public open houses. A total of twelve members of the public signed in at this event.

Second Round of Public Open Houses (June 15 to July 29, 2009)

The second round of public open houses were held at six locations June 15, 2009 and July 29, 2009. Initially, the open houses were scheduled to conclude by June 25, 2009, but the final open house was rescheduled to July 29, 2009 due to a civic strike. The purpose of the second round was to provide:

- Responses to frequently heard comments at Open House 1;
- Key objectives of the Eglinton Crosstown LRT;
- Typical portal, stop and station plans;
- Details of specific surface stops and underground stations (including proposed station entrance locations):
- Traffic management for surface LRT stops (including rerouted left turns at 10 key intersections); •
- Potential corridors for the LRT between Martin Grove Road and Pearson International Airport; and
- Potential underground construction methods (including twin bore and single bore tunnelling). •

In addition to notification to the general public through the methods described in Section 6.1.2, letters were issued to private property owners to advise of preliminary full and partial property requirements defined to date through the Preliminary Planning process.

The level of participation during the third round of Open Houses is summarized in Exhibit 186.

Date	Location	Number of Participants signed-in	Number of Comment Forms Received
June 15, 2009	William Lea Room 1073 Millwood Road	257	82
June 17, 2009	Eglinton Public School 223 Eglinton Avenue East	160	37
June 18, 2009	Richview Collegiate 1738 Islington Avenue	275	35
June 23, 2009	York Memorial Collegiate 2690 Eglinton Avenue West	99	15
June 24, 2009	Beth Sholom Synagogue 1445 Eglinton Avenue West	168	44
July 29, 2009	Ionview Heights United Church 115 Ionview Road	45	7
	Total	1,004	220

Dons Mills Residents, Inc. (July 27, 2009)

A meeting was held at the request of the Don Mills Residents, Inc. to review the Eglinton Crosstown LRT project in general and the options for Don Mills Station and Wynford Stop. In addition to the general project comments received, feedback was given regarding the assessment of the two Don Mills LRT interface options (including the proposed bus Terminal) and the two options at Wynford Drive.

TTC Advisory Committee on Accessible Transportation (ACAT) (July 27, 2009)

An overview of the materials provided for public review and comment at the second round of public open houses was presented to the ACAT Design Review Sub-committee for information.

Third Round Public Open House (September 2, 2009)

Subsequent to the completion of the second round, a separate open house was held on September 2, 2009 at the Etobicoke Olympium at 590 Rathburn Road. The purpose of this round of consultation was to present the recommended route for the LRT from Martin Grove Road to Pearson International Airport.

The open house presentation materials included:

- The five alternative routes between Martin Grove Road and Pearson International Airport:
- Reasons for selecting Route 1 (via Eglinton Avenue, Commerce Boulevard, Convair Drive and Silver Dart Drive) as the preferred route; and
- Stop concepts for the recommended route.

A total of 139 participants signed in, and 30 comment forms were submitted.

Transit Project Assessment 6.3

Technical Agencies and Municipal Staff 6.3.1

The involvement of the government agencies, technical agencies and municipal staff as listed in Section 6.2.1 continued through the Transit Project Assessment phase.

Stakeholder Agency Workshop (January 8, 2010)

A stakeholder agency workshop was held to present the preferred design and proposed environmental impacts and impacts and to solicit comments from government review and technical agencies in advance of issuance of the draft Environmental Project Report.

Thirty-seven staff representing the government and technical review agencies and municipal departments listed below attended the workshop:

- **Bell Canada**
- Canadian Environmental Assessment Agency
- City of Mississauga
- City of Toronto City Planning (Transportation Planning)
- City of Toronto City Planning (Urban Design)
- MARCH 2010

- City of Toronto Emergency Medical Services •
- City of Toronto Fire Services •
- City of Toronto Parks, Forestry and Recreation •
- City of Toronto Transportation Services
- Enbridge Gas Distribution
- Metrolinx/GO Transit
- Ministry of the Environment •
- Ministry of Transportation
- Rogers Cable
- Toronto and Region Conservation Authority
- Toronto Hydro
- **Toronto Water**

The meeting included a presentation of the preferred design as well as proposed environmental impacts and mitigation measures. Attendees participated in facilitated discussion groups and completed work books which requested comments about the proposed environmental impacts and mitigation measures, commitments to future work (to be included in the Environmental Project Report) and permits and approvals required for implementation of the Eglinton Crosstown LRT. Comments heard at the Stakeholders Workshop are summarized in Exhibit 172 shown later.

As for the Preliminary Planning phase, and as summarized in Exhibit 187 and Exhibit 188, focused meetings were held during the Transit Project Assessment to address key issues.

Exhibit 187: Transit Project Assessment - Meetings with Technical Review Agencies Purpose

Date	Agency	
November 25, 2009	CEAA	Conference the Canadi
January 5, 2010	TRCA	Follow-up t 2009 and to Water Man

Exhibit 188: Transit Project Assessment - Meetings with Municipal Staff

Date	Agency	
November 13, 2009	City of Toronto – Parks, Forestry and Recreation	Meeting to Community
January 21, 2010	City of Toronto – Parks, Forestry and Recreation	Meeting to o Features Pr to review th
February 1, 2010	City of Toronto-	Meeting to

e call to discuss Project Description prepared under an Environmental Assessment Act

to site visits held on Sept. 15, 2009 and Sept. 29, to review TRCA comments on Drainage and Storm agement Report and Structures Report

Issues

coordinate the design of the Keelesdale Centre with the West Launch Site

discuss the requirement of the Ravine and Natural rotection by-law and the Tree Protection by-law and he design of the Wynford stop

review Cultural Hertiage Assessment Report

Date	Agency	Issues
	Heritage Preservation Services	
February 1, 2010	City of Toronto – Parks, Forestry and Recreation	Subsequent meeting to discuss the West Launch Site at Keelesdale Park

As part of the government and technical reviewed agency consultation, technical special reports to key agencies as requested. **Exhibit 189** lists which agencies received the technical specialist reports.

Technical Specialist Report	Circulation Agency
Air Quality	Ministry of the Environment
Stage 1 and Stage 2 Archaeological Assessment Report	Ministry of Culture
	City of Toronto - Heritage Preservation Services
Cultural Heritage Assessment Report	City of Toronto - Heritage Preservation Services
Drainage and Storm Water Management Report	Toronto and Region Conservation Authority
Geotechnical Assessment Report	Toronto and Region Conservation Authority
Hydrogeological Assessment Report	Toronto and Region Conservation Authority
Natural Heritage Assessment Report	City of Toronto – Parks, Forestry and Recreation
	Toronto and Region Conservation Authority
Noise and Vibration Assessment Report	Ministry of the Environment
Traffic	City of Toronto – Transportation Services
	City of Toronto – City Planning
	Ministry of Transportation
	City of Mississauga

6.3.2 Municipalities

There was continued involved of municipal political representatives in the City of Toronto and the City of Mississauga during the Transit Project Assessment Process. The Toronto Transit Commission, Toronto City Council and City of Mississauga Council have endorsed the Transit Project and the filing of the Environmental Project Report. Key municipal consultation dates are noted in Exhibit 190.

Exhibit 190: Transit Project Ass	ess
Date	
November 17, 2009	Т
December 4, 2009	Т
December 2, 2009	N
January 19, 2010	C
February 17, 2010	Т

6.3.3 Aboriginal Consultation

Following clarification received during the Scarborough Malvern LRT project, all Williams Treaty Bands were contacted in addition to the Mississaugas of the New Credit First Nation. The following contacts were made:

- November 12, 2009: a letter and Notice of Commencement was sent to all Williams Treaty Bands and their legal coordinator Ms. Karry Sandy McKenzie asking for written confirmation of any interest they may have in the project. The Williams Treaty Bands include: Alderville, Beausoleil, Chippewas of Georgina Island, Chippewas of Rama, Curve Lake, Hiawatha, Mississaugas of Scugog, Moose Deer Point First Nations.
- November 12, 2009: The Mississaugas of the New Credit were contacted via e-mail (their • preferred method and asked to provide written confirmation of any interest they may have in the project); and
- November 12, 2009: Notices were sent to INAC Specific Claims, INAC LMRB, and INAC ٠ Comprehensive Claims and the Ontario Ministry of Aboriginal Affairs to confirm First Nation contacts.

Chief Sharon Stinson Henry (Chippewas of Rama First Nation) confirmed receipt of the Notice of commencement and letter via e-mail on November 12, 2009 and did not express interest. The Alderville First Nation (Shelley Gray - Consultation Coordinator) confirmed receipt of the Notice of Commencement and letter on January 7th, 2009. The Alderville First Nation expressed no concerns with the project but wishes to be contacted should any environmental or archaeological issues arise. A letter dated October 29th, 2009 from the Beausoleil First Nation acknowledged receipt of the Preliminary Planning notice for the Eglinton LRT.

Follow-up emails asking for confirmation of receipt of the November 12 letter and Notice of Commencement for the Eglinton Crosstown LRT were e-mailed to the Mississaugas of the New Credit and all Williams Treaty First Nations on January 4, 2010.

Follow-up phone calls were made to the Mississaugas of the New Credit First Nation on Feb 22nd and to all Williams Treaty Bands and Ms. Karry Sandy McKenzie, their legal coordinator on February 23 and 24, 2010. On Feb 23rd, the Chippewas of Georgina confirmed receipt of the Notice of Commencement, as did the Curve Lake First Nation. Neither expressed concerns and Curve Lake (Chief Knott) indicated an interest in being notified of any archaeological finds.

Toronto Transit Commission/City of Toronto EGLINTON CROSSTOWN LIGHT RAIL TRANSIT TRANSIT PROJECT ASSESSMENT **Environmental Project Report**

sment - Municipal Consultation

Purpose

oronto Transit Commission

oronto City Council

Aississauga City Council

City of Toronto Pedestrian Committee

Foronto Transit Commission

As of February 25, 2010, no specific interest or concerns have been raised by The Mississaugas of the New Credit and/or by any of the Williams Treaty Bands.

A Notice of Completion will be sent to all First Nations agencies, Williams Treaty Bands and the Mississaugas of the New Credit First Nation with an additional request for each First Nation to express any interest they may have in writing and to confirm receipt. Furthermore, these First Nations will be contacted immediately should any potential First Nation archaeology be discovered.

6.3.4 General Public and Property Owners

Through November and early December, 2009, seven Open Houses were held across the study corridor after the formal Notice of Study Commencement was issued. The following summarizes consultation undertaken. Key public consultation events held during the Transit Project Assessment Process were:

- TTC Advisory Committee on Accessible Transportation Design Review Sub-Committee (November 18, 2009),
- Fourth Round of Public Open Houses (November 23, 2009 to December 10, 2009) (seven locations),
- Mount Dennis Community Meeting December 14, 2009,
- Ward 34 Open House January 14, 2010,
- Airport Corporate Centre Businesses Meeting January 18, 2010,
- Mount Dennis Community Association Meeting hosted by Councillor Lindsay Luby January 28, 2010,
- Latvian Canadian Cultural Centre Board of Directors Meeting Feb 1, 2010,
- Ward 4 Community Meeting February 3 2010,
- Ward 34 Meeting hosted by Councillor Minnan Wong Feb 9, 2010,
- Wards 11 and 12 meeting hosted by Councillors Nunziata and Di Giorgio Feb 11, 2010

During the Transit Project Assessment Process, TTC issued notification to all property owners for whom permanent full or partial property acquisition requirements were identified through the preliminary planning process. Several owners attended the fourth round of public open houses. Additional meetings were arranged with affected property owners upon request.

Fourth Round Public Open Houses (November 23 to December 10, 2009)

The purpose of the public open houses was to provide information covering:

- Response to frequently heard comments at Open Houses 2 and 3;
- Details and locations of specific surface stops and underground stations;
- Recommendations at Jane Street., Black Creek Drive, Wynford Drive. and Don Mills Road.;
- Locations of surface facilities (station entrances, emergency exit buildings, ventilation shafts and traction power substations);
- Recommended traffic management (including rerouted left turns at nine key intersections);

Construction methods; and

•

Potential environmental impacts and recommended mitigation measures.
 Exhibit 191 summarizes the level of participation for the fourth round of public open houses.

Exhibit	191:	Fourth	Round	of Or	ben

Date	Location	Number of Participants signed-in	Number of Comment Forms Received
November 23, 2009	York Memorial Collegiate 2690 Eglinton Avenue West	112	14
November 24, 2009	Etobicoke Olympium 590 Rathburn Road	125	11
November 25, 2009	Northern Secondary School 1929 Bayview Avenue	161	19
November 26, 2009	Richview Collegiate 1738 Islington Avenue	206	34
December 2, 2009	Canadian National Institute for the Blind 851 Mt. Pleasant Road	122	34
December 8, 2009	Don Montgomery Community Centre 2467 Eglinton Avenue East	63	14
December 10, 2009	Beth Sholom Synagogue 1445 Eglinton Avenue West	71	13
	Total	860	139

TTC Advisory Committee on Accessible Transportation (November 18, 2009)

A presentation was made to the ACAT Design Review Subcommittee meeting of November 18, 2009 to provide an overview of the recommendations approved by the Commission at is November 17, 2009. Subcommittee members registered concerns about stop and station spacing and recommended the implementation of parallel bus service.

Mount Dennis Community Meeting (December 14, 2009)

The Mount Dennis Community Association and Councillor Frances Nunziata invited the TTC to a community meeting to discuss the LRT on December 14, 2009. Approximately 75 residents attended. Specific information was presented by project staff related to the rationale for selecting a surface LRT alignment versus an underground option. The councillor invited all residents who had been formally contacted by TTC regarding property impacts. Therefore, project staff explained the property acquisition

Toronto Transit Commission/City of Toronto EGLINTON CROSSTOWN LIGHT RAIL TRANSIT TRANSIT PROJECT ASSESSMENT Environmental Project Report

Houses – Summary of Participation

process in detail to the residents in attendance to ensure they had a clear understanding. Residents and Councillor Nunziata indicated they would follow-up with TTC to confirm a community position regarding preference for above ground versus below-ground LRT in advance of the Commission meeting in order for deputations to be made from local residents directly to the City Councillors overseeing the Commission.

Ward 34 Open House (January 14, 2010)

At the request of Councillor Denzil Minnan-Wong, an additional public open house was held at the Latvian Centre; 144 participants signed in at the event and 30 comment forms were received. The key issue raised by meeting attendees was strong opposition to the recommended removal of the LRT stop at Swift Drive/ Credit Union Road.

Airport Corporate Centre Businesses (January 18, 2010)

In response to a motion raised at the December 2, 2009 Mississauga Council meeting, City of Mississauga staff hosted an information meeting for Airport Corporate Centre (vicinity of Eglinton Avenue and Commerce Drive, south of Highway 401) businesses. The event opened with a presentation by City of Mississauga staff about the Mississauga Bus Rapid Transit project staff. TTC provided an overview presentation of the Transit Project Assessment Process recommendations for the Airport Corporate Centre area. Following the presentations, an informal question and answer session was held. The meeting was attended by 3 persons representing two property owners.

Mount Dennis Community Association Meeting (January 28, 2010)

The Mount Dennis Community Association board invited TTC staff, Councillors Nunziata and Di Giorgio to discuss their concerns with surface LRT, and propose an alternative design option. The Mount Dennis Community Association put forward a hybrid option. The Mount Dennis Community Association proposal was for a half surface LRT on the north side of Eglinton Avenue (from the planned Black Creek portal to the rail corridor bridge) and half underground tunnel (from the west side of the rail corridor bridge under Weston Road and emerging at a portal on the east side of Jane street.

The Mount Dennis Community Association indicated their proposal was based on attempting to minimize additional cost requirements by including a surface section, bypass the need for undercutting the rail corridor supports, minimize traffic disruption and minimizing residential acquisition. Mount Dennis Community Association noted they were particularly interested in ensuring a full surface stop to serve the new recreation centre, a hub connection with the GO line, and new green space created by the tunnel deck from the rail corridor to Weston Road.

Councillors Di Giorgio and Nunziata stated that their preference was not for a hybrid option or surface LRT but only for underground LRT from Keele Street to Jane Street. Councillor Di Giorgio expressed specific concerns with surface LRT and the Mount Dennis Community Association's hybrid proposal in terms of traffic back-ups at Black Creek.

TTC reviewed the Mount Dennis Community Association proposal and indicated significant concerns with LRT operations and traffic flow, and traffic safety for the proposed north side of Eglinton Avenue surface alignment.

Latvian Canadian Cultural Centre Board of Directors Meeting (February 1, 2010)

On February 1, 2010, TTC staff attended a meeting at the Latvian Canadian Cultural Centre with members of the Board of Directors and members of the Latvian Canadian Cultural Centre. This was a follow-up initiative to the Open House held at the Centre on January 14, 2010 with Councillor Minnan-Wong (Ward 34).

Led by the Chair of the Board of Directors of the Latvian Canadian Cultural Centre, several members declared their opposition to the removal of the stop, stating their belief that the decision to remove the stop will have detrimental effects to usership of the Centre, especially by the senior population.

TTC staff explained the rationale for recommending against the stop due to the steep grade of Eglinton Avenue between the Don River Valley and Swift/Credit Union. Specifically the intersection would need to be lowered by 6 metres. As well as additional costs, this treatment would also require the closure or relocation of driveways at 3 Swift Drive, 25 Swift Drive, and 1681 Eglinton Avenue. TTC noted that the nearest LRT stop at Bermondsey is located 350 metres to the east. The maximum walking distance to the Bermondsey Stop is 600 metres, considered an acceptable walking distance to transit.

The ECLRT team explained that although the technical recommendation to remove the stop had already been approved by City Council, groups wishing to provide feedback could submit letters or make deputations directly to the TTC Commission on February 17 when a report on the public consultation results would be considered by the Commission. TTC provided Latvian Canadian Cultural Centre members with some further engineering information in advance of the Commission presentation deadline regarding an option suggested at the meeting to modify the bridge over the East Don River Valley.

Ward 4 Public Meeting (February 3, 2010)

Councillor Lindsay Luby hosted a meeting at Richview Collegiate to discuss rerouted left turns at major intersections in Ward 4. The meeting was attended by 120 members of the public. TTC staff made a presentation about the rerouted left turns and Metrolinx staff provided an overview of the Transit City Program.

Residents largely indicated they would prefer a subway as opposed to surface LRT as they were concerned about traffic and noise.

Ward 34 Meeting (February 9, 2010)

On February 9, 2010 TTC staff attended a meeting eam met in a common room in the condominium at 1700 Eglinton Avenue East. The meeting was arranged by Councillor Minnan-Wong as a follow-up to a January 14, 2010 Open House to discuss the Transit City technical recommendation to eliminate a stop at Swift/Credit Union, in the vicinity of where the meeting was held.

The Councillor's office issued invitations to local stakeholders including the President of the local Parkway Honda dealership at 1681 Eglinton Avenue East, representatives of condominium buildings and property management companies in the area and the Victoria Village Residents Association. A representative from the Latvian Canadian Cultural Centre also attended to represent the Latvian Canadian Cultural Centre.

TTC staff explained the rationale for recommending against the stop due to the steep grade of Eglinton Avenue between the Don River Valley and Swift/Credit Union and distributed a hand-out outlining that the

intersection would need to be lowered by 6 metres. As well as additional costs, this treatment would also require the closure or relocation of driveways at 3 Swift Drive, 25 Swift Drive, and 1681 Eglinton Avenue.

TTC staff advised that the nearest LRT stop at Bermondsey is located 350 metres to the east. The maximum walking distance to the Bermondsey Stop is 600 metres, considered an acceptable walking distance to transit.

Attendees raised questions regarding the retaining walls that would be necessary if a stop was recommended and various engineering accommodations that would have to be adopted with a stop at Swift/Credit Union were explained.

General information about the Transit City Eglinton LRT line were discussed, including the centre median operation and at-grade operation, as well as general construction season impacts.

Ward 11 and Ward 12 Community Meeting (February 11, 2010)

Councillors Nunziata and Di Giorgio hosted a meeting and invited TTC to clarify the challenges of building an underground and an above ground LRT in order for their constituents, in order to confirm a community preference to present directly to the TTC Commissioners. Approximately 150 residents attended and they indicated a strong preference for an underground LRT from Keele Street to Jane Street.

Residents raised specific concerns with surface LRT in regards to traffic and safety - particularly for crossings at Black Creek, Weston Road and Jane Street. Residents expressed access concerns with surface LRT to York Memorial Collegiate, the future recreation centre on the south side of Eglinton, as well as both vehicular and pedestrian access concerns to Keelesdale Park and Eglinton Flats.

TTC indicated that the cost of underground LRT options, including underground stations from Keele Street to Jane Street ranges from \$200-300 million compared to the surface LRT and analysis shows that traffic and pedestrian flow would be accommodated by surface LRT operations.

The audience indicated that extra money should be spent for underground LRT to Jane Street, even if that means re-allocating funds from other Transit City lines. Although outside the scope of this TPA, many residents from the Green Hills Community Association in Councillor Di Giorgio's ward spoke out against a future maintenance and storage (pocket) facility location at Black Creek.

6.4 Summary of Consultation

The input received through the consultation processes undertaken during the Preliminary Planning and Transit Project Assessment phases indicate that there is broad public and stakeholder support for the Eglinton Crosstown LRT. As indicated throughout this chapter (and described in further detail in **Appendix M**) a number of concerns were also raised by the general public and by stakeholders. The key comments raised up to January 25, 2010 and how they were addressed is outlined in **Exhibit 192**.

Exhibit 192: Comment Tracking Table			
Project Element	Comment/Issue	How Comment Was Addressed	Stakeholders
1) Airport Extension	Preferred routes from Martin Grove to the Airport (some members of the public preferred Renforth/Commerce, others preferred Highway 27)	A special study was undertaken to evaluate 5 proposed routing options between Martin Grove Road and the Airport. The preferred alignment is from Martin Grove Road along Eglinton Avenue to Commerce Boulevard, then Commerce Boulevard across Highway 401 to Convair Drive and Silver Dart Drive.	City of Toronto – Transportation Services City of Toronto - City
			Planning
			GOTTANSI
			MIO
2) Business Impacts	Concern about pedestrian and vehicular access to businesses during construction	TTC will prepare detailed maintenance of traffic plans during design to address traffic issues during the construction phase. The plan will include pedestrian access to businesses.	Business Improvement Areas
			City of Toronto – Transportation Services
3) Connection with BRT	BRT and LRT interchange at Commerce Boulevard needs to be further addressed/examined to provide convenient transfer	The interface between the Mississauga BRT station and the Eglinton Crosstown LRT will be refined during the design phase	Mississauga BRT GO Transit
4) Construction	Single bore tunnel is preferred over twin bore tunnel	Analysis has concluded that this alternative is less desirable due to:	General Public
Wethod	for building the underground section	• The lower station platform of the single bore tunnel scheme would have been less desirable for passengers moving between the surface and platform levels	Technical Advisory Committee
		The technology for the single bore tunnel would have been in excess of 13 metres in diameter and would have been without precedent as the largest bore ever attempted in North America Evisting geological state would have resulted in higher risk of ground impacts at the surface and to adjacent	
		• Existing geological strata would have resulted in higher lisk of ground impacts at the surface and to adjacent buildings during the boring operations	
5) Cycling	Provide for cycling lanes and bike facilities	The standard cross-section for the Eglinton Crosstown LRT includes bicycle lanes on each side of the road. In the area between Martin Grove Road and Jane Street, no bike lanes will be provided, as the existing bike path will serve as the primary bicycle route.	City of Toronto – Transportation Services
			General Public
6) East Mall Stop	A stop is needed at East Mall at the ramp from Highway 427 to Eglinton Avenue West	A detailed traffic assessment was prepared for the intersection of the ramp from Highway 427 to the Eglinton Avenue West/East Mall intersection. A bus queue jump lane is proposed to provide an opportunity for bus riders on the 191 Highway 27 Rocket to transfer to the Eglinton Crosstown LRT.	City of Toronto – Transportation Services
			МТО

Project Element	Comment/Issue	How Comment Was Addressed	Stakeholders
7) Network Connectivity	Ensure that the LRT system interfaces with the existing subway and other transit systems such as GO Transit	The Eglinton Crosstown LRT will interface with the Mississauga BRT at the proposed BRT station near Commerce Drive. It will also interface with the Spadina Subway at Eglinton West Station, the Yonge Subway at Eglinton Station, and the Scarborough RT/Danforth Subway at Kennedy Station. Future connections with GO Transit rail lines will be protected at Weston Road (GO Georgetown line) and at Caledonia Station (GO Barrie-Bradford line). The Eglinton Crosstown LRT will also interface with the Jane LRT, the Don Mills LRT and the Scarborough/Malvern LRT lines.	Mississauga Transit GO Transit
8) Noise and Vibration	Noise and Vibration and vibration concerns during construction and during operations phase	A detailed noise and vibration study was carried out in accordance with the established MOE/TTC Protocol. No noise impacts are anticipated from LRT operations. A noise barrier is proposed for the Keele Bus Terminal. Further analysis is recommended to determine any noise impacts and potential mitigation measures from traction power substations and station vent shafts. No vibration impacts are expected from LRT operations in general running track areas. Further analysis will be undertaken during design to assess vibration impacts at special trackwork areas.	Local Residents
9) New Bridge	Length of time required for gaining approval of Bridge over Highway 401	Coordination with Ministry of Transportation is underway to obtain approval for a new LRT structure over Highway 401 in Mississauga	МТО
10) Number of Lanes	Maintain at least four lanes of traffic (2 lanes per direction) – loss of lanes will result in increased traffic congestion	In the west surface section, the current lane configuration is two travel lanes in each direction from Commerce Boulevard to Weston Road. In the east surface section, the existing lane configuration is two general purpose travel lanes in each direction plus one peak period HOV lane in each direction. The standard cross-section for the Eglinton Crosstown LRT consists of two travel lanes in each direction and will not affect traffic.	City of Toronto – Transportation Services City of Toronto – City Planning
11) Parking	Request for commuter parking lots	No commuter parking is included in the Transit City Plan, of which the Eglinton Crosstown LRT is included. The focus of access to the LRT is by pedestrians and by transit users transferring from other modes (bus, subway, RT, other LRT lines)	General Public
12) Allen Station	Impacts to 13 Division Property near Eglinton West Station	Placement of a station entrance at Eglinton West Station on the south side of Eglinton Avenue west will impact land owned by the 13 Division of Toronto Police Services. A concept plan for mitigating the impact to the parking lot was prepared and accepted by Police Services.	City of Toronto –Police Services
13) Property Impacts	Concern about impacts to private property	Compensation will be provided for temporary and permanent property requirements. For permanent property taking, compensation will be provide at fair market value, which is determined at the time of purchase with a property appraisal report forming the basis of negotiations. Compensation will also be provided for the temporary property requirements.	Local Residents City of Toronto
14) Keele Station 15) Chaplin Station	Impacts to property owned by Emergency Medical Services at Keele Station and Chaplin Station	Through consultation with Emergency Medical Services, the station entrances at Keele Station and Chaplin Station have been shifted to avoid impact to future development plans by EMS at these locations.	City of Toronto - Emergency Medical Services

Г <u></u>			
Project Element	Comment/Issue	How Comment Was Addressed	Stakeholders
 16) Bayview Station 17) Dufferin Station 18) Chaplin Station 19) Allen Station 20) Eglinton Park 	Impacts to property owned by Parks, Forestry and Recreation due to proposed station entrances/vent shafts at Bayview, Dufferin, Chaplin, Allen Stations and the emergency exit building at Eglinton Park.	Consultation has commenced with City of Toronto Parks, Forestry and Recreation regarding placement of station entrances and/or vent shafts at these park/parkette locations. Station entrances, vent shafts and/or EEBs at these park/parkette locations.	City of Toronto – Parks, Forestry and Recreation
21) Station Spacing	Provide a station between Dufferin and Caledonia	Caledonia Station was shifted westward from Caledonia Road to the location where Eglinton Avenue passes over the GO Transit Barrie-Bradford line. This shift was undertaken to protect for a future connection with GO Transit and to provide better access to the West Side Mall.	City of Toronto – City Planning GO Transit
22) Station Location	Provide a station at Laird and at Brentcliffe	The station spacing between Laird and Brentcliffe is too close to meet the TTC desired goal of approximately 850 metres between stations for the underground section.	General Public
23) Station Spacing	Continue to provide bus service on Eglinton Avenue because of long distances between stations to help seniors access transit service	In the underground section, stations will be located about 850 metres apart, typically at intersections where existing north-south bus routes or the Yonge and Spadina Subway lines cross Eglinton Avenue. This station spacing is similar to the central sections of the existing Bloor-Danforth and Yonge-University subway lines where passengers accept a longer walk to reach the frequent, reliable service and weather-protected waiting area provided by the underground operation.	General Public TTC Advisory Committee on Accessible Transit
		While the distance between underground stations is longer than the distance between surface stops, the resulting longer walk is an acceptable compromise between access, increased reliability, and cost.	
		Parallel bus service is not proposed at this time.	
24) Swift/Credit Union Stop	Provide a stop at the Swift/Credit Union intersection.	A stop was initially proposed but due to cost and property impact considerations, the stop was dropped from further consideration. The removal of the stop was presented at the third round of Open Houses in November and December. A subsequent meeting was held at the Latvian Centre on January 14, 2010 to further review the issues of placing a stop at this location.	General Public
25) Technology	Build a subway instead of LRT – subways have greater capacity	The design of a transit service is based on the number of people it is expected to carry per hour in a single direction at the 'peak point', the busiest spot on the line. City planning forecasts for the Eglinton Crosstown corridor into the foreseeable future show a peak point demand in the order of 5,000 to 5,400 people per hour. This demand can easily be accommodated by LRT, particularly given that the new light rail vehicles being designed for the TTC will be about twice the size of a standard Toronto streetcar, and can be easily 'coupled' to operate as two-car or three-car trains, if single vehicle operation is too frequent to avoid vehicle bunching. A peak point demand of 5,000 to 5,400 per hour is well below the 10,000 passengers per hour generally required to justify the much higher cost of a subway.	General Public
26) Traffic	Re-routing of Left Turns at nine intersections will impact traffic travel times	In order to provide for optimum LRT performance on the surface sections, left turns will be re-routed to U-turns at nine intersections (Martin Grove, Kipling, Islington, Royal York, Scarlett, Jane, Victoria Park, Warden and Birchmount). The re-routing of traffic to U-turns will not have a significant impact on traffic travel times.	General Public City of Toronto – Transportation

Project Element	Comment/Issue	How Comment Was Addressed
27) Traffic	Concern about infiltration of traffic onto local streets	The proposed cross-section for the Eglinton Crosstown LRT will retain the existing number throughout most of the corridor (except for a small section from Weston Road to Black Cr decrease in capacity will result, no traffic infiltration is expected. During construction, a tr will be prepared. It is anticipated that at least 3 lanes of traffic will be available at the und provide as much traffic capacity on Eglinton Avenue as possible.
28) Traffic	Concern about truck routing in the corridor as a result of restricting left turns at nine intersections	A preliminary truck routing plan was prepared during the analysis of traffic operations at t where left turns are recommended to be restricted. Further consultation will be undertake City of Toronto Transportation Services Division regarding truck routes.
29) Underground Stations- General	Number of entrances at each station	Initially, a main entrance, one secondary entrance and an emergency exit were proposed Following consultation and after further review, the typical station entrance was revised to and two secondary entrances.
30) Urban Development	Protect for future development opportunities west of Black Creek Drive	Development opportunities exist on the former Kodak lands and the current No-Frills prop
31) Urban Design/Pedestrian Realm	Provide an aesthetically pleasing urban environment	The standard cross-section for the Eglinton Crosstown LRT includes a boulevard with a to design of station entrances, bus terminals, traction power substations and other facilities consultation with the City of Toronto City Planning Division – Urban Design.
32) Utilities	Utility relocations can require a significant amount of time to design and implement	Consultation with utility companies will be undertaken early in the design phase to accomrequirements of utility relocations.
33) Vegetation	Impacts to vegetation communities	Impacts to vegetation communities will need to be tallied during design. Effort will be un minimize impacts.

Envir	onmental Project Report
	Stakeholders
	Services
	City of Toronto –
	City Planning
ber of general traffic lanes Creek Drive). As no	General Public
traffic management plan	City of Toronto –
nderground section to	Services
	City of Toronto –
	City Planning
t the nine intersections	General Public
aton daning doolgin wan and	City of Toronto –
	Transportation
ed at underground stations.	City of Toronto – City Planning
roperty.	General Public
	City of Toronto –
	I ransportation Services
	City of Toronto –
	City Planning
a tree planting area. The	City of Toronto – City
es will be prepared in	Planning
	General Public
ommodate the timing	Utility companies affected by the design
Indertaken during design to	TRCA
	City of Toronto –

Project Element	Comment/Issue	How Comment Was Addressed	Stakeholders
			Parks, Forestry and Recreation
34) Vertical Alignment	Build the LRT underground	Light rail transit can be constructed more cost-effectively on the surface than in an underground or aerial configuration. The central section of the Eglinton Crosstown LRT is being built in an underground configuration due to the narrow width of Eglinton Avenue from Keele Street to Brentcliffe Road. The width of Eglinton Avenue in the western and eastern sections is sufficient to accommodate the LRT.	General Public

As part of the Transit Project Assessment Process, a draft version of this document was distributed to technical review on January 25, 2010 to solicit comments. **Exhibit 193** summarizes major comments received and the responses to those comments. A complete listing of all comments received and responses thereto appears in **Appendix M**.

Project Element	Stakeholders	Comment/Issue	How Comment Was Addres
1) Air Quality	MOE	Although at this time, the proponent is not aware of the contamination that will be present during the construction of the Eglinton LRT undertaking. However, during construction there could be the possibility of contaminated soils be exposed and thus impacting nearby receptors or pedestrians. If TTC during the design stage is aware of a contamination issue, at that time TTC should consult with the Ministry Central Region Office to discuss the requirements in dealing with contamination issues and ambient monitoring requirements, if applicable.	If contamination is found, TTC Environment.
2) Bridges	City of Toronto – City Planning	Pedestrian sidewalk widths on Bridges - To each of the two main bridges being discussed at Black Creek and the East and West Don River- add a note- design of pedestrian sidewalks across bridges will acknowledge their unique challenges for pedestrians and will provide adequate space with appropriate rails, splash guards and lighting to promote safe comfortable pedestrian crossings.	Bridges that require widening regarding rails, splash guards
3) Design Review	City of Toronto – City Planning	 The location and appearance of substations and emergency exit buildings need to be located with the guidance of City planning and City urban designers, the building appearance should fit within its context and landscaping should be provided. The proposed main entrances and secondary entrances should be integrated within developments when ever possible rather than being free standing elements. The proposed Fire Ventilation Shafts and the Traction Power Sub Stations should ideally be integrated within existing or new buildings where possible. They should not be free standing elements which sterilize potential development parcels. When and where possible TTC must work with Community Planning and Urban Design to fully integrate TTC facilities with proposed development. 	TTC will consult with City Plar and facilities associated with t
4) Natural Heritage	City of Toronto – Urban	• The second paragraph mentioning the protection of natural areas in the OP should also mention the Ravine & Natural Feature Protection bylaw as the	The text has been revised to r

Exhibit 193: Summary of Comments and Responses to Draft Environmental Project Report

Toronto Transit Commission/City of Toronto EGLINTON CROSSTOWN LIGHT RAIL TRANSIT TRANSIT PROJECT ASSESSMENT Environmental Project Report

sed

C will discuss the requirements with Minstry of the

will be widened to accommodate sidewalks. Details and lighting will be addressed in design.

nning during design regarding the design of features the LRT.

mention the Ravine and Natural Feature Protection

Project Element	Stakeholders	Comment/Issue	How Comment Was Address
	Forestry	means of providing that protection, similar to that provided in Section 5.4 in the Natural Heritage Assessment Report	bylaw.
		 More clarification is needed regarding removal/disturbance to edge features and diminishment of area. Also to say that vegetation loss is not considered as significant is misleading and erroneous. 	Section 4.2.4.1 was revised to natural areas in part protected bylaw that is defined and adm
		 Should add the following regarding tree permits: Trees are protected against injury or removal in the City of Toronto by a number of bylaws. In areas of the City protected by the Ravine & Natural Feature Protection bylaw, all trees are protected and grades are protected against alteration. Outside of this protected area, trees greater than 30 cm dbh on private property are protected by the Private Tree bylaw. All trees on city owned land, including streets and parks, are protected. Urban Forestry has delegated authority to issue permits. Completed applications along with supporting information, must be made to Urban Forestry. The issuance of permits may be conditional, for example, on the applicant providing for compensatory planting, to UF standards. 	Forestry. Proposed removal or reviewed and subject to appro
5) Noise	MOE	 The noise and vibration protocols in the noise report should be revised for clarity to state that the upper limit for vibration levels is 0.1 mm/s rms. The LRT system is being assessed based on the use of 2-car trains. It is acknowledged that in the future 3-car trains will be provided. Therefore, the noise assessment should account for 3-car trains. 	The Noise and Vibration Asse upper limit for vibration levels Section 4.1.3 of the Noise and include 3-car trains.
6) Parks	City of Toronto - Park	 Tunnel section drawings do not include plan for Emergency Exit Building #3 which is proposed for Eglinton Park. Include the plan for EEB in Eglinton Park in final EPR. The Interaction Matrix should include a 'strong' impact for the interaction between Stations/Park and Open Space. Station entrances are proposed for St. Hilda's Parkette and Howard Talbot Park. The Interaction Matrix does not identify impacts to Parks and Open Spaces from Western Launch Site in Keelesdale Park. Table should identify all impacts from the Launch Site, including a 'strong' impact for the interaction between Tunnelling/Parks and Open Space, Material Import and Stockpilling/Park and Open Space. Private property acquisition should continue to be investigated to lessen impact to parkland and compensate for loss of public parkland. Parks, Forestry & Recreation have identified that the Western Launch Site will result in the following impacts: loss of the sports field during construction; displacement of recreational permit holders; loss of revenue generated from permitting; tree and vegetation disturbance; and potential noise, dust and traffic impacts to the rest of the park. TTC has committed to re-instating the soccer pitch after construction. In addition, TTC will be asked to satisfactorily address these impacts as an agreement to occupy the site is developed. TTC will 	The tunnel sections drawings Building #3. The interaction m to property acquisition, in cond of public property before consi discussions with Parks, Fores Keelesdale Park as the West
		continue discussions with PF&R to determine agreements, compensation, mitigation and restoration plans for use of Keelesdale Park as Western Launch Site.	
() Public Art	City of Toronto – City	Public Art commitment must be acknowledged in the EPK. The public art plan	A commitment to consult with

sed

o include the following paragraph: "Protection of d by the Ravine and Natural Feature Protection ninistered through the City of Toronto's Urban of trees and features within protected areas will be oval by City of Toronto's Urban Forestry

essment Report has been revised to state that the is 0.1 mm/s rms.

Vibration Assessment Report has been revised to

a now include the area around Emergency Exit matrix has been revised accordingly. TTC's approach accert with City Planning, is to investigate acquisition sidering private property. TTC will continue stry and Recreation regarding the temporary use of Launch Site.

City Planning concering public art has been added

Project Element	Stakeholders	Comment/Issue	How Comment Was Addres
	Planning	must be planned during the design process - not after the fact.	to Chapter 6.
8) Subway Station Design	City of Toronto – Police Services	 As is the current practice with any new subway station designs, police input into the design of any underground stations would be recommended. The design of the area surrounding the Eglinton intersections may also need further review, as it may present a number of traffic-related access problems both for the public and the police. As with new development, we recommend the application of Crime Prevention Through Environmental Design (CPTED). The Toronto Police Service is regularly involved in CPTED, which embodies the concept that the design and effective use of the built environment can lead to a reduction in the opportunity for crime through strategies of natural surveillance, natural access control, and territorial reinforcement. 	As indicated in Chapter 6, TT providers during design.
9) Stray Current	City of Toronto – Parks, Forestry and Recreation; Water	Is there an influence of stray current from substations?	TCG needs to address – the or to this comment.
10) Surface Water	Environment Canada	Interaction between concrete forming and surface water should be added, and given a "strong" level of interaction.	The Interaction Matrix has be
11) Surace Water	MOE	 Throughout the body of this document, the author has indicated that impacts of the proposed LRT development on the natural environment will be minimal however, Exhibit 155: Interaction Matrix indicates that the "Footprint, Construction and Operations and Maintenance Impacts" will be "strong" regarding the surface water elements. Please clarify this variation, additionally, "dewatering and the tunnel construction" should also be graded as having some potential impacts on surface water. As noted, dewatering at rates higher than 50,000 L/day will require a Permit To Take Water (PTTW) issued by the Ministry of the Environment (MOE). Included in the PTTW applications, the MOE requires a discussion of potential impacts to the natural environment, any risks posed to nearby structures due to subsidence resulting from construction dewatering, the potential for the movement of contaminated groundwater due to construction dewatering, and the potential impacts on surrounding waterbody features. PTTW applications should also detail the planned discharge method for the water taking and discuss how the discharged water will meet the quality criteria for the chosen discharge method. Due to the scale and complexity of the ECLRT project, the TTC is encouraged to initiate a pre-consultation process with the MOE regarding the required PTTWs for ECLRT construction dewatering. 	TCG for first bullet. The comr Water has been revised to inc The commitment in Chapter 6 revised to include pre-consult
12) Traffic Management During Construction	City of Toronto – City Planning; Transportation Services	A traffic management plan is needed during construction.	Chapter 6, Commitments to F traffic, parking, transit, cycling included in construction contra
13) Tree Protection	City of Toronto – Urban	Road improvements activity under footprint impacts would strongly impact City streetscape trees and possibly private trees, with any significant changes in the	Streetscape trees and private on the street scape trees and private on the street scape trees and private on the street scape trees and private s

sed

C has committed to consult with emergency service

comment tracking table is not complete with respect

en changed to reflect a strong level of interaction.

mitment in Chapter 6 regarding the Permit to Take clude pre-consultation where appropriate.

6 regarding the Permit to Take Water has been tation where appropriate.

Future Work, includes a commitment to develop g and pedestrian management strategies to be act documents.

te trees are covered under the Populations/Species already marked.

Project Element	Stakeholders	Comment/Issue	How Comment Was Addres
	Forestry	 current curb locations, within the Eglinton Avenue E and W City road allowances. Currently, this box is not 'S' marked in the Interaction Matrix. A significant number of properties in Exhibit 157 'List of Property Acquisitions' indicate road widening as the reason for Property Impacts. This is an indicator of significant curb realignments involved in this project. Others with significant negative tree impacts are: Launch Shaft and Work zone; Station, Secondary and Alternate entrances; Fire Vents; Emergency Exit Buildings, and Right turn lanes. The bulk of the existing City trees along Eglinton Avenue West and East will likely require removal to facilitate either the surface road reconstruction and curb alignments, or the underground station construction, including existing utility relocation. Trees On City Streets (TCS) by-law allows for such City streetscape tree removal, if it is in the interest of the public good. However, this is generally quite a contentious issue. Councillor consultation is recommended, if the project has not yet been approved by Council. This pre-Council approval scenario would also include the PDIM/Forestry Directors' sign-off with PFR General Manager notification requirement for park tree removal approval, on a park by park basis. A complete permit application, under the PTP by-law, will be required for any applicable private trees, to be injured or destroyed by proposed work well within their respective tree protection zones, as all City 	 The interaction of Population impacts is now marked as "% marked as "M". Other intera TTC will apply for permits as already received City Counc
		agencies, boards, commissions, and divisions are subject to the Private Tree Protection (PTP) by-law.	
14) Truck Routing	City of Toronto – City Planning; Transportation Services	Address truck routing concerns relative to relocated left turns at U-turn locations	Chapter 6, Commitments to F truck routings prior to the com
15) U-Turns	City of Toronto – City Planning; Transportation Services	 Allow pedestrian crossings at U-turn locations Possibly realign Sinnot to align with Thermos at U-turn location 	The U-turns were developed were to keep the traffic cycle length operations and traffic. Relocations
16) U-turns	City of Toronto – Police Services	Concerns regarding redirection of left turning vehicles resulting in heavy traffic. Pedestrian and motorists should be notified of the changes and the proper approach to the new rules. Signage should be clear, as people may not follow the left turn restrictions due to inconvenience.	As part of the design process, U-turn location that will replac
17) Utilities	City of Toronto – Water	 The impacts to the utilities should be further assessed, especially regarding impacts on maintenance and future replacement or capital works There is contract underway to install a 750mm water main to replace sections of the 600 mm water main 	A commitment has been adderespect to maintenance, future added regarding the 750 mm
18) Wynford Drive	City of Toronto – City Planning; Transportation Services; Parks, Forestry and Recreation	Commit to work with the City of Toronto regarding the design of the Wynford Stop.	A commitment has been adde

sed

on/Species with road improvements under footprint 'S" and the interaction with building demolition is now actions were marked as "S".

s required. The Eglinton Crosstown LRT Project has cil approval.

uture Work, includes a commitment to further study pletion of design.

without pedestrian crossings or cross traffic in order hs as short as possible to minimize delay to LRT ation of Sinnot and Thermos is not required for the

s, signage will be provided to direct motorists to the ce the existing left turn.

ed to Chapter 6 regarding review of utilities with re replacement or capital works. Text has been water main.

ed to Chapter 6.

CONSULTATION PROCESS 6.

Introduction 6.1

Overview of Consultation Process 6.1.1

An extensive consultation process was undertaken to assist in the planning and impact assessment process for the Eglinton Crosstown LRT project. The consultation process was designed to address the requirements of Ontario Regulation 231/08. Consultation was conducted during the Preliminary Planning Phase prior to the formal declaration of the Transit Project Assessment process on November 13, 2009 through the issuance of the Notice of Commencement.

Consultation was conducted with the government review agencies, technical agencies and local municipalities, the general public, business improvement areas and ratepayers associations, property owners, Aboriginal communities,

This chapter outlines the consultation carried out during the Preliminary Planning phase and during the formal Transit Project Assessment process. A detailed summary of how the issues noted in Schedule 2 of Ontario Regulation 231/08 were addressed is included in Section 6.4

Staff from key technical agencies and municipalities and the TTC participated in a Technical Advisory Committee which met each month throughout the Preliminary Planning and Transit Project Assessment. Other technical agencies and municipal were engaged through issue-specific meetings, working groups and a stakeholder agency workshop. As well, key study recommendations were endorsed by the Toronto Transit Commission and the City of Mississauga Council and approved by Toronto City Council. Detailed information about technical agency and municipal consultation is presented in Section 6.2.1 and Section 6.3.1.

During the Preliminary Planning phase, a letter was sent to the Ministry of the Environment (MOE), Environmental Assessment Approvals Branch (EAAB) Director requesting input for First Nation Consultation. The details of First Nations Consultation are included in Section 6.2.3.

The general public and property owners were able to choose their level of involvement from one or more of the following options:

- Public open houses,
- Project website, and/or
- Contacting the project team directly (24/7 hot line; fax; e-mail; and regular mail).

At the public open houses, information about the project was presented on display panels arranged in sequence in a public meeting place. Project staff was available at the open houses to answer directly any questions or concerns raised by a member of the public.

As discussed in Section 6.2.4 and Section 6.3.4 four formal rounds of public consultation were undertaken. Appendix M includes reports which summarize public comments submitted for each of round of consultation as well as a log of all public comments received during the study.

6.1.2 Notification Protocol

To notify the general public, business improvement associations, ratepayers associations and property owners within the study area of the consultation dates, newspaper advertisements were placed in the Toronto Star and community-base newspapers. Similar notices were issued by Canada Post mail walk to 72.200 households and business in the study area and were also placed on the project website and posted at key TTC subway stations.

Letters were sent to members of the general public, affected land owners and interest groups by regular mail and/ or by email. As the study progressed, the mailing lists were update to include new individuals taking an interest in the LRT project. In addition, all property owners within 30 metres of the project were advised on the Notice of Commencement.

The Notice of Commencement of the Transit Project Assessment was done in accordance with the requirements of Section 7 (4) of the regulation. Specifically:

- Letters were sent to all property owners within 30 metres of the project: ٠
- Email notices were sent to the MOE Regional Director and EAAB Director in addition to the • government ministries, agencies and local municipalities noted later in this chapter;
- All members of the public that participated in previous consultation events received notification; •
- Newspaper ads were placed in the Toronto Star, Metro News, City Centre Mirror, North York • Mirror, East York Mirror, Scarborough Mirror, and Etobicoke Guardian; and
- A notice was posted on the project website. •

Study Organization and Study Stages 6.1.3

As shown in **Exhibit 181**, the study included two distinct phases: the Preliminary Planning phase and the subsequent Transit Project Assessment process.

The focus of rthe Preliminary Planning phase was to discuss planning issues with stakeholders and identify a project. This phase occurred between March 2008 and November 12, 2009. The consultation undertaken as part of Preliminary Planning is outlined in Section 6.2.

The focus of the Transit Project Assessment process, which commenced on November 13, 2009, was to consult on the project, the alternatives considered, the potential impacts and proposed mitigation measures. The consultation undertaken during the Transit Project Assessment is outlined in Section 6.3.



Preliminary Planning 6.2

Technical Agencies and Municipal Staff 6.2.1

Notification and consultation was carried out to encourage the involvement of government, technical agencies and municipal staff during the Preliminary Planning Phase. The following technical review agencies and municipal departments were engaged during Preliminary Planning and the subsequent Transit Project Assessment process.

The following technical review agencies were invited to be involved in the Preliminary Planning Study as well as the formal Transit Project Assessment process.

Federal Government Review Agencies

Canadian Environmental Assessment Agency Canadian Transportation Agency Indian and Northern Affairs Canada Environment Canada **Department of Fisheries and Oceans** Transport Canada

Provincial Government Review Agencies

Ministry of Aboriginal Affairs Ministry of Agriculture, Food and Rural Affairs Ministry of Citizenship and Immigration Ministry of Culture

Ministry of Energy and Infrastructure Ministry of the Environment Ministry of Municipal Affairs and Housing Ministry of Natural Resources Ministry of Transportation **Ontario Realty Corporation**

Technical Agencies

Bell Canada Enbridge Gas Distribution Enbridge Pipelines Hydro One Networks Incorporated **Rogers** Cable Sarnia Products Pipeline Company, Inc. Sun-Canadian Pipeline Company, Inc. Toronto Hydro Trans-Northern Pipeline Canadian National Railway Canadian Pacific Railway Greater Toronto Airports Authority (GTAA) Toronto and Region Conservation Authority (TRCA) VIA Rail GO Transit

Municipal Staff

City of Mississauga City of Toronto - City Planning City of Toronto – Emergency Medical Services City of Toronto – Transportation Services City of Toronto - Parks Forestry and Recreation City of Toronto – Public Health Conseil Scolaire de district Catholique Centre-Sud **Toronto District School Board Toronto Catholic District School Board Toronto Fire Services Toronto Parking Authority Toronto Police Services** Toronto Water

A Technical Advisory Committee (TAC) was established early in the Preliminary Planning phase to facilitate communication between the study team and key stakeholders, including TTC departments, the City of Toronto (co-proponents), GO Transit and Mississauga Transit. The TAC provided advice to the study team and was consulted on key recommendations during Preliminary Planning.

- City of Toronto City Planning Transportation Planning (East, North and West District)
- City of Toronto City Planning Urban Design •
- City of Toronto Transportation Services

- TTC Service Planning
- GO Transit
- Mississauga Transit

In addition to monthly TAC meetings, focussed meetings were held with government and technical review agencies and City of Toronto and City of Mississauga departments in order to communication key study recommendations and to resolve issues. Exhibit 182 lists meetings held with government review and technical agencies and Exhibit 183 lists meetings held with municipal staff during Preliminary Planning.

Key issues raised and the study team's responses and/ or follow-up actions are summarized in Section6.4.

Date	Agency	Purpose
September 4, 2008	GO Transit	Coordinate future plans with GO Transit
October. 30, 2008	MTO	Coordination with Mississauga BRT
December. 1, 2008	TRCA	Initial meeting with TRCA to review western section of Eglinton Crosstown LRT Project
December 16, 2008	TRCA	Initial meeting with TRCA to review eastern section of Eglinton Crosstown LRT Project
January 8, 2009	TRCA	Initial site visit to review the Humber River, Mimico Creek and Black Creek watersheds
January 12, 2009	TRCA	Site visit to review the Don River watersheds
January 22, 2009	MOE	Present Eglinton Crosstown LRT to MOE
February. 2, 2009	GO Transit	Discuss potential opportunities to interface GO Transit services with the Eglinton Crosstown LRT
March 11, 2009	MTO	Coordination with Mississauga BRT
April. 14, 2009	GTAA	Coordinate the alignment of the Eglinton Crosstown LRT with the Airports Authority
April. 17, 2009	GTAA	Coordinate the alignment of the Eglinton Crosstown LRT with the Airports Authority
April. 28, 2009	GTAA	Coordinate the alignment of the Eglinton Crosstown LRT with the Airports Authority
May 5, 2009	TRCA	Meeting to discuss floodplain and property issues at Jane Street
July 16, 2009	GTAA	Coordinate the alignment of the Eglinton Crosstown LRT with the Airports Authority
July 29, 2008	GTAA	Coordinate the alignment of the Eglinton Crosstown LRT with the Airports Authority
July 29, 2009	MOE	Consultation/Coordination with the Project Officer from MOE
August 24, 2009	MTO	Coordination with Mississauga BRT

Discusion Technical Association Marstin

Date	Agency	
August 27, 2009	MOE	Present overview of Eg scopes of work for Air, investigations
September 2, 2008	GTAA	Coordinate the alignme Authority
September. 15, 2009	TRCA	Site visit to review surfa Black Creek and West
September 29, 2009	TRCA	Site visit to review surfa Don River, East Don R
December. 18, 2009	GTAA	Coordinate the alignme Authority

In accordance with TRCA's requirements, a copy of all letters issued by TRCA during Preliminary Planning and the Transit Project Assessment are included in Appendix M.

Exhibit 183: Preliminary Plannin Date **City/ Department** April 17, 2008 City of Mississauga Coord June 10, 2008 City of Toronto - Toronto Propo Water June 18, 2008 City of Mississauga Coord City of Toronto - City September 16, 2008 Don Planning Kick-October 21, 2008 City of Toronto - City Obtai Planning Distri November 5, 2008 City of Toronto - City Don Planning Initial City of Toronto - City December 8, 2008 Work Planning & Transportation Services City of Toronto - City December. 12, 2008 Work Planning & Transportation Services January 20, 2009 City of Toronto - City Traffi Planning & **Transportation Services** January 22, 2009 City of Toronto - Toronto Propo Water January 28, 2009 City of Toronto - City

Toronto Transit Commission/City of Toronto EGLINTON CROSSTOWN LIGHT RAIL TRANSIT TRANSIT PROJECT ASSESSMENT Environmental Project Report

Purpose

linton Crosstown LRT to MOE staff and to review Noise and Vibration, and Water Resources

ent of the Eglinton Crosstown LRT with the Airports

ace water issues at Mimico Creek, Jane Street, **Tunnel Launch Site**

face water issues at East Tunnel Launch Site, West River, Wilson Brooke and Massey Creek

ent of the Eglinton Crosstown LRT with the Airports

g - Municipal Staff Meetings
Purpose
dination with Mississauga BRT
osed water main at Mt. Pleasant Road
dination with Mississauga BRT
Vills LRT/Eglinton Crosstown LRT Special Study off
in information on development plans in the North ct
Mills LRT/Eglinton Crosstown LRT Screening of Alternatives
shop on Traffic Issues – West Surface Section
shop on Traffic Issues – East Surface Section
c Issues – Wynford and Victoria Park
osed water main at Mt. Pleasant Road

Traffic Issues – Martin Grove, Kipling and Jane

Date	City/ Department	Purpose
	Planning & Transportation Services	
February. 2, 2009	City of Toronto - City Planning & Transportation Services	Traffic Issues – Wynford and Victoria Park
February 6, 2009	City of Toronto - Toronto Water	Proposed water main at Mt. Pleasant Road
March 11, 2009	City of Mississauga	Coordination with Mississauga BRT
March 27, 2009	City of Toronto - Transportation Services	Traffic Analysis – U-turn versus standard intersection configuration
March 30, 2009	City of Mississauga	Coordination with Mississauga BRT
Apr. 7, 2009	City of Toronto - City Planning & Transportation Services	Black Creek traffic and Maintenance and Storage (pocket) access analysis
April 8, 2009	City of Toronto - City Planning	Station Entrances
April 21, 2009	City of Toronto - City Planning & Transportation Services	Interface with Jane LRT
April 30, 2009	City of Toronto - City Planning	Station Entrances
May 1, 2009	City of Toronto - Transportation Services	Intersection Concepts – West Surface Section
May 1, 2009	City of Toronto - Transportation Services	Intersection Concepts – East Surface Section
May 1, 2009	City of Toronto - City Planning	Don Mills LRT/Eglinton Crosstown LRT Special Study Final Results
May 7, 2009	City of Toronto - Parks, Forestry & Recreation	Meeting to discuss floodplain and property issues at Jane Street
May 22, 2009	City of Toronto - Police, Fire, EMS	Consultation with issues related to property owned by these services
June 6, 2009	City Planning & Transportation Services	Black Creek traffic and Maintenance and Storage (pocket) access analysis
July 13, 2009	City of Mississauga	Coordination with Mississauga BRT
August 14, 2009	City of Toronto - Transportation Services	Updated traffic analysis
September 3, 2009	City of Toronto - City Planning	Station Entrances
September 9, 2009	City of Toronto - City	Black Creek traffic and Maintenance and Storage

Date	City/ Department	
	Planning & Transportation Services	(pock
September 10, 2009	City of Toronto - Transportation Services	Traffi
October 2, 2009	City of Mississauga	Coord
October 14, 2009	City of Mississauga	Coord
October 20, 2009	City of Mississauga	Coord
October 28, 2009	City of Toronto - Parks, Forestry & Recreation	Meeti where buildi
November. 13, 2009	City of Toronto - Parks, Forestry & Recreation	Discu

6.2.2 Municipalities

In addition to the involvement of municipal staff on technical elements of the study, municipal political representatives in the City of Toronto and the City of Mississauga were provided with project overview presentations at key milestones during Preliminary Planning. The dates of key meetings held are noted in **Exhibit 184.**

Exhibit 184: Preliminary Planning – Municipal Meetings

Date	Purpose
August 7, 2009	City of Toronto Councillor Briefing – First Round of Public Open Houses
June 3 and 4, 2009	City Councillor Briefing – Second Round of Public Open Houses
August 31, 2009	City Councillor Briefing – Third Round of Public Open Houses

6.2.3 Aboriginal Consultation

Ontario Regulation 231/08 requires transit project proponents to request from the Ministry of the Environment's Environmental Assessment and Approvals Branch "for a list of bodies that, in the opinion of the Director, would be able to assist in identifying aboriginal communities that may be interested in the transit project" (Section 7(4)(a). On November 11, 2008, the TTC wrote to the Environmental Assessment and Approvals Branch to request agency contacts that could assist in identifying potentially interested aboriginal communities for the Transit City projects including the Eglinton Crosstown LRT.

The MOE Environmental Assessment and Approvals Branch (Zeljko Romic) wrote the TTC on December 3, 2008 with detailed information regarding agencies to assist in identifying potentially interested communities. The agencies included: Ontario Ministry of Aboriginal Affairs, and Indian and Northern Affairs Canada (INAC): (Specific Claims, Litigation Management and Resolution Branch (LMRB) and Comprehensive Claims).

Toronto Transit Commission/City of Toronto EGLINTON CROSSTOWN LIGHT RAIL TRANSIT TRANSIT PROJECT ASSESSMENT Environmental Project Report

Purpose

ket) access analysis

ic analysis update

dination with Mississauga BRT

dination with Mississauga BRT

dination with Mississauga BRT

ing to discuss property issues on City parklands e station entrances, fire vent shafts, emergency exit ings or traction power substations would be located.

uss the West Launch Shaft site at Keelesdale Park

During the first round of public consultation in the preliminary planning phase, notices were sent to:

- INAC Specific Claims, LMRB and Comprehensive Claims (July 31, 2008),
- Ministry of Aboriginal Affairs (July 31, 2008), and
- Mississaugas of the New Credit First Nation (July 31, 2008).

No comments were received from these organizations during the first round of open houses.

During the second round of consultation in the preliminary planning phase, notices were sent as follows:

- INAC Specific Claims, INAC LMRB, and INAC Comprehensive Claims (June 3, 2009),
- Ontario Ministry of Aboriginal Affairs (June 3, 2009), and
- Mississaugas of the New Credit First Nation (June 3, 2009).
- No comments were received from these organizations during the second round of open houses.

On September 2, 2009, an additional open house was held to specifically discuss the section of the LRT from Martin Grove Road to Pearson International Airport. Notices for this additional open house during preliminary planning were sent to the Mississaugas of the New First Nation (August 21, 2009). No comments were received from the Mississaugas as part of this Open House.

General Public and Property Owners 6.2.4

Involvement of the general public, community associations, ratepayers groups and property owners was an integral component of the study.

The following community associations and ratepayers groups received notification of public consultation events during both Preliminary Planning and the Transit Project Assessment process:

- Avenue Road Eglinton Community Association
- Bayview Blythwood Ratepayers Association
- Canadian Hispanic Congress
- Centennial Community Ratepayers Association
- Clairlea Regent Heights Neighbourhood Association
- Community of Rathburn-Grove Ratepayers
- **Confederation of Resident & Ratepayers Associations**
- Corvette Residents' Association
- Eglinton Way BIA
- Green Hills Residents' Association
- Islington Ratepayers & Residents Association
- Kennedy Road BIA
- Leaside Business Park
- Leaside Property Owners Association

MARCH 2010

- Markland Homes Association •
- Martin Grove Ratepayers' Association
- Maryvale Community Association •
- Midland Park Community Association
- Mount Dennis Community Association
- North Leaside Resident Association
- **Renaissance Tenants Association**
- Santamonica Birchmount Neighbourhood Association
- Silverthorne Ratepayers Association
- St. Andrew-St. Patrick Tenants Association
- The Princess Anne Manor Ratepayers Association
- Upper Village BIA .
- West Deane Homeowners Association
- West Gate Residents Association .
- Wexford BIA .
- Wynford/Concorde Residents Association
- York-Eglinton BIA

Key public consultation dates during preliminary planning were:

- First round of public open houses August 14 to September 22 2009 (6 locations),
- Ward 12 Open House December 9, 2008,
- Second round of public open houses June 15 to July 29, 2009 (6 Locations), •
- TTC Advisory Committee on Accessible Transit July 27, 2009,
- Don Mills Residents Incorporated July 27, 2009, and
- Third round public open house September 2, 2009.

Three rounds of public open house were held at key points during the Preliminary Planning phase. At each open house display panels were presented for public review and representatives TTC, City of Toronto, City of Mississauga (third open house only), and the consultants were available to discuss the study on a oneon-one basis with members of the public.

First Round of Public Open Houses (August 14 to September 22, 2008

The first round consisted of six open houses held between August 14, 2008 and September 22, 2008. The purpose of the first round was to share information about the Eglinton Crosstown LRT project with the community and to gather feedback on preliminary project plans. Each open house presented information on:

The planning context (rationale) for the LRT on Eglinton Avenue; ٠

- Background information about the Eglinton Avenue Corridor (such as consistency with City and • Provincial Plans, existing conditions and a description of LRT technology);
- Proposed surface and underground sections;
- Proposed stop and station locations; and
- Potential construction methods.

The level of public participation for the first round of open houses is summarized in Exhibit 185.

Exhibit 185: First Round of Public Open Houses – Summary of Participation				
	Location	Number of Participants signed-in	Number of Comments Forms Received	
August 14, 2008	Forest Hill Memorial Arena	119	35	
	340 Chaplin Crescent			
August 19, 2008	Leaside Arena	172	45	
	1073 Millwood Road			
August 25, 2008	Humber Valley United Church	209	52	
	76 Anglesey Boulevard			
August 27, 2008	Don Montgomery Community Centre	48	8	
	2467 Eglinton Avenue East			
September 4, 2008	Richview Baptist Church	70	11	
	1548 Kipling Avenue			
September 22, 2008(*)	Centennial Recreation Centre	73	18	
	2694 Eglinton Avenue West			
	Total	691	169	

(*) Joint Open House with the Jane LRT

Ward 12 Open House (December 9, 2008)

In addition, at the request of Councillor Frank DiGiorgio, an informal open house was held on December 9, 2008. The open house included the same presentation materials as the first round of public open houses. A total of twelve members of the public signed in at this event.

Second Round of Public Open Houses (June 15 to July 29, 2009)

The second round of public open houses were held at six locations June 15, 2009 and July 29, 2009. Initially, the open houses were scheduled to conclude by June 25, 2009, but the final open house was rescheduled to July 29, 2009 due to a civic strike. The purpose of the second round was to provide:

- Responses to frequently heard comments at Open House 1;
- Key objectives of the Eglinton Crosstown LRT;
- Typical portal, stop and station plans;
- Details of specific surface stops and underground stations (including proposed station entrance locations):
- Traffic management for surface LRT stops (including rerouted left turns at 10 key intersections); •
- Potential corridors for the LRT between Martin Grove Road and Pearson International Airport; and
- Potential underground construction methods (including twin bore and single bore tunnelling). •

In addition to notification to the general public through the methods described in Section 6.1.2, letters were issued to private property owners to advise of preliminary full and partial property requirements defined to date through the Preliminary Planning process.

The level of participation during the third round of Open Houses is summarized in Exhibit 186.

Date	Location	Number of Participants signed-in	Number of Comment Forms Received
June 15, 2009	William Lea Room 1073 Millwood Road	257	82
June 17, 2009	Eglinton Public School 223 Eglinton Avenue East	160	37
June 18, 2009	Richview Collegiate 1738 Islington Avenue	275	35
June 23, 2009	York Memorial Collegiate 2690 Eglinton Avenue West	99	15
June 24, 2009	Beth Sholom Synagogue 1445 Eglinton Avenue West	168	44
July 29, 2009	Ionview Heights United Church 115 Ionview Road	45	7
	Total	1,004	220

Dons Mills Residents, Inc. (July 27, 2009)

A meeting was held at the request of the Don Mills Residents, Inc. to review the Eglinton Crosstown LRT project in general and the options for Don Mills Station and Wynford Stop. In addition to the general project comments received, feedback was given regarding the assessment of the two Don Mills LRT interface options (including the proposed bus Terminal) and the two options at Wynford Drive.

TTC Advisory Committee on Accessible Transportation (ACAT) (July 27, 2009)

An overview of the materials provided for public review and comment at the second round of public open houses was presented to the ACAT Design Review Sub-committee for information.

Third Round Public Open House (September 2, 2009)

Subsequent to the completion of the second round, a separate open house was held on September 2, 2009 at the Etobicoke Olympium at 590 Rathburn Road. The purpose of this round of consultation was to present the recommended route for the LRT from Martin Grove Road to Pearson International Airport.

The open house presentation materials included:

- The five alternative routes between Martin Grove Road and Pearson International Airport:
- Reasons for selecting Route 1 (via Eglinton Avenue, Commerce Boulevard, Convair Drive and Silver Dart Drive) as the preferred route; and
- Stop concepts for the recommended route.

A total of 139 participants signed in, and 30 comment forms were submitted.

Transit Project Assessment 6.3

Technical Agencies and Municipal Staff 6.3.1

The involvement of the government agencies, technical agencies and municipal staff as listed in Section 6.2.1 continued through the Transit Project Assessment phase.

Stakeholder Agency Workshop (January 8, 2010)

A stakeholder agency workshop was held to present the preferred design and proposed environmental impacts and impacts and to solicit comments from government review and technical agencies in advance of issuance of the draft Environmental Project Report.

Thirty-seven staff representing the government and technical review agencies and municipal departments listed below attended the workshop:

- **Bell Canada**
- Canadian Environmental Assessment Agency
- City of Mississauga
- City of Toronto City Planning (Transportation Planning)
- City of Toronto City Planning (Urban Design)
- MARCH 2010

- City of Toronto Emergency Medical Services •
- City of Toronto Fire Services •
- City of Toronto Parks, Forestry and Recreation •
- City of Toronto Transportation Services
- Enbridge Gas Distribution
- Metrolinx/GO Transit
- Ministry of the Environment •
- Ministry of Transportation
- Rogers Cable
- Toronto and Region Conservation Authority
- Toronto Hydro
- **Toronto Water**

The meeting included a presentation of the preferred design as well as proposed environmental impacts and mitigation measures. Attendees participated in facilitated discussion groups and completed work books which requested comments about the proposed environmental impacts and mitigation measures, commitments to future work (to be included in the Environmental Project Report) and permits and approvals required for implementation of the Eglinton Crosstown LRT. Comments heard at the Stakeholders Workshop are summarized in Exhibit 172 shown later.

As for the Preliminary Planning phase, and as summarized in Exhibit 187 and Exhibit 188, focused meetings were held during the Transit Project Assessment to address key issues.

Exhibit 187: Transit Project Assessment - Meetings with Technical Review Agencies Purpose

Date	Agency	
November 25, 2009	CEAA	Conference the Canadi
January 5, 2010	TRCA	Follow-up t 2009 and to Water Man

Exhibit 188: Transit Project Assessment - Meetings with Municipal Staff

Date	Agency	
November 13, 2009	City of Toronto – Parks, Forestry and Recreation	Meeting to Community
January 21, 2010	City of Toronto – Parks, Forestry and Recreation	Meeting to o Features Pr to review th
February 1, 2010	City of Toronto-	Meeting to

e call to discuss Project Description prepared under an Environmental Assessment Act

to site visits held on Sept. 15, 2009 and Sept. 29, to review TRCA comments on Drainage and Storm agement Report and Structures Report

Issues

coordinate the design of the Keelesdale Centre with the West Launch Site

discuss the requirement of the Ravine and Natural rotection by-law and the Tree Protection by-law and he design of the Wynford stop

review Cultural Hertiage Assessment Report

Date	Agency	Issues
	Heritage Preservation Services	
February 1, 2010	City of Toronto – Parks, Forestry and Recreation	Subsequent meeting to discuss the West Launch Site at Keelesdale Park

As part of the government and technical reviewed agency consultation, technical special reports to key agencies as requested. **Exhibit 189** lists which agencies received the technical specialist reports.

Technical Specialist Report	Circulation Agency
Air Quality	Ministry of the Environment
Stage 1 and Stage 2 Archaeological Assessment Report	Ministry of Culture
	City of Toronto - Heritage Preservation Services
Cultural Heritage Assessment Report	City of Toronto - Heritage Preservation Services
Drainage and Storm Water Management Report	Toronto and Region Conservation Authority
Geotechnical Assessment Report	Toronto and Region Conservation Authority
Hydrogeological Assessment Report	Toronto and Region Conservation Authority
Natural Heritage Assessment Report	City of Toronto – Parks, Forestry and Recreation
	Toronto and Region Conservation Authority
Noise and Vibration Assessment Report	Ministry of the Environment
Traffic	City of Toronto – Transportation Services
	City of Toronto – City Planning
	Ministry of Transportation
	City of Mississauga

6.3.2 Municipalities

There was continued involved of municipal political representatives in the City of Toronto and the City of Mississauga during the Transit Project Assessment Process. The Toronto Transit Commission, Toronto City Council and City of Mississauga Council have endorsed the Transit Project and the filing of the Environmental Project Report. Key municipal consultation dates are noted in Exhibit 190.

Exhibit 190: Transit Project Ass	ess
Date	
November 17, 2009	Т
December 4, 2009	Т
December 2, 2009	N
January 19, 2010	C
February 17, 2010	Т

6.3.3 Aboriginal Consultation

Following clarification received during the Scarborough Malvern LRT project, all Williams Treaty Bands were contacted in addition to the Mississaugas of the New Credit First Nation. The following contacts were made:

- November 12, 2009: a letter and Notice of Commencement was sent to all Williams Treaty Bands and their legal coordinator Ms. Karry Sandy McKenzie asking for written confirmation of any interest they may have in the project. The Williams Treaty Bands include: Alderville, Beausoleil, Chippewas of Georgina Island, Chippewas of Rama, Curve Lake, Hiawatha, Mississaugas of Scugog, Moose Deer Point First Nations.
- November 12, 2009: The Mississaugas of the New Credit were contacted via e-mail (their • preferred method and asked to provide written confirmation of any interest they may have in the project); and
- November 12, 2009: Notices were sent to INAC Specific Claims, INAC LMRB, and INAC ٠ Comprehensive Claims and the Ontario Ministry of Aboriginal Affairs to confirm First Nation contacts.

Chief Sharon Stinson Henry (Chippewas of Rama First Nation) confirmed receipt of the Notice of commencement and letter via e-mail on November 12, 2009 and did not express interest. The Alderville First Nation (Shelley Gray - Consultation Coordinator) confirmed receipt of the Notice of Commencement and letter on January 7th, 2009. The Alderville First Nation expressed no concerns with the project but wishes to be contacted should any environmental or archaeological issues arise. A letter dated October 29th, 2009 from the Beausoleil First Nation acknowledged receipt of the Preliminary Planning notice for the Eglinton LRT.

Follow-up emails asking for confirmation of receipt of the November 12 letter and Notice of Commencement for the Eglinton Crosstown LRT were e-mailed to the Mississaugas of the New Credit and all Williams Treaty First Nations on January 4, 2010.

Follow-up phone calls were made to the Mississaugas of the New Credit First Nation on Feb 22nd and to all Williams Treaty Bands and Ms. Karry Sandy McKenzie, their legal coordinator on February 23 and 24, 2010. On Feb 23rd, the Chippewas of Georgina confirmed receipt of the Notice of Commencement, as did the Curve Lake First Nation. Neither expressed concerns and Curve Lake (Chief Knott) indicated an interest in being notified of any archaeological finds.

Toronto Transit Commission/City of Toronto EGLINTON CROSSTOWN LIGHT RAIL TRANSIT TRANSIT PROJECT ASSESSMENT **Environmental Project Report**

sment - Municipal Consultation

Purpose

oronto Transit Commission

oronto City Council

Aississauga City Council

City of Toronto Pedestrian Committee

Foronto Transit Commission

As of February 25, 2010, no specific interest or concerns have been raised by The Mississaugas of the New Credit and/or by any of the Williams Treaty Bands.

A Notice of Completion will be sent to all First Nations agencies, Williams Treaty Bands and the Mississaugas of the New Credit First Nation with an additional request for each First Nation to express any interest they may have in writing and to confirm receipt. Furthermore, these First Nations will be contacted immediately should any potential First Nation archaeology be discovered.

6.3.4 General Public and Property Owners

Through November and early December, 2009, seven Open Houses were held across the study corridor after the formal Notice of Study Commencement was issued. The following summarizes consultation undertaken. Key public consultation events held during the Transit Project Assessment Process were:

- TTC Advisory Committee on Accessible Transportation Design Review Sub-Committee (November 18, 2009),
- Fourth Round of Public Open Houses (November 23, 2009 to December 10, 2009) (seven locations),
- Mount Dennis Community Meeting December 14, 2009,
- Ward 34 Open House January 14, 2010,
- Airport Corporate Centre Businesses Meeting January 18, 2010,
- Mount Dennis Community Association Meeting hosted by Councillor Lindsay Luby January 28, 2010,
- Latvian Canadian Cultural Centre Board of Directors Meeting Feb 1, 2010,
- Ward 4 Community Meeting February 3 2010,
- Ward 34 Meeting hosted by Councillor Minnan Wong Feb 9, 2010,
- Wards 11 and 12 meeting hosted by Councillors Nunziata and Di Giorgio Feb 11, 2010

During the Transit Project Assessment Process, TTC issued notification to all property owners for whom permanent full or partial property acquisition requirements were identified through the preliminary planning process. Several owners attended the fourth round of public open houses. Additional meetings were arranged with affected property owners upon request.

Fourth Round Public Open Houses (November 23 to December 10, 2009)

The purpose of the public open houses was to provide information covering:

- Response to frequently heard comments at Open Houses 2 and 3;
- Details and locations of specific surface stops and underground stations;
- Recommendations at Jane Street., Black Creek Drive, Wynford Drive. and Don Mills Road.;
- Locations of surface facilities (station entrances, emergency exit buildings, ventilation shafts and traction power substations);
- Recommended traffic management (including rerouted left turns at nine key intersections);

Construction methods; and

•

Potential environmental impacts and recommended mitigation measures.
 Exhibit 191 summarizes the level of participation for the fourth round of public open houses.

Exhibit	191:	Fourth	Round	of Or	ben

Date	Location	Number of Participants signed-in	Number of Comment Forms Received
November 23, 2009	York Memorial Collegiate 2690 Eglinton Avenue West	112	14
November 24, 2009	Etobicoke Olympium 590 Rathburn Road	125	11
November 25, 2009	Northern Secondary School 1929 Bayview Avenue	161	19
November 26, 2009	Richview Collegiate 1738 Islington Avenue	206	34
December 2, 2009	Canadian National Institute for the Blind 851 Mt. Pleasant Road	122	34
December 8, 2009	Don Montgomery Community Centre 2467 Eglinton Avenue East	63	14
December 10, 2009	Beth Sholom Synagogue 1445 Eglinton Avenue West	71	13
	Total	860	139

TTC Advisory Committee on Accessible Transportation (November 18, 2009)

A presentation was made to the ACAT Design Review Subcommittee meeting of November 18, 2009 to provide an overview of the recommendations approved by the Commission at is November 17, 2009. Subcommittee members registered concerns about stop and station spacing and recommended the implementation of parallel bus service.

Mount Dennis Community Meeting (December 14, 2009)

The Mount Dennis Community Association and Councillor Frances Nunziata invited the TTC to a community meeting to discuss the LRT on December 14, 2009. Approximately 75 residents attended. Specific information was presented by project staff related to the rationale for selecting a surface LRT alignment versus an underground option. The councillor invited all residents who had been formally contacted by TTC regarding property impacts. Therefore, project staff explained the property acquisition

Toronto Transit Commission/City of Toronto EGLINTON CROSSTOWN LIGHT RAIL TRANSIT TRANSIT PROJECT ASSESSMENT Environmental Project Report

Houses – Summary of Participation

process in detail to the residents in attendance to ensure they had a clear understanding. Residents and Councillor Nunziata indicated they would follow-up with TTC to confirm a community position regarding preference for above ground versus below-ground LRT in advance of the Commission meeting in order for deputations to be made from local residents directly to the City Councillors overseeing the Commission.

Ward 34 Open House (January 14, 2010)

At the request of Councillor Denzil Minnan-Wong, an additional public open house was held at the Latvian Centre; 144 participants signed in at the event and 30 comment forms were received. The key issue raised by meeting attendees was strong opposition to the recommended removal of the LRT stop at Swift Drive/ Credit Union Road.

Airport Corporate Centre Businesses (January 18, 2010)

In response to a motion raised at the December 2, 2009 Mississauga Council meeting, City of Mississauga staff hosted an information meeting for Airport Corporate Centre (vicinity of Eglinton Avenue and Commerce Drive, south of Highway 401) businesses. The event opened with a presentation by City of Mississauga staff about the Mississauga Bus Rapid Transit project staff. TTC provided an overview presentation of the Transit Project Assessment Process recommendations for the Airport Corporate Centre area. Following the presentations, an informal question and answer session was held. The meeting was attended by 3 persons representing two property owners.

Mount Dennis Community Association Meeting (January 28, 2010)

The Mount Dennis Community Association board invited TTC staff, Councillors Nunziata and Di Giorgio to discuss their concerns with surface LRT, and propose an alternative design option. The Mount Dennis Community Association put forward a hybrid option. The Mount Dennis Community Association proposal was for a half surface LRT on the north side of Eglinton Avenue (from the planned Black Creek portal to the rail corridor bridge) and half underground tunnel (from the west side of the rail corridor bridge under Weston Road and emerging at a portal on the east side of Jane street.

The Mount Dennis Community Association indicated their proposal was based on attempting to minimize additional cost requirements by including a surface section, bypass the need for undercutting the rail corridor supports, minimize traffic disruption and minimizing residential acquisition. Mount Dennis Community Association noted they were particularly interested in ensuring a full surface stop to serve the new recreation centre, a hub connection with the GO line, and new green space created by the tunnel deck from the rail corridor to Weston Road.

Councillors Di Giorgio and Nunziata stated that their preference was not for a hybrid option or surface LRT but only for underground LRT from Keele Street to Jane Street. Councillor Di Giorgio expressed specific concerns with surface LRT and the Mount Dennis Community Association's hybrid proposal in terms of traffic back-ups at Black Creek.

TTC reviewed the Mount Dennis Community Association proposal and indicated significant concerns with LRT operations and traffic flow, and traffic safety for the proposed north side of Eglinton Avenue surface alignment.

Latvian Canadian Cultural Centre Board of Directors Meeting (February 1, 2010)

On February 1, 2010, TTC staff attended a meeting at the Latvian Canadian Cultural Centre with members of the Board of Directors and members of the Latvian Canadian Cultural Centre. This was a follow-up initiative to the Open House held at the Centre on January 14, 2010 with Councillor Minnan-Wong (Ward 34).

Led by the Chair of the Board of Directors of the Latvian Canadian Cultural Centre, several members declared their opposition to the removal of the stop, stating their belief that the decision to remove the stop will have detrimental effects to usership of the Centre, especially by the senior population.

TTC staff explained the rationale for recommending against the stop due to the steep grade of Eglinton Avenue between the Don River Valley and Swift/Credit Union. Specifically the intersection would need to be lowered by 6 metres. As well as additional costs, this treatment would also require the closure or relocation of driveways at 3 Swift Drive, 25 Swift Drive, and 1681 Eglinton Avenue. TTC noted that the nearest LRT stop at Bermondsey is located 350 metres to the east. The maximum walking distance to the Bermondsey Stop is 600 metres, considered an acceptable walking distance to transit.

The ECLRT team explained that although the technical recommendation to remove the stop had already been approved by City Council, groups wishing to provide feedback could submit letters or make deputations directly to the TTC Commission on February 17 when a report on the public consultation results would be considered by the Commission. TTC provided Latvian Canadian Cultural Centre members with some further engineering information in advance of the Commission presentation deadline regarding an option suggested at the meeting to modify the bridge over the East Don River Valley.

Ward 4 Public Meeting (February 3, 2010)

Councillor Lindsay Luby hosted a meeting at Richview Collegiate to discuss rerouted left turns at major intersections in Ward 4. The meeting was attended by 120 members of the public. TTC staff made a presentation about the rerouted left turns and Metrolinx staff provided an overview of the Transit City Program.

Residents largely indicated they would prefer a subway as opposed to surface LRT as they were concerned about traffic and noise.

Ward 34 Meeting (February 9, 2010)

On February 9, 2010 TTC staff attended a meeting eam met in a common room in the condominium at 1700 Eglinton Avenue East. The meeting was arranged by Councillor Minnan-Wong as a follow-up to a January 14, 2010 Open House to discuss the Transit City technical recommendation to eliminate a stop at Swift/Credit Union, in the vicinity of where the meeting was held.

The Councillor's office issued invitations to local stakeholders including the President of the local Parkway Honda dealership at 1681 Eglinton Avenue East, representatives of condominium buildings and property management companies in the area and the Victoria Village Residents Association. A representative from the Latvian Canadian Cultural Centre also attended to represent the Latvian Canadian Cultural Centre.

TTC staff explained the rationale for recommending against the stop due to the steep grade of Eglinton Avenue between the Don River Valley and Swift/Credit Union and distributed a hand-out outlining that the

intersection would need to be lowered by 6 metres. As well as additional costs, this treatment would also require the closure or relocation of driveways at 3 Swift Drive, 25 Swift Drive, and 1681 Eglinton Avenue.

TTC staff advised that the nearest LRT stop at Bermondsey is located 350 metres to the east. The maximum walking distance to the Bermondsey Stop is 600 metres, considered an acceptable walking distance to transit.

Attendees raised questions regarding the retaining walls that would be necessary if a stop was recommended and various engineering accommodations that would have to be adopted with a stop at Swift/Credit Union were explained.

General information about the Transit City Eglinton LRT line were discussed, including the centre median operation and at-grade operation, as well as general construction season impacts.

Ward 11 and Ward 12 Community Meeting (February 11, 2010)

Councillors Nunziata and Di Giorgio hosted a meeting and invited TTC to clarify the challenges of building an underground and an above ground LRT in order for their constituents, in order to confirm a community preference to present directly to the TTC Commissioners. Approximately 150 residents attended and they indicated a strong preference for an underground LRT from Keele Street to Jane Street.

Residents raised specific concerns with surface LRT in regards to traffic and safety - particularly for crossings at Black Creek, Weston Road and Jane Street. Residents expressed access concerns with surface LRT to York Memorial Collegiate, the future recreation centre on the south side of Eglinton, as well as both vehicular and pedestrian access concerns to Keelesdale Park and Eglinton Flats.

TTC indicated that the cost of underground LRT options, including underground stations from Keele Street to Jane Street ranges from \$200-300 million compared to the surface LRT and analysis shows that traffic and pedestrian flow would be accommodated by surface LRT operations.

The audience indicated that extra money should be spent for underground LRT to Jane Street, even if that means re-allocating funds from other Transit City lines. Although outside the scope of this TPA, many residents from the Green Hills Community Association in Councillor Di Giorgio's ward spoke out against a future maintenance and storage (pocket) facility location at Black Creek.

6.4 Summary of Consultation

The input received through the consultation processes undertaken during the Preliminary Planning and Transit Project Assessment phases indicate that there is broad public and stakeholder support for the Eglinton Crosstown LRT. As indicated throughout this chapter (and described in further detail in **Appendix M**) a number of concerns were also raised by the general public and by stakeholders. The key comments raised up to January 25, 2010 and how they were addressed is outlined in **Exhibit 192**.

Exhibit 192: Comment Tracking Table					
Project Element	Comment/Issue	How Comment Was Addressed	Stakeholders		
1) Airport Extension	Preferred routes from Martin Grove to the Airport (some members of the public preferred Renforth/Commerce, others preferred Highway 27)	A special study was undertaken to evaluate 5 proposed routing options between Martin Grove Road and the Airport. The preferred alignment is from Martin Grove Road along Eglinton Avenue to Commerce Boulevard, then Commerce Boulevard across Highway 401 to Convair Drive and Silver Dart Drive.	City of Toronto – Transportation Services City of Toronto - City		
			Planning		
			GOTTANSI		
			MIO		
2) Business Impacts	Concern about pedestrian and vehicular access to businesses during construction	TTC will prepare detailed maintenance of traffic plans during design to address traffic issues during the construction phase. The plan will include pedestrian access to businesses.	Business Improvement Areas		
			City of Toronto – Transportation Services		
3) Connection with BRT	BRT and LRT interchange at Commerce Boulevard needs to be further addressed/examined to provide convenient transfer	The interface between the Mississauga BRT station and the Eglinton Crosstown LRT will be refined during the design phase	Mississauga BRT GO Transit		
4) Construction	Single bore tunnel is preferred over twin bore tunnel	Analysis has concluded that this alternative is less desirable due to:	General Public		
Wethod	for building the underground section	• The lower station platform of the single bore tunnel scheme would have been less desirable for passengers moving between the surface and platform levels	Technical Advisory Committee		
		The technology for the single bore tunnel would have been in excess of 13 metres in diameter and would have been without precedent as the largest bore ever attempted in North America Evicting geological strate would have resulted in higher risk of ground impacts at the surface and to adjacent			
		• Existing geological strata would have resulted in higher lisk of ground impacts at the surface and to adjacent buildings during the boring operations			
5) Cycling	Provide for cycling lanes and bike facilities	The standard cross-section for the Eglinton Crosstown LRT includes bicycle lanes on each side of the road. In the area between Martin Grove Road and Jane Street, no bike lanes will be provided, as the existing bike path will serve as the primary bicycle route.	City of Toronto – Transportation Services		
			General Public		
6) East Mall Stop	A stop is needed at East Mall at the ramp from Highway 427 to Eglinton Avenue West	A detailed traffic assessment was prepared for the intersection of the ramp from Highway 427 to the Eglinton Avenue West/East Mall intersection. A bus queue jump lane is proposed to provide an opportunity for bus riders on the 191 Highway 27 Rocket to transfer to the Eglinton Crosstown LRT.	City of Toronto – Transportation Services		
			МТО		

Project Element	Comment/Issue	How Comment Was Addressed	Stakeholders
7) Network Connectivity	Ensure that the LRT system interfaces with the existing subway and other transit systems such as GO Transit	The Eglinton Crosstown LRT will interface with the Mississauga BRT at the proposed BRT station near Commerce Drive. It will also interface with the Spadina Subway at Eglinton West Station, the Yonge Subway at Eglinton Station, and the Scarborough RT/Danforth Subway at Kennedy Station. Future connections with GO Transit rail lines will be protected at Weston Road (GO Georgetown line) and at Caledonia Station (GO Barrie-Bradford line). The Eglinton Crosstown LRT will also interface with the Jane LRT, the Don Mills LRT and the Scarborough/Malvern LRT lines.	Mississauga Transit GO Transit
8) Noise and Vibration	Noise and Vibration and vibration concerns during construction and during operations phase	A detailed noise and vibration study was carried out in accordance with the established MOE/TTC Protocol. No noise impacts are anticipated from LRT operations. A noise barrier is proposed for the Keele Bus Terminal. Further analysis is recommended to determine any noise impacts and potential mitigation measures from traction power substations and station vent shafts. No vibration impacts are expected from LRT operations in general running track areas. Further analysis will be undertaken during design to assess vibration impacts at special trackwork areas.	Local Residents
9) New Bridge	Length of time required for gaining approval of Bridge over Highway 401	Coordination with Ministry of Transportation is underway to obtain approval for a new LRT structure over Highway 401 in Mississauga	МТО
10) Number of Lanes	Maintain at least four lanes of traffic (2 lanes per direction) – loss of lanes will result in increased traffic congestion	In the west surface section, the current lane configuration is two travel lanes in each direction from Commerce Boulevard to Weston Road. In the east surface section, the existing lane configuration is two general purpose travel lanes in each direction plus one peak period HOV lane in each direction. The standard cross-section for the Eglinton Crosstown LRT consists of two travel lanes in each direction and will not affect traffic.	City of Toronto – Transportation Services City of Toronto – City Planning
11) Parking	Request for commuter parking lots	No commuter parking is included in the Transit City Plan, of which the Eglinton Crosstown LRT is included. The focus of access to the LRT is by pedestrians and by transit users transferring from other modes (bus, subway, RT, other LRT lines)	General Public
12) Allen Station	Impacts to 13 Division Property near Eglinton West Station	Placement of a station entrance at Eglinton West Station on the south side of Eglinton Avenue west will impact land owned by the 13 Division of Toronto Police Services. A concept plan for mitigating the impact to the parking lot was prepared and accepted by Police Services.	City of Toronto –Police Services
13) Property Impacts	Concern about impacts to private property	Compensation will be provided for temporary and permanent property requirements. For permanent property taking, compensation will be provide at fair market value, which is determined at the time of purchase with a property appraisal report forming the basis of negotiations. Compensation will also be provided for the temporary property requirements.	Local Residents City of Toronto
14) Keele Station 15) Chaplin Station	Impacts to property owned by Emergency Medical Services at Keele Station and Chaplin Station	Through consultation with Emergency Medical Services, the station entrances at Keele Station and Chaplin Station have been shifted to avoid impact to future development plans by EMS at these locations.	City of Toronto - Emergency Medical Services

Г <u></u>			
Project Element	Comment/Issue	How Comment Was Addressed	Stakeholders
 16) Bayview Station 17) Dufferin Station 18) Chaplin Station 19) Allen Station 20) Eglinton Park 	Impacts to property owned by Parks, Forestry and Recreation due to proposed station entrances/vent shafts at Bayview, Dufferin, Chaplin, Allen Stations and the emergency exit building at Eglinton Park.	Consultation has commenced with City of Toronto Parks, Forestry and Recreation regarding placement of station entrances and/or vent shafts at these park/parkette locations. Station entrances, vent shafts and/or EEBs at these park/parkette locations.	City of Toronto – Parks, Forestry and Recreation
21) Station Spacing	Provide a station between Dufferin and Caledonia	Caledonia Station was shifted westward from Caledonia Road to the location where Eglinton Avenue passes over the GO Transit Barrie-Bradford line. This shift was undertaken to protect for a future connection with GO Transit and to provide better access to the West Side Mall.	City of Toronto – City Planning GO Transit
22) Station Location	Provide a station at Laird and at Brentcliffe	The station spacing between Laird and Brentcliffe is too close to meet the TTC desired goal of approximately 850 metres between stations for the underground section.	General Public
23) Station Spacing	Continue to provide bus service on Eglinton Avenue because of long distances between stations to help seniors access transit service	In the underground section, stations will be located about 850 metres apart, typically at intersections where existing north-south bus routes or the Yonge and Spadina Subway lines cross Eglinton Avenue. This station spacing is similar to the central sections of the existing Bloor-Danforth and Yonge-University subway lines where passengers accept a longer walk to reach the frequent, reliable service and weather-protected waiting area provided by the underground operation.	General Public TTC Advisory Committee on Accessible Transit
		While the distance between underground stations is longer than the distance between surface stops, the resulting longer walk is an acceptable compromise between access, increased reliability, and cost.	
		Parallel bus service is not proposed at this time.	
24) Swift/Credit Union Stop	Provide a stop at the Swift/Credit Union intersection.	A stop was initially proposed but due to cost and property impact considerations, the stop was dropped from further consideration. The removal of the stop was presented at the third round of Open Houses in November and December. A subsequent meeting was held at the Latvian Centre on January 14, 2010 to further review the issues of placing a stop at this location.	General Public
25) Technology	Build a subway instead of LRT – subways have greater capacity	The design of a transit service is based on the number of people it is expected to carry per hour in a single direction at the 'peak point', the busiest spot on the line. City planning forecasts for the Eglinton Crosstown corridor into the foreseeable future show a peak point demand in the order of 5,000 to 5,400 people per hour. This demand can easily be accommodated by LRT, particularly given that the new light rail vehicles being designed for the TTC will be about twice the size of a standard Toronto streetcar, and can be easily 'coupled' to operate as two-car or three-car trains, if single vehicle operation is too frequent to avoid vehicle bunching. A peak point demand of 5,000 to 5,400 per hour is well below the 10,000 passengers per hour generally required to justify the much higher cost of a subway.	General Public
26) Traffic	Re-routing of Left Turns at nine intersections will impact traffic travel times	In order to provide for optimum LRT performance on the surface sections, left turns will be re-routed to U-turns at nine intersections (Martin Grove, Kipling, Islington, Royal York, Scarlett, Jane, Victoria Park, Warden and Birchmount). The re-routing of traffic to U-turns will not have a significant impact on traffic travel times.	General Public City of Toronto – Transportation

Project Element	Comment/Issue	How Comment Was Addressed
27) Traffic	Concern about infiltration of traffic onto local streets	The proposed cross-section for the Eglinton Crosstown LRT will retain the existing number throughout most of the corridor (except for a small section from Weston Road to Black Crodecrease in capacity will result, no traffic infiltration is expected. During construction, a trawill be prepared. It is anticipated that at least 3 lanes of traffic will be available at the uncoprovide as much traffic capacity on Eglinton Avenue as possible.
28) Traffic	Concern about truck routing in the corridor as a result of restricting left turns at nine intersections	A preliminary truck routing plan was prepared during the analysis of traffic operations at t where left turns are recommended to be restricted. Further consultation will be undertake City of Toronto Transportation Services Division regarding truck routes.
29) Underground Stations- General	Number of entrances at each station	Initially, a main entrance, one secondary entrance and an emergency exit were proposed Following consultation and after further review, the typical station entrance was revised to and two secondary entrances.
30) Urban Development	Protect for future development opportunities west of Black Creek Drive	Development opportunities exist on the former Kodak lands and the current No-Frills prop
31) Urban Design/Pedestrian Realm	Provide an aesthetically pleasing urban environment	The standard cross-section for the Eglinton Crosstown LRT includes a boulevard with a t design of station entrances, bus terminals, traction power substations and other facilities consultation with the City of Toronto City Planning Division – Urban Design.
32) Utilities	Utility relocations can require a significant amount of time to design and implement	Consultation with utility companies will be undertaken early in the design phase to accomrequirements of utility relocations.
33) Vegetation	Impacts to vegetation communities	Impacts to vegetation communities will need to be tallied during design. Effort will be un minimize impacts.

Envir	onmental Project Report		
	Stakeholders		
	Services		
	City of Toronto –		
	City Planning		
ber of general traffic lanes Creek Drive). As no	General Public		
traffic management plan	City of Toronto –		
nderground section to	Services		
	City of Toronto –		
	City Planning		
t the nine intersections	General Public		
	City of Toronto –		
	Transportation Services		
ed at underground stations.	City of Toronto – City		
l to include a main entrance	Planning		
coperty.	General Public		
openy.			
	City of Toronto – Transportation		
	Services		
	City of Toronto –		
	City Planning		
a tree planting area. The	City of Toronto – City		
	General Public		
ommodate the timing	Utility companies affected by the design		
undertaken during design to	TRCA		
	City of Toronto –		
Project Element	Comment/Issue	How Comment Was Addressed	Stakeholders
------------------------	---------------------------	--	--------------------------------
			Parks, Forestry and Recreation
34) Vertical Alignment	Build the LRT underground	Light rail transit can be constructed more cost-effectively on the surface than in an underground or aerial configuration. The central section of the Eglinton Crosstown LRT is being built in an underground configuration due to the narrow width of Eglinton Avenue from Keele Street to Brentcliffe Road. The width of Eglinton Avenue in the western and eastern sections is sufficient to accommodate the LRT.	General Public

As part of the Transit Project Assessment Process, a draft version of this document was distributed to technical review on January 25, 2010 to solicit comments. **Exhibit 193** summarizes major comments received and the responses to those comments. A complete listing of all comments received and responses thereto appears in **Appendix M**.

Project Element	Stakeholders	Comment/Issue	How Comment Was Addres
1) Air Quality	MOE	Although at this time, the proponent is not aware of the contamination that will be present during the construction of the Eglinton LRT undertaking. However, during construction there could be the possibility of contaminated soils be exposed and thus impacting nearby receptors or pedestrians. If TTC during the design stage is aware of a contamination issue, at that time TTC should consult with the Ministry Central Region Office to discuss the requirements in dealing with contamination issues and ambient monitoring requirements, if applicable.	If contamination is found, TTC Environment.
2) Bridges	City of Toronto – City Planning	Pedestrian sidewalk widths on Bridges - To each of the two main bridges being discussed at Black Creek and the East and West Don River- add a note- design of pedestrian sidewalks across bridges will acknowledge their unique challenges for pedestrians and will provide adequate space with appropriate rails, splash guards and lighting to promote safe comfortable pedestrian crossings.	Bridges that require widening regarding rails, splash guards
3) Design Review	City of Toronto – City Planning	 The location and appearance of substations and emergency exit buildings need to be located with the guidance of City planning and City urban designers, the building appearance should fit within its context and landscaping should be provided. The proposed main entrances and secondary entrances should be integrated within developments when ever possible rather than being free standing elements. The proposed Fire Ventilation Shafts and the Traction Power Sub Stations should ideally be integrated within existing or new buildings where possible. They should not be free standing elements which sterilize potential development parcels. When and where possible TTC must work with Community Planning and Urban Design to fully integrate TTC facilities with proposed development. 	TTC will consult with City Plar and facilities associated with t
4) Natural Heritage	City of Toronto – Urban	• The second paragraph mentioning the protection of natural areas in the OP should also mention the Ravine & Natural Feature Protection bylaw as the	The text has been revised to r

Exhibit 193: Summary of Comments and Responses to Draft Environmental Project Report

Toronto Transit Commission/City of Toronto EGLINTON CROSSTOWN LIGHT RAIL TRANSIT TRANSIT PROJECT ASSESSMENT Environmental Project Report

sed

C will discuss the requirements with Minstry of the

will be widened to accommodate sidewalks. Details and lighting will be addressed in design.

nning during design regarding the design of features the LRT.

mention the Ravine and Natural Feature Protection

Project Element	Stakeholders	Comment/Issue	How Comment Was Address
	Forestry	means of providing that protection, similar to that provided in Section 5.4 in the Natural Heritage Assessment Report	bylaw.
		 More clarification is needed regarding removal/disturbance to edge features and diminishment of area. Also to say that vegetation loss is not considered as significant is misleading and erroneous. 	Section 4.2.4.1 was revised to natural areas in part protected bylaw that is defined and adm
		 Should add the following regarding tree permits: Trees are protected against injury or removal in the City of Toronto by a number of bylaws. In areas of the City protected by the Ravine & Natural Feature Protection bylaw, all trees are protected and grades are protected against alteration. Outside of this protected area, trees greater than 30 cm dbh on private property are protected by the Private Tree bylaw. All trees on city owned land, including streets and parks, are protected. Urban Forestry has delegated authority to issue permits. Completed applications along with supporting information, must be made to Urban Forestry. The issuance of permits may be conditional, for example, on the applicant providing for compensatory planting, to UF standards. 	Forestry. Proposed removal or reviewed and subject to appro
5) Noise	MOE	 The noise and vibration protocols in the noise report should be revised for clarity to state that the upper limit for vibration levels is 0.1 mm/s rms. The LRT system is being assessed based on the use of 2-car trains. It is acknowledged that in the future 3-car trains will be provided. Therefore, the noise assessment should account for 3-car trains. 	The Noise and Vibration Asse upper limit for vibration levels Section 4.1.3 of the Noise and include 3-car trains.
6) Parks	City of Toronto - Park	 Tunnel section drawings do not include plan for Emergency Exit Building #3 which is proposed for Eglinton Park. Include the plan for EEB in Eglinton Park in final EPR. The Interaction Matrix should include a 'strong' impact for the interaction between Stations/Park and Open Space. Station entrances are proposed for St. Hilda's Parkette and Howard Talbot Park. The Interaction Matrix does not identify impacts to Parks and Open Spaces from Western Launch Site in Keelesdale Park. Table should identify all impacts from the Launch Site, including a 'strong' impact for the interaction between Tunnelling/Parks and Open Space, Material Import and Stockpilling/Park and Open Space. Private property acquisition should continue to be investigated to lessen impact to parkland and compensate for loss of public parkland. Parks, Forestry & Recreation have identified that the Western Launch Site will result in the following impacts: loss of the sports field during construction; displacement of recreational permit holders; loss of revenue generated from permitting; tree and vegetation disturbance; and potential noise, dust and traffic impacts to the rest of the park. TTC has committed to re-instating the soccer pitch after construction. In addition, TTC will be asked to satisfactorily address these impacts as an agreement to occupy the site is developed. TTC will 	The tunnel sections drawings Building #3. The interaction m to property acquisition, in cond of public property before cons discussions with Parks, Fores Keelesdale Park as the West
		continue discussions with PF&R to determine agreements, compensation, mitigation and restoration plans for use of Keelesdale Park as Western Launch Site.	
7) Public Art	City of Toronto – City	Public Art commitment must be acknowledged in the EPR. The public art plan	A commitment to consult with

sed

o include the following paragraph: "Protection of d by the Ravine and Natural Feature Protection ninistered through the City of Toronto's Urban of trees and features within protected areas will be oval by City of Toronto's Urban Forestry

essment Report has been revised to state that the is 0.1 mm/s rms.

Vibration Assessment Report has been revised to

a now include the area around Emergency Exit matrix has been revised accordingly. TTC's approach accert with City Planning, is to investigate acquisition sidering private property. TTC will continue stry and Recreation regarding the temporary use of Launch Site.

City Planning concering public art has been added

Project Element	Stakeholders	Comment/Issue	How Comment Was Addres
	Planning	must be planned during the design process - not after the fact.	to Chapter 6.
8) Subway Station Design	City of Toronto – Police Services	 As is the current practice with any new subway station designs, police input into the design of any underground stations would be recommended. The design of the area surrounding the Eglinton intersections may also need further review, as it may present a number of traffic-related access problems both for the public and the police. As with new development, we recommend the application of Crime Prevention Through Environmental Design (CPTED). The Toronto Police Service is regularly involved in CPTED, which embodies the concept that the design and effective use of the built environment can lead to a reduction in the opportunity for crime through strategies of natural surveillance, natural access control, and territorial reinforcement. 	As indicated in Chapter 6, TT providers during design.
9) Stray Current	City of Toronto – Parks, Forestry and Recreation; Water	Is there an influence of stray current from substations?	TCG needs to address – the or to this comment.
10) Surface Water	Environment Canada	Interaction between concrete forming and surface water should be added, and given a "strong" level of interaction.	The Interaction Matrix has be
11) Surace Water	MOE	 Throughout the body of this document, the author has indicated that impacts of the proposed LRT development on the natural environment will be minimal however, Exhibit 155: Interaction Matrix indicates that the "Footprint, Construction and Operations and Maintenance Impacts" will be "strong" regarding the surface water elements. Please clarify this variation, additionally, "dewatering and the tunnel construction" should also be graded as having some potential impacts on surface water. As noted, dewatering at rates higher than 50,000 L/day will require a Permit To Take Water (PTTW) issued by the Ministry of the Environment (MOE). Included in the PTTW applications, the MOE requires a discussion of potential impacts to the natural environment, any risks posed to nearby structures due to subsidence resulting from construction dewatering, the potential for the movement of contaminated groundwater due to construction dewatering, and the potential impacts on surrounding waterbody features. PTTW applications should also detail the planned discharge method for the water taking and discuss how the discharged water will meet the quality criteria for the chosen discharge method. Due to the scale and complexity of the ECLRT project, the TTC is encouraged to initiate a pre-consultation process with the MOE regarding the required PTTWs for ECLRT construction dewatering. 	TCG for first bullet. The comr Water has been revised to inc The commitment in Chapter 6 revised to include pre-consult
12) Traffic Management During Construction	City of Toronto – City Planning; Transportation Services	A traffic management plan is needed during construction.	Chapter 6, Commitments to F traffic, parking, transit, cycling included in construction contra
13) Tree Protection	City of Toronto – Urban	Road improvements activity under footprint impacts would strongly impact City streetscape trees and possibly private trees, with any significant changes in the	Streetscape trees and priva environmental factor. "S" is

sed

C has committed to consult with emergency service

comment tracking table is not complete with respect

en changed to reflect a strong level of interaction.

mitment in Chapter 6 regarding the Permit to Take clude pre-consultation where appropriate.

6 regarding the Permit to Take Water has been tation where appropriate.

Future Work, includes a commitment to develop g and pedestrian management strategies to be act documents.

te trees are covered under the Populations/Species already marked.

Project Element	Stakeholders	Comment/Issue	How Comment Was Addres
	Forestry	 current curb locations, within the Eglinton Avenue E and W City road allowances. Currently, this box is not 'S' marked in the Interaction Matrix. A significant number of properties in Exhibit 157 'List of Property Acquisitions' indicate road widening as the reason for Property Impacts. This is an indicator of significant curb realignments involved in this project. Others with significant negative tree impacts are: Launch Shaft and Work zone; Station, Secondary and Alternate entrances; Fire Vents; Emergency Exit Buildings, and Right turn lanes. The bulk of the existing City trees along Eglinton Avenue West and East will likely require removal to facilitate either the surface road reconstruction and curb alignments, or the underground station construction, including existing utility relocation. Trees On City Streets (TCS) by-law allows for such City streetscape tree removal, if it is in the interest of the public good. However, this is generally quite a contentious issue. Councillor consultation is recommended, if the project has not yet been approved by Council. This pre-Council approval scenario would also include the PDIM/Forestry Directors' sign-off with PFR General Manager notification requirement for park tree removal approval, on a park by park basis. A complete permit application, under the PTP by-law, will be required for any applicable private trees, to be injured or destroyed by proposed work well within their respective tree protection zones, as all City 	 The interaction of Population impacts is now marked as "% marked as "M". Other intera TTC will apply for permits as already received City Counc
		agencies, boards, commissions, and divisions are subject to the Private Tree Protection (PTP) by-law.	
14) Truck Routing	City of Toronto – City Planning; Transportation Services	Address truck routing concerns relative to relocated left turns at U-turn locations	Chapter 6, Commitments to F truck routings prior to the com
15) U-Turns	City of Toronto – City Planning; Transportation Services	 Allow pedestrian crossings at U-turn locations Possibly realign Sinnot to align with Thermos at U-turn location 	The U-turns were developed were to keep the traffic cycle length operations and traffic. Relocations
16) U-turns	City of Toronto – Police Services	Concerns regarding redirection of left turning vehicles resulting in heavy traffic. Pedestrian and motorists should be notified of the changes and the proper approach to the new rules. Signage should be clear, as people may not follow the left turn restrictions due to inconvenience.	As part of the design process, U-turn location that will replac
17) Utilities	City of Toronto – Water	 The impacts to the utilities should be further assessed, especially regarding impacts on maintenance and future replacement or capital works There is contract underway to install a 750mm water main to replace sections of the 600 mm water main 	A commitment has been adderespect to maintenance, future added regarding the 750 mm
18) Wynford Drive	City of Toronto – City Planning; Transportation Services; Parks, Forestry and Recreation	Commit to work with the City of Toronto regarding the design of the Wynford Stop.	A commitment has been adde

sed

on/Species with road improvements under footprint 'S" and the interaction with building demolition is now actions were marked as "S".

s required. The Eglinton Crosstown LRT Project has cil approval.

uture Work, includes a commitment to further study pletion of design.

without pedestrian crossings or cross traffic in order hs as short as possible to minimize delay to LRT ation of Sinnot and Thermos is not required for the

s, signage will be provided to direct motorists to the ce the existing left turn.

ed to Chapter 6 regarding review of utilities with re replacement or capital works. Text has been water main.

ed to Chapter 6.

COMMITMENTS TO FUTURE ACTION 7.

During the Transit Project Assessment, the TTC and the City of Toronto have worked closely with key stakeholders to address and resolve all issues or concerns identified. However, not all issues can be addressed within the context of a Transit Project Assessment since the design of the Eglinton Crosstown LRT has been prepared at a conceptual level and further details are required to finalize property requirements, planning initiatives, construction issues and permits/approvals. The following sections present the TTC's and City of Toronto's commitments to future action during preliminary and detail design.

Consultations 7.1

The TTC will consult with the public, property owners and stakeholder agencies (including emergency service providers) during the design of the Eglinton Crosstown LRT alignment, stops/stations, bus terminals and ancillary facilities. Specifically, the TTC will:

- a) Develop a public consultation plan, which will include a strategy for public participation during design and addressing community issues/concerns during construction of design; and
- b) Consult with City of Toronto emergency service providers (including fire, police and emergency medical services) on the design of the surface LRT stops and runningway.

Property Acquisition 7.2

The City of Toronto and the TTC will proceed with property acquisition (including permanent property requirements and temporary construction easements) as follows:

- a) The TTC will conduct a Property Protection Study during the early stages of the design;
- b) The City of Toronto and the TTC will continue property negotiations with the Greater Toronto Airports Authority (Pearson International Airport lands), the Ministry of Transportation, Hydro One Networks Inc., Ontario Realty Corporation, the Toronto and Region Conservation Authority, the City of Mississauga, the Toronto District School and the Toronto Catholic District School Board for publicly-owned property;
- c) For privately-owned properties within the City of Toronto, the City of Toronto will acquire property by negotiation or expropriation, as required; and
- d) For privately-owned properties located within the City of Mississauga (west of Renforth Drive), the City of Toronto will secure the required property interests by negotiation or expropriation as required and will coordinate the property acquistion activities with the City of Mississauga.

Planning and Design Initiatives 7.3

The TTC, City of Toronto and the City of Mississauga will undertake the following planning and design initiatives:

a) The TTC will work with the City of Toronto to ensure that selected locations for station entrances, vent shafts, traction power substations (and Emergency Exit Buildings) meet established urban design and community planning policies and guidelines, limit impact, and provide opportunities for enhancements of the sites and pedestrian access;

- b) The TTC will work with the City of Toronto and the City of Mississauga to ensure that short- and longterm cycling amenities are incorporated into the Eglinton Crosstown LRT facility designs, in accordance with prevailing City policies and design standards:
- c) The TTC and the City will "conduct an early planning review of the Eglinton/Oakwood station node, where the Toronto Parking Authority is currently exploring a joint venture development" (refer to Section 1.8);
- d) The TTC wil incorporate City of Toronto and City of Mississauga urban design criteria into the design of Eglinton Crosstown LRT facilities. Specifically, the TTC and the City of Toronto will undertake an Urban Design Study to identify characteristics of the existing and planned context along the corridor:
- e) The TTC will work with the City of Toronto and the City of Mississauga to ensure that the pedestrian environment at surface stops and underground stations meets established urban design and community planning policies and guidelines;
- f) The City of Toronto and the TTC will work with the Greater Toronto Airports Authority (GTAA) to select a preferred alignment and stop(s) at Pearson International Airport as part of a special study;
- and Extension Project, to confirm the alignment of the Eglinton Crosstown LRT from the intersection of Kennedy Road into Kennedy Station;
- h) The TTC will work with Metrolinx to ensure that appropriate interface opportunities with GO Transit rail lines are protected for in the vicinity of Black Creek Drive/Weston Road, Caledonia Road and Leslie Street:
- The TTC and the City of Toronto will conduct further traffic analyses for nine key intersections where i) left turn prohbitions are to be implemented (Martin Grove Road, Kipling Avenue, Islington Avenue, Royal York Road, Scarlett Road, Jane Street, Victoria Park Avenue, Pharmacy Avenue and Birchmount Road) to support fast and reliable LRT service and to encourage transit-oriented development in the Eglinton Avenue corridor;
- The TTC will implement public art in accordance with prevailing TTC Corporate Policy; and i)
- The City of Mississauga will amend its Official Plan to include a rapid transit corridor from Eglinton Avenue West and Commerce Boulevard to Pearson International Airport via Commerce Boulevard, Convair Drive and Silver Dart Drive.

74 Construction Issues

The TTC will conduct further research and analysis for the construction of the Eglinton Crosstown LRT, including, but not limited to the following activities:

- a) Prepare a monitoring plan in accordance with subsection 9.2.8 of Ontario Regulation 231/08 to verify the effectiveness of mitigation measures;
- b) b) Include noise, vibration and air quality monitoring and mitigation measures and construction site maintenance/upkeep requirements in construction contract documents;
- c) Develop traffic, parking, transit, cycling and pedestrian management strategies to be included in construction contract documents;
- d) Analyse cut and cover construction sites further with the objective to minimize impacts including: reducing width of station box construction by refinement of station platform width and tunnel diameter: alternate methods of excavation support for cut and cover locations; use of mining methods at critical locations; and development of comprehensive pedestrian and traffic management plans;
- e) Develop utility, pipeline and municipal servicing relocation plans with service providers (including but

Toronto Transit Commission/City of Toronto EGLINTON CROSSTOWN LIGHT RAIL TRANSIT TRANSIT PROJECT ASSESSMENT **Environmental Project Report**

The TTC will complete a separate Transit Project Assessment, under the Scarborough RT Conversion

not limited to Bell Canada, Enbridge Gas Distribution, Trans-Northern Pipelines, Rogers Cable, Sun-Canadian Pipelines, Toronto Hydro, Toronto Water, Enersource and the Region of Peel:

- f) Develop emergency response plans with emergency service providers to maintain fire, police and emergency medical services during construction;
- g) Prepare and implement arborist reports, tree protection plans, edge management and streetscape plans;
- h) In consultation with TRCA, City of Toronto and City of Mississauga, determine areas where compensation for vegetation loss will be required; determine quantity and type of species to be used; and, identify sites where restoration efforts would be maximized;
- Undertake Designated Substances Surveys for any buildings or structures which require demolition and to reflect the findings in construction contract documents;
- Develop procedures for disposal of excavated materials, including excess soils, in accordance with Ministry of the Environment requirements;
- k) Prepare and implement a Soil and Groundwater Management Strategy, including water treatment methods, which results in discharge water quality complying with prevailing TRCA and City of Toronto water guidelines and requirements; and contaminated soils management, in accordance with environmental legislation, regulations and guidelines;
- Prepare an erosion and sedimentation control plan, which complies with prevailing TRCA, City of Toronto and City of Mississauga water guidelines and requirements;
- m) Undertake buildings, structures, and railway protection and monitoring;
- n) Prepare Cultural Heritage Evaluation Reports and/or undertake Heritage Impact Assessments at select sites to address City of Toronto Heritage Preservation Services and City of Mississauga Local Municipal Heritage Committee requirements. In the City of Toronto, cultural heritage resources of "heritage interest" but not on the Municipal Register, will be screened to assess local significance and whter to proceed through to the Heritage Impact Assessment process.;
- o) Undertake stray current protection (if applicable) and monitoring for pipelines and other utilities;
- p) Manage brownfield sites in accordance with Ontario Regulation 153/04 and Ontario Regulation 511/09 once it comes into force:
- q) Conduct a Phase 1 and 2 Environmental Site Assessment for any areas of existing contamination prior to property acquisition for the Eglinton Crosstown LRT and consult with MOE as appropriate;
- Conduct a Stage 2 archaeological assessment for properties with archaeological potential that could r) not be assessed during the Transit Project Assessment; and
- For lands under TRCA ownership, conduct archaeological investigations in accordance with TRCA and s) Ministry of Culture requirements.

Permits and Approvals 7.5

The TTC will secure necessary permits and approvals for the implementation of the Eglinton Crosstown LRT, including, but not limited to:

- a) Planning approvals (including Site Plan Approval) for all above-grade structures and facilities (through the City of Toronto or the City of Mississauga);
- b) Park access permits (through the City of Toronto) for access to parks for construction and staging activities;
- c) Building permits for the stations, emergency exit buildings and traction power substations (through the City of Toronto or the City of Mississauga);
- d) Navigable Waters Protection Act approval (through Transport Canada) at the Humber River, West Don River and East Don River:
- e) Permit(s) to Take Water (from the Ministry of the Environment) (for locations where dewatering exceeds 50,000 litres per day);
- Ontario Regulation 166/06 (Regulation of Development, Interference with Wetlands and Alterations to f) Shorelines and Watercourses) permits (through TRCA) for work within regulated areas including Mimico Creek, Silver Creek, Lower Main Humber River, Black Creek, West Don River, East Don River, Wilson Brook and Massey Creek:
- g) Stormwater management, in accordance with City of Toronto, City of Mississauga, TRCA and MOE requirements:
- h) Sewer discharge approvals, in accordance with Region of Peel, City of Mississauga, City of Toronto and TRCA requirements:
- i) Railway Crossing Agreements at the Weston Subdivision, Mactier Subdivision, Newmarket Subdivision, Belleville Subdivision and Bala Subdivision (through CN Rail, CP Rail or Metrolinx);
- i) Pipeline Crossing Agreements, as required;
- k) Permits and/or approvals for a new bridge crossing Highway 401 and modifications to the Highway 401/427 interchange and the Highway 427 ramps (through the Ministry of Transportation Corridor Management Office);
- I) Certificate of Approval for Air Quality in accordance with the Environmental Protection Act (through MOE):
- m) Permits for construction within the existing road allowances (through the City of Toronto and City of Mississauga); and
- n) Highway Alteration By-law approval for alterations to Eglinton Avenue (through the City of Toronto).
- o) Permits and approvals for tree protection and removal/injury (through TRCA, the City of Mississauga and the City of Toronto as applicable);
- p) Assure that applicable Ontario Energy Board approvals are obtained for utility relocations; and
- q) Comply with City of Toronto Ravine and Natural Feature Protection By-law, as applicable.
- Noise and Vibration Protocols 7.6

The TTC will conduct additional noise and vibration studies as required, in accordance with existing MOE/TTC protocols.

Toronto Transit Commission/City of Toronto EGLINTON CROSSTOWN LIGHT RAIL TRANSIT TRANSIT PROJECT ASSESSMENT **Environmental Project Report**

Canadian Environmental Assessment Act Determination 7.7

TTC submitted a CEAA Project Description to the Canadian Environmental Assessment Agency (CEA Agency). The CEA Agency has circulated the Project Description to relevant federal agencies to determine if there is a need for an environmental assessment and which federal agencies may have a responsibility or interest. Most of the federal agencies have not identified a trigger; however, Transport Canada, Department of Fisheries and Oceans and Canadian Transportation Agency may still identify a trigger under the Navigable Waters Protection Act, Fisheries Act or Canada Transportation Act, once project design has advanced. If required, TTC will conduct an environmental screening to secure a determination under the Canadian Environmental Assessment Act.

Municipal Approvals 7.8

Toronto City Council 7.8.1

At its meeting of November 30, 2009, Toronto City Council approved a report from the Toronto City Manager which included the following recommendations:

In addition to amendments to Section 7.3, City Council approved the following motions:

- a) "Local Councillor(s) be consulted during the prepartation of property protection sutdies, and as part of the property acquisition process for termporay construction easements.
- b) No specific discussion on the deferral of the construction of "any stops" will occur with Metrolinx without first consulting the local Councillor(s) well in advance of that consideration.
- c) The deferral of the construction of any stops shall not occur without the TTC seeking approval of City Council.
- d) City Council request the TTC to have the Eglinton Crosstown LRT connection from Martin Grove Road to Pearson International Airport and the Etobicoke-Finch West LRT connection from Humber College to Pearson International Ariport evaluated together as the Transit City Light Rail Network, and that evaluations of options include maintenance and operating costs from a network perspective as evaluation criteria.
- e) City Council requests the TTC to consider full property acquisitions for use as secondary station accesses, not soley for fire vents, where practical.
- f) The City Manager and TTC staff report back on a truck operations plan including appropriate highway signage, in conjunction with the design for the Eglinton LRT.
- g) The TTC be requested to provide detailed analysis on truck movements prior to completion of the final design.
- h) City Council requests the TTTC to expedite the implementation of the Eglinton Crosstown LRT and that the City Manager be requested to report to the TTC on any impediments or specific issues that need to be resolved in order to eliminate delay."

These City Council-approved motions are included in this chapter of the Environmental Project Report as a commitment to future action.

City of Mississauga General Committee 7.8.2

At its meeting of December 3, 2009, the City of Mississauga General Committee (a Committee of City of Mississauga Council) endorsed the City of Toronto and the Toronto Transit Commission' (TTC) Eglinton Crosstown Light Rail Transit (LRT) Project from Kennedy Station to Pearson Airport, specifically the alignment in the City of Mississauga on Eglinton Avenue and Commerce Boulevard with a new crossing of Highway 401 as part of LRT connection to Toronto Pearson International Airport." In addition, the Committee approved the recommendations that staff:

- a) "report back to General Committee at the appropriate time on the official plan amendment needed to support the Airport transit connection.
- b) That staff be directed to facilitate information meetings with the landowners and the business community."

These Committee-approved recommendations are included in this chapter of the Environmental Project Report as a commitment to future action.

Addendum Process 7.9

The TTC will prepare an addendum if significant changes to the project occur after the Notice of Completion is issued in accordance with Section 15 of the Transit Projects Regulation, including:

- Preparation of an addendum to the Environmental Project Report; •
- Preparation of a Notice of Addendum to the Environmental Project Report; and,
- Distribution of the Notice of Addendum to relevant stakeholders and the Ministry of the • Environment.

Upon resolution of the alignment on the Airport Lands with the GTAA and Metrolinx, the TTC and the City of Toronto will proceed with amending the Environmental Project Report under the Provincial process if required.

Toronto Transit Commission/City of Toronto EGLINTON CROSSTOWN LIGHT RAIL TRANSIT TRANSIT PROJECT ASSESSMENT **Environmental Project Report**

GLOSSARY OF TERMS

Airport Link	Light Rail Transit connection between the Pearson International Airport and the area at Eglinton Avenue/Martin Grove Road.	Emergency Exit Building	Building I from the emergen stations t
Avenues	Important corridors along major streets where redevelopment and growth is encouraged.		route who establish
Alignment	Refers to the specific horizontal and vertical location of the Light Rail Transit tracks.	Environment	Environm Assessm
Ambient/Background Sound Level	The all-encompassing noise associated with a given		a) air, Iar
	environment and comprises as composite of sounds from many sources, other than the source of interest, near and far.		b) plant a
	In the context of this document, the ambient or existing noise level is the noise level, which exists at a receptor as a result		c) the so the life of
	of existing traffic conditions without the addition of noise generated by the proposed undertaking or the new source of noise.		d) any bu made by
At-grade	Roadway and/or LRT rail corridor at the same elevation as the surrounding land.		e) any sc radiation or
Below-grade	Roadway and/or LRT rail corridor beneath the elevation of the surrounding land.		f) any pa interrelat
Bus Bays	Off-street areas for loading and unloading passengers within the bus circulation potion of a transit station.	Environmental Impacts	Ontario. Positive o
Bus Terminal	Off-street and on-street structures for loading and unloading bus passengers.		construct Subway
Centre Stop	LRT surface stop located on either side of the intersection.	Environmental Project Report	A report of
Concourse Level	The level of the LTR station between the street level and the platform level.		associate for a tran
Crossover Track	Consists of two tracks of opposite orientation superimposed upon each other. Crossovers allow trains to transfer from	Erosion	A slow w and wate
Cut and Cover	Construction method for shallow tunnels consisting of	Evaluation Criteria	Principle
	excavation from the surface to the bottom of the tunnel. A		be based
	trench is excavated and roofed over.	Excavation	The act o
Decibel (dB)	A unit of measurement of loudness as detected by the human ear.	Expropriation	The acqu Expropria
Easements	Right to enter subject property for specific reasons.	Farside Stop	LRT surfa
Electromagnetic Interference	A disturbance that affects an electrical circuit due to either electromagnetic conduction or electromagnetic radiation emitted from an external source. The disturbance may interrupt, obstruct, or otherwise degrade or limit the effective	Fire Ventilation Shafts	Shafts where the surfar and static air supply

Toronto Transit Commission/City of Toronto EGLINTON CROSSTOWN LIGHT RAIL TRANSIT TRANSIT PROJECT ASSESSMENT Environmental Project Report

performance of the circuit.

located at street level used to evacuate passengers Light Rail Transit tunnels in the event of an ncy. It is typically located between two underground to provide passengers and staff an intermediate exit en stations are further than 762m apart to meet ned code and guideline requirements.

nent as defined in the Ontario Environmental nent Act means:

nd or water;

and animal life, including human life;

cial, economic and cultural conditions that influence f humans or a community;

uilding, structure, machine or other device or thing humans;

blid, liquid, gas, odour, heat, sound, vibration or resulting directly or indirectly from human activities;

art or combination of the foregoing and the tionships between any two or more of them, in or of

or negative effects on the environment caused by the tion or operation and maintenance of the Spadina Extension.

documenting the Transit Project Assessment , the conclusions reached, the impacts, the ed mitigation measures, and the future commitments nsit project.

rearing away of the surface by natural action of wind

or standard on which a judgement or decision may

of taking out material.

uisition of property in accordance with the ations Act of Ontario.

ace stop located beyond the intersection in the of travel.

which connect from the platform level of a station to ace used to balance air pressure within the tunnels ons and to provide for emergency exhaust and fresh y in case of an underground fire.

Floodplain	Normally dry land areas that are adjacent to a natural stream or watercourse and that are temporarily inundated during floods.	Main Entrance	Access an undergrout concentrat
GO Rail service	Commuter rail service which is operated by GO Transit.		elevator, a street leve
Grade Separation	Bridge separating two linear facilities at cross points. This is most commonly used in discussing crossings of roads and rail.	Mississauga Bus Rapid Transit (BRT)	Transit ser (busway) r
Grade	The profile of the centre of the Light Rail Transit running way structure or its rate of ascent or descent.		allowing bu roadway, v
Groundwater	Free water contained in the zone below the water table. The source of water in wells, springs, etc.		The buswa Parkway, a
Headway	The time separation between two vehicles, both travelling in the same direction; this is measured from the time the head	Mitigating Measures	Actions to effects cau
	of the first vehicles passes a fixed point to the time the second vehicle passes the same fixed point.	Mitigation	Action nec adverse ef
Higher Order Transit Corridor	Term used in the City of Toronto Official Plan, which refers to the existing or future transportation routes warranting improved transit priority and capacity. It includes busways, Light Rail Transit and subways.	Nearside Stop	LRT surfaction of
		Net Effects	Advantage enhancem
Landscaping	Enhancing the natural features of the land through the design and use of vegetation and other materials.	Noise Barrier	A barrier o noise level
Light Rail Transit Vehicles (LRV)	The Light Rail Transit vehicles will be of modern European- style design with a varying length of approximately 30 metres and a width of 2.54 metres. They will consist of two cars initially, with an opportunity to expand to three cars when ridership levels warrant. The rated capacity for a Light Rail Transit car is 130 passengers. Maximum operating speed is 70 km/hr, with average speed including stops of 22 km/h on the surface and 32 km/h underground. The vehicles will be powered by electrical power from overhead wires. Operations, both locomotive control and opening/closing of doors, will be controlled by on-board staff.	Noise	Defined as
		Official Plan	An Official governs de that has be Act.
		Off-Street	Transit ope
		On-Street	Transit ope
		Overburden	The mass
Light Rail Transit (LRT)	Electrically powered vehicles that operate on a partially exclusive right-of-way (reserved lanes) with traffic crossings at signalized intersections. These systems are capable of carrying medium to high volumes of people.	Parallel Stop	LRT surface
		Peak Hour	Defined pe three-hour
		Pillar Width	Horizontal
Level of service (LOS)	A qualitative measure describing operational conditions within a traffic stream and motorists' perceptions of those conditions	Platform Level	The area o use to ente
Volume to capacity ratio (v/c)	The ratio of traffic demand to available capacity. The V/C	Platform	The area o Light Rail
	not the physical geometry provides sufficient capacity for the traffic movement.	Pollution	Contamina harmful su

nd egress point of walk-in traffic along the and LRT. Main entrances form anchor points for the tion of people, uses and activities. It includes an an escalator, and stairs. The entrance connects the el to the station concourse level.

rvice travelling a two-lane bus-only roadway running across the City of Mississauga. The ill be grade separated from all crossing roads, uses to operate at up to 80 km/hr on their own with no other traffic, no signals and no stop sign. ay will run parallel to part of Highway 403, Eastgate and Eglinton Avenue.

reduce or eliminate any negative environmental used by the Eglinton Crosstown Light Rail Transit.

- cessary to prevent, change or remedy potential ffects.
- ce stop located before the intersection in the of travel.
- es/disadvantages remaining after mitigation or nent have been addressed.
- of earth, stone, concrete or wood to reduce the on abutting property.
- s any unwanted sound.
- I Plan is a long-term policy document, which evelopment and land use activities of a municipality een implemented in accordance with the Planning
- eration occurring off a road right-of-way.
- eration occurring within a road right-of-way.
- of soil that overlies a source of rock or gravel.
- ce stop located on either side of the intersection.
- eriod of maximum travel demand, generally the r period during a weekday.
- distance between two bored tunnels.
- of the Light Rail Transit station which passengers er and exit Light Rail Transit vehicles.
- of a station which passengers use to enter and exit Transit vehicles.
- ation of any component of the total environment by ubstances, sounds, smells or sights degrading or

	injurious to humans and other living organisms.		mostly at r
Portal	Approach entrances where the Eglinton Crosstown Light Rail Transit surface section transitions into the Light Rail Transit underground section.	Storage (pocket) Track	Also referr the two ma This allows
Profile	A longitudinal section of the Light Rail Transit runningway, station or stop.		be stored o disabled.
Proof-of-Payment	Method of payment where the transit rider must provide proof of payment for a transit ticket from automated vending machines or other document.	Storm Drain	A system o collect, cor usually a n
Right-of-way (ROW)	Land generally publicly owned, acquired for and devoted to transportation purposes, predominantly roads.	Streetscape	Visual app comprising lighting and
Riparian	A riparian zone or riparian area is the interface between land and stream.	Surface Transit Priority Notwork	landscapin
Route	General corridor linking the Pearson International Airport and the area at Eglinton Avenue and Martin Grove Road intersection.	Surface mansit Friority Network	the measu the City. T intersection
Secondary Entrance	Access and egress point of walk-in traffic along the underground. Secondary entrances will include only stairs.		lanes for b street park
	The entrance connects the street level to the station	Tail track	See Stora
Sediment	Fragmentary material that originates from weathering of rocks and is transported by suspended in or deposited by water.	Traction Power Substation	A facility lo DC current traction po
Signalized Intersections	Intersections with traffic signals controlling the movement of traffic.		circuit will the transit and step a
Slope	Any ground whose surface makes an angle with the plan of the horizon	Traffic Island	An island p
Soil Stabilization	Measures taken to eliminate or minimize the erosion of soil, or to improve its supporting capacity.		islands.
Soil	Sediment or other unconsolidated accumulation of solid	Traffic Lanes	Portion of of vehicles
	particles produced by the natural physical and chemical disintegration of rocks and which may or may not contain organic matter.	Traffic Volume	The numbe specific pe
Station Layout	A preliminary subway station concept which shows the general location of the station platform and concourse, pedestrian entrances and other surface facilities.	Transit Project Assessment Process	A decision advantage proceeding
Station	A passenger facility on the underground section of the Eglinton Crosstown LRT providing access to underground LRT trains. They are located at major roadway intersections along Eglinton Avenue. A station includes one main and two secondary entrances.		the new re Toronto Tr Regulation the Greate framework
Stops	A passenger facility on the surface section of the Eglinton Crosstown LRT located on the centre of the road right-of-way		objection p environme
MARCH 2010	Pag	e 329	

major roadway intersections.

red to tail track, it is a third track section between ain line tracks with turn outs at one or both ends. 's vehicles to be moved off of the mainline track to during lower demand periods or when vehicles are

of catch basins and underground pipes design to ncentrate and convey water to an outfall, which is nearby watercourse.

bearance of a street and its components, g both hard (e.g. concrete, paving stones, asphalt, ad furniture) and soft (e.g. grass, trees and shrubs) ng.

d in the City of Toronto Official Plan, which refers to ures intended to increase transit priority throughout These priority measures include priority signalized ons for streetcars and buses, reserved or dedicated buses and streetcars, and limiting or removing onking during part or all of the day.

ge (pocket) Track.

bocated at street level which converts AC current to at used to operate Light Rail Transit vehicles. A ower network, including transformer, switches and supply adequate power at an acceptable voltage to vehicles while minimizing stray current activities and touch voltage hazards.

provided in the roadway to separate or direct f traffic; includes both divisional and channelizing

the travelled way for the movement of a single line s.

er of vehicles passing a given point during a eriod of time.

n-making process used to determine the es and disadvantages to the environment of g with a proposed project. This process was by the Province of Ontario in June 2008, based on egulation named "Transit Projects and Greater ransportation Authority Undertakings, Ontario n 231/08" for undertaking transit-related projects in er Toronto Area. The TPAP Regulation provides a k for an accelerated focused consultation and process for completing the assessment of potential ental impacts of a transit project, so that decision-

	making can be completed within six months.	City of Toronto. 2006. City of Toronto's Official Plan.
Tunnel Boring Machine	Used for deep tunnelling where most of the tunnelling activity	City of Mississauga. 2003. City Plan.
	occurs below ground level.	City of Mississauga. 2009. Website - http://www.miss
Underground Walkway	A corridor for passengers to walk underground between surface facilities (such as commuter parking or bus terminals)	City of Toronto. 2001. Toronto Bike Plan.
	to the concourse level of the subway station.	City of Toronto. 2002. Toronto Pedestrian Charter.
Vibration	A temporal and spatial oscillation of displacement, velocity or acceleration in a solid medium.	Metrolinx. 2008. The Big Move: Transforming Transp
Water Table	The top of the zone of permanent soil saturation. The water table may rise or fall seasonally, or it may be drawn down by removal of water.	
Watershed	The divide separating one drainage basin from another. The divide separating one drainage basin from another.	
Tangent	A straight segment of road/rail free of horizontal or vertical curvature.	

REFERENCE LIST

A.J Chandler & Associates Ltd. 2010. Air Quality Assessment for the Proposed Eglinton Crosstown LRT.

Archeoworks Inc. 2009. Stage 2 Archaeological Assessment Report for: Proposed Eglinton Crosstown LRT.

Unterman McPhail Associates. 2010. Cultural Heritage Resource Assessment Report Built Heritage Resources & Cultural Heritage Landscapes for Eglinton Crosstown Light Rail Transit (LRT); Kennedy Road to Pearson International Airport.

Giffels Associated Limited/IBI Group. 2010. Drainage and Stormwater Management Assessment Report: Eglinton Crosstown LRT from Pearson International Airport to Kennedy Road.

Coffey Geotechnics Inc. 2010. Geotechnical Investigation, Environmental Assessment for Eglinton Crosstown Light Rail Transit.

Coffey Geotechnics Inc. 2010. Geotechnical Investigation, Environmental Assessment for Eglinton Crosstown Light Rail Transit – Airport Link.

Coffey Geotechnics Inc. 2010. Hydrogeological Study: Proposed Eglinton Crosstown Light Rail Transit and Airport Link.

Coffey Geotechnics Inc. 2010. Contamination Overview Study in Support of Environmental Assessment for Eglinton Crosstown Light Rail

J.E. Coulter Associates Limited. 2010. Noise and Vibration Impact Assessment: Proposed Eglinton Crosstown Light Rail Transit.

LGL Limited. 2010. Natural Heritage Assessment Report: Eglinton Crosstown LRT.

"TTC - Design and Supply of the Low Floor Light Rail Vehicle – Technical Specification" "Transportation Association of Canada (TAC) – Geometric Design Guidelines".

J:\24649_trnst_cityEA\10.0 Reports\March 2010 Final EPR Content\Draft EPR\Report\TTR_EPR_2010-03-09.docx\2010-03-09\SD

Toronto Transit Commission/City of Toronto EGLINTON CROSSTOWN LIGHT RAIL TRANSIT TRANSIT PROJECT ASSESSMENT Environmental Project Report

sissauga.ca/

portation in the Greater Toronto and Hamilton Area.